MBSPSU

Maharaja Bhupinder Singh Punjab Sports University

Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab
Established under Punjab Act No. 11 of 2019

REQUEST FOR PROPOSAL · TWO-COVER (QCBS) E-TENDER

Selection of an Agency for the Design, Development and Implementation of an Enterprise Resource Planning (ERP) System

Tender Reference No. **MBSPSU/PUR/ERP/2026/01**

SELECTION METHOD **QCBS · 70 : 30**	TENDER FEE **₹ 5,000**
EMD / BID SECURITY **₹ 96,000**	BID SUBMISSION CLOSES **T + 42, 15:00**

Bids are to be submitted **online only**, live on the Punjab e-Procurement Portal — **https://eproc.punjab.gov.in**

ISSUED BY
The Registrar, MBSPSU, Patiala

WEBSITE
https://mbspsu.ac.in

Confidential — This document is issued solely for the purpose of inviting proposals and must not be reproduced or used for any other purpose.

Important Dates

Tender Reference No. **MBSPSU/PUR/ERP/2026/01** · all times are Indian Standard Time (IST)
"T" denotes the date of publication of the NIT and this RFP on the Punjab e-Procurement Portal. All milestones are derived from T; days are calendar days, and where a computed date falls on a gazetted holiday in Punjab the next working day applies.

#	Event	Date & Time
1	Publication / Release of NIT + RFP — Punjab e-Procurement Portal, SPPP & University website	T :- 20/08/2026
2	Last date for written pre-bid queries (Annexure P format only)	T + 9, 05:00 PM (29/8/26)
3	Pre-registration for Pre-Bid Meeting attendance	T + 12, 01:00 PM (01/09/26)
4	Pre-Bid Meeting (hybrid — University campus / video-conference)	T + 13, 11:00 AM (02/09/26)
5	Issue of Corrigendum / consolidated replies to queries	on or about T + 20 (09/09/26)
6	Last date & time for online bid submission	T + 42, 03:00 PM (01/10/26)
7	Opening of Cover-1 (Fee / EMD + Technical)	T + 43, 03:30 PM (03/10/26)
8	Technical Presentation & Product Demonstration	T + 55 to T + 57 (as intimated) (14/10/26 — 16/10/26)
9	Opening of Cover-2 (Financial)	To be intimated to technically-qualified Bidders (to be intimated later on)
10	Award of Contract (LoA)	Within the bid-validity period (180 days)

TENDER FEE
₹ 5,000

EMD / BID SECURITY
₹ 96,000

ESTIMATED VALUE
₹ 48,00,000

SELECTION
QCBS · 70 : 30

The actual calendar dates corresponding to **T** are published with the NIT. Any change is made by corrigendum published on **https://eproc.punjab.gov.in** and **https://sppp.punjab.gov.in**; where a milestone is extended, **all dependent milestones are extended by the same interval**. The authoritative Fact Sheet is at Section 1; submission instructions are at Section 2.

Table of Contents

1 Introduction & Background

2 Instructions to Bidders

3 Scope of Work

4 Functional Requirements (SRS)

5 Technical Requirements

6 Project Management & Implementation

7 Pricing & Payment Terms

8 Bid Evaluation Criteria (QCBS)

9 Terms & Conditions of Contract

10 Annexures & Bid Forms

Sections 1–10 constitute the complete RFP. Bid forms and templates are provided in Section 10 (Annexures).

Section 1 — Introduction and Background

> **Note —** This Section is introductory and contextual. Where a value stated here (for example a date, a fee, or a threshold) also appears in a later Section of this Request for Proposal, the two shall be read as one and the same. In the event of any inconsistency, the order of precedence shall be: (i) any Corrigendum issued by the University; (ii) the Section of this RFP that specifically governs the subject matter (Section 2 for bidding procedure, Section 8 for evaluation, Section 9 for contract terms); and (iii) summaries, including the RFP Fact Sheet in this Section.

1.1 About MBSPSU

Maharaja Bhupinder Singh Punjab Sports University (hereinafter "MBSPSU", "the University", or "the Purchaser") is the **first specialised Sports University of the State of Punjab**. It was established on **29 August 2019** under the **Maharaja Bhupinder Singh Punjab Sports University Act, 2019 (Punjab Act No. 11 of 2019)**, and was recognised by the University Grants Commission (UGC) in September 2019. The University is a **residential and affiliating State (Government) University** dedicated to physical education, sports sciences, sports technology, sports management, coaching, and yoga.

The University is presently headed by its Vice-Chancellor, **Dr. Pushpinder Singh Gill**. The University is located at its campus on **Bhadson Road, Patiala – 147006, Punjab, adjoining the Rajiv Gandhi National Law University (RGNUL)**, where its 97-acre campus is being progressively developed and expanded. All references in this RFP to the University's address shall mean: **The Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab**.

1.1.1 University at a glance

Attribute	Detail
Full legal name	**Maharaja Bhupinder Singh Punjab Sports University (MBSPSU)**
Distinction	First specialised Sports University of the State of Punjab
Date of establishment	**29 August 2019**
Enabling statute	Maharaja Bhupinder Singh Punjab Sports University Act, 2019 (**Punjab Act No. 11 of 2019**)
Statutory recognition	University Grants Commission (UGC), September 2019
Type	Residential and affiliating State (Government) University
Vice-Chancellor	**Dr. Pushpinder Singh Gill**
Address	**The Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab**

Attribute	Detail
Campus	97-acre campus on Bhadson Road, Patiala (progressively under development and expansion)
Academic focus	Physical education, sports sciences, sports technology, sports management, coaching, yoga
Official website	https://mbspsu.ac.in

1.1.2 Academic programmes

The University offers, and continues to expand, a portfolio of undergraduate, postgraduate, and diploma programmes, including but not limited to the following:

Level	Representative programmes
Undergraduate	**BPES** (Bachelor of Physical Education and Sports), **BSS** (Bachelor of Sports Science), **B.P.Ed** (Bachelor of Physical Education), and associated BA / BSc streams
Postgraduate	**MPES / M.P.Ed** (Master of Physical Education and Sports), **M.Sc. Yoga**, and associated MSc streams
Diploma	**PG Diploma in Yoga** and allied certificate / diploma courses
Affiliation	The University affiliates colleges of physical education and sports across its jurisdiction

The University's academic base is expanding into new sports and coaching courses, and it discharges affiliating-university functions for affiliated institutions.

> **Note —** Because MBSPSU is a specialised Sports University, sports-domain capabilities — including athlete performance and talent management, sports facility and equipment management, sports nutrition and health / injury tracking, and tournament / event management — are **first-class, mandatory requirements** of the ERP, and not optional add-ons. The Bidder shall treat these as core to the solution throughout this RFP.

1.2 Purpose of this RFP

The Registrar, MBSPSU, Patiala (the "Tendering Authority"), for and on behalf of the University, invites sealed online proposals through this **Request for Proposal (RFP)** for the **Selection of an Agency for the Design, Development, and Implementation of an Enterprise Resource Planning (ERP) System at MBSPSU**, together with its subsequent Operations, Maintenance, Support, and Annual Maintenance Contract (AMC) for a period of five (5) years post-Go-Live.

The purpose of this RFP is to:

1. Solicit competitive technical and financial proposals from eligible and experienced agencies (each a "Bidder") capable of delivering an integrated, secure, scalable, and standards-compliant ERP solution for a multi-location, affiliating Sports University;
2. Establish, in a transparent and non-discriminatory manner, the **eligibility, technical, and commercial criteria** against which proposals shall be evaluated;

3. Select a single Successful Bidder (the "Successful Bidder" or "System Integrator") through a **Quality-and-Cost-Based Selection (QCBS)** process on a **Two-Cover (Two-Bid) online e-Tender** basis; and
4. Define the scope, deliverables, service levels, contractual terms, and payment terms that shall govern the resulting engagement.

The University is open to a suitable solution architecture, whether a **custom-developed** system, a configurable **Commercial Off-The-Shelf (COTS)** product, or a **Software-as-a-Service (SaaS)** offering, provided the solution fully satisfies the functional and technical requirements set out in Section 4 (Functional Requirements) and Section 5 (Technical Requirements) respectively.

> **Mandatory —** This RFP shall be read in its entirety, including all Sections, Annexures, and any Corrigendum issued on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in). Submission of a bid shall constitute the Bidder's unconditional acceptance of all terms, conditions, and requirements of this RFP.

1.3 Objectives of the ERP Initiative

The University intends, through this initiative, to replace fragmented, manual, and standalone systems with a single, unified, digitally-governed platform. The specific outcome objectives are:

1. **Single source of truth** — establish one authoritative, integrated data repository spanning academics, administration, finance, human resources, and sports operations, eliminating duplicate and inconsistent records across departments and campuses.
2. **End-to-end digitisation** — digitise the complete student lifecycle (enquiry, admission, registration, examination, results, certification, and alumni) and the complete employee lifecycle (recruitment to retirement) with configurable, auditable workflows.
3. **Sports-domain excellence** — provide purpose-built modules for athlete performance and talent management, sports facilities and equipment, sports nutrition / health and injury management, and tournament / event management, reflecting the University's specialised mandate.
4. **Financial control and transparency** — automate budgeting, fee collection, payments, procurement, inventory, payroll, and statutory compliance, with online collections via the **SBIePay** aggregator and full reconciliation.
5. **Multi-location, role-based access** — enable secure, role-based, single-sign-on access for stakeholders across the University campus and affiliated colleges, from web and mobile channels.
6. **Regulatory and statutory compliance** — support compliance and reporting obligations towards UGC, AICTE (where applicable), AISHE, NAAC, NBA, NIRF, NAD / DigiLocker, RTI, POSH, and the **Digital Personal Data Protection Act, 2023 (DPDP Act 2023)**.
7. **Data-driven governance** — deliver real-time dashboards, management information system (MIS) reports, and analytics to support institutional planning, accreditation, and decision-making by University leadership.
8. **Security, availability, and resilience** — ensure information security, data residency within India, high availability (**99.5% monthly uptime**, measured at the application layer), and robust disaster recovery aligned with defined RTO / RPO targets.
9. **Accessibility and inclusion** — provide an interface conforming to the Web Content Accessibility Guidelines (WCAG) and the Guidelines for Indian Government Websites (GIGW), ensuring equitable

access for all users, including persons with disabilities.

10. **Sustainable operations and low total cost of ownership** — ensure maintainability, interoperability through open APIs, knowledge transfer, and a predictable **5-year Total Cost of Ownership (TCO)**, with a clean exit and no vendor lock-in.

1.4 Present Situation and Need for the ERP

As a young University established in 2019, operating from its developing campus on Bhadson Road, Patiala, and serving a network of affiliated institutions, MBSPSU presently relies on a combination of **standalone spreadsheets, paper-based files and registers, and disconnected point solutions** for its academic and administrative functions. This fragmented environment gives rise to the following challenges, which this initiative is intended to resolve:

#	Present challenge	Consequence
1	Siloed spreadsheets and paper registers maintained department-wise	No single source of truth; duplicate, inconsistent, and un-reconciled data
2	Manual, offline workflows for admissions, fees, examinations, and approvals	Delays, transcription errors, weak audit trails, and limited accountability
3	Absence of integration between academic, finance, HR, and sports functions	Repeated data entry, reconciliation effort, and reporting gaps
4	Multi-location operations (University campus and affiliated colleges)	Fragmented, non-real-time information; no consolidated institutional view
5	Limited digital fee collection and reconciliation	Manual collection handling; reconciliation and refund difficulties
6	Sports-specific functions unsupported by generic tools	No structured athlete-performance, facility, nutrition, or tournament data
7	Manual compilation of statutory and accreditation returns (AISHE, NAAC, NIRF, etc.)	High effort, error-prone submissions, and compliance risk
8	Weak information-security posture and data-protection controls	Exposure under the DPDP Act 2023; no structured access control or audit
9	Absence of dashboards and analytics for leadership	Decisions made without timely, reliable, consolidated information

There is, accordingly, a clear and pressing need for an **integrated, secure, and scalable ERP system** that unifies these functions on a common platform, embeds sports-domain capabilities as first-class features, and positions the University for growth as it develops its campus and expands its academic footprint.

> **Important —** The description of the present situation is provided for the Bidder's general understanding only. The Bidder is expected to satisfy itself, including through the Pre-Bid Meeting, as to the actual operating environment. The University makes no representation that the present-state description is exhaustive.

1.5 Scope of this Document

This RFP document is organised into ten (10) Sections and a set of Annexures. Read together, they constitute the complete bidding document. The Bidder shall study all Sections carefully before submitting a bid.

Section	Title	What it covers (one-line pointer)
Section 1	Introduction and Background	About the University, purpose, objectives, present situation, definitions, RFP Fact Sheet, and disclaimer (this Section)
Section 2	Instructions to Bidders	General instructions, **Pre-Qualification / Eligibility Criteria**, tender fee and EMD, Two-Cover online submission on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in), pre-bid, amendments, validity, opening, and rejection
Section 3	Scope of Work	Scope overview, objectives, solution approaches (Custom / COTS / SaaS), deliverables, out-of-scope items, system context, and ownership
Section 4	Functional Requirements	The functional Software Requirements Specification (SRS) — all module suites with numbered, testable requirements and workflows
Section 5	Technical Requirements	The technical SRS — architecture, hosting / data residency, security and compliance (CERT-In, DPDP Act 2023), integrations including **SBIePay**, performance, and accessibility
Section 6	Project Management and Implementation	Methodology, phases, timeline, team, training, change management, SLA, support, and transition / exit
Section 7	Pricing and Payment Terms	Commercial-bid instructions, **Bill of Quantities (BOQ)** format, TCO definition, payment milestones, taxes, and penalties
Section 8	Evaluation Criteria	**QCBS methodology**, stage flow, Technical Evaluation Matrix (100 marks), demonstration scoring, and financial / composite formulae
Section 9	Terms and Conditions	General and Special Conditions of Contract — award, PBG, IPR / escrow, confidentiality, warranty, indemnity, force majeure, termination, exit, and dispute resolution
Section 10	Annexures and Forms	Prescribed bid forms and formats (Annexures A–Q), including covering letter, compliance sheets, BOQ / Financial Bid format, and mandatory undertakings

1.6 Definitions and Abbreviations

For the purposes of this RFP, unless the context otherwise requires, the following terms and abbreviations shall carry the meanings assigned to them below. Words in the singular include the plural and vice versa;

references to statutes include any statutory modification or re-enactment thereof.

#	Term / Abbreviation	Meaning / Expansion
1	**RFP**	Request for Proposal — this bidding document, including all Sections, Annexures, and Corrigenda
2	**ERP**	Enterprise Resource Planning — the integrated system to be designed, developed, and implemented under this RFP
3	**SI**	System Integrator — the Successful Bidder responsible for delivery, integration, and support of the solution
4	**COTS**	Commercial Off-The-Shelf — a pre-built, licensable software product configurable to the University's needs
5	**SaaS**	Software-as-a-Service — a subscription-based, cloud-hosted software delivery model
6	**QCBS**	Quality-and-Cost-Based Selection — the evaluation method combining technical and financial scores in a 70:30 ratio
7	**L1**	Lowest evaluated financial bid — the lowest quoted / evaluated price among responsive bids
8	**EMD**	Earnest Money Deposit — the bid security furnished by a Bidder along with its bid
9	**PBG**	Performance Bank Guarantee — security furnished by the Successful Bidder for due performance of the contract
10	**BOQ**	Bill of Quantities — the itemised financial bid format submitted in Cover-2
11	**TCO**	Total Cost of Ownership — the aggregate 5-year cost basis used for financial evaluation
12	**SLA**	Service Level Agreement — the measurable service-performance standards and associated penalties
13	**AMC**	Annual Maintenance Contract — the post-Go-Live maintenance and support arrangement
14	**O&M**	Operations and Maintenance — running, supporting, and maintaining the system after Go-Live
15	**UAT**	User Acceptance Testing — testing by University users to accept the delivered system
16	**SIT**	System Integration Testing — testing of integrated modules and interfaces
17	**FAT**	Final Acceptance Test — the final acceptance milestone marking exit of hypercare
18	**BBP**	Business Blueprint — the detailed as-configured process and solution design document
19	**SRS**	Software Requirements Specification — the functional and technical requirement baseline
21	**CERT-In**	Indian Computer Emergency Response Team — the national agency for cybersecurity, under MeitY
22	**DPDP Act 2023**	Digital Personal Data Protection Act, 2023 — India's personal data protection law
23	**MeitY**	Ministry of Electronics and Information Technology, Government of India

#	Term / Abbreviation	Meaning / Expansion
24	**Portal**	The **Punjab e-Procurement Portal, https://eproc.punjab.gov.in**, on which this RFP is hosted and administered and on which bids are submitted and opened. The University website (https://mbspsu.ac.in) carries a **notification only** and is not a bidding platform or a source of tender documents
25	**LoA**	Letter of Award — the University's formal communication awarding the contract
26	**LD**	Liquidated Damages — pre-agreed damages for delay in milestone completion
27	**MSME**	Micro, Small and Medium Enterprises — as defined under the MSMED Act, 2006 and notifications thereunder
28	**OEM**	Original Equipment Manufacturer — the product owner / manufacturer of any proposed software
29	**MAF**	Manufacturer's Authorisation Form — OEM authorisation to the Bidder to offer its product
30	**PoA**	Power of Attorney — authorisation empowering a signatory to bind the Bidder
31	**SIS**	Student Information System — the student-lifecycle component of the ERP
32	**LMS**	Learning Management System — the teaching-learning and content component
33	**HRMS**	Human Resource Management System — the employee-lifecycle and payroll component
34	**CRM**	Customer / Constituent Relationship Management — enquiry, admissions, and outreach management
35	**CMS**	Content Management System — management of website / portal content
36	**NAD**	National Academic Depository — digital repository of academic awards
37	**DigiLocker**	Government of India platform for issuance and verification of digital documents
38	**AISHE**	All India Survey on Higher Education — annual Ministry of Education data-collection exercise
39	**NAAC**	National Assessment and Accreditation Council
40	**NBA**	National Board of Accreditation
41	**NIRF**	National Institutional Ranking Framework
42	**UGC**	University Grants Commission
43	**AICTE**	All India Council for Technical Education
44	**POSH**	The Sexual Harassment of Women at Workplace (Prevention, Prohibition and Redressal) Act, 2013
45	**ICC**	Internal Complaints Committee — constituted under the POSH Act
46	**SGRC**	Student Grievance Redressal Committee
47	**RTI**	Right to Information — under the Right to Information Act, 2005

#	Term / Abbreviation	Meaning / Expansion
48	**RBAC**	Role-Based Access Control — access governed by user roles and privileges
49	**MFA**	Multi-Factor Authentication — authentication using two or more independent factors
50	**SSO**	Single Sign-On — unified authentication across the ERP modules
51	**API**	Application Programming Interface — a defined interface for system-to-system integration
52	**HA**	High Availability — architecture designed to minimise service downtime
53	**DR**	Disaster Recovery — capability to restore service after a disruptive event
54	**RTO**	Recovery Time Objective — maximum acceptable time to restore service after disruption
55	**RPO**	Recovery Point Objective — maximum acceptable data loss measured in time
56	**WCAG**	Web Content Accessibility Guidelines
57	**GIGW**	Guidelines for Indian Government Websites
58	**SBIePay**	State Bank of India ePay — the payment aggregator for online fee collection
59	**DVP**	Delivery-versus-Payment — the settlement model applicable to SBIePay transactions
60	**MSE**	Micro and Small Enterprises — micro and small (not medium) enterprises as defined under the MSMED Act, 2006; the public-procurement benefits under the Public Procurement Policy for MSEs Order, 2012 apply to MSEs only
61	**Udyam**	Udyam Registration — the Government of India online registration of MSMEs under the MSMED Act, 2006 (formerly Udyog Aadhaar)
62	**DPIIT**	Department for Promotion of Industry and Internal Trade, Government of India — the authority that recognises Startups for public-procurement and other benefits
63	**BSD**	Bid Security Declaration — the declaration furnished in lieu of the EMD by Bidders exempted under Clause 2.2A of Section 2
64	**GFR**	General Financial Rules, 2017 (as amended) — Government of India financial rules referenced for procurement norms
65	**PTPP Act**	Punjab Transparency in Public Procurement Act, 2019 (Punjab Act No. 12 of 2019), together with the rules made thereunder — the governing State procurement law for this RFP
66	**The University / Purchaser**	Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Bhadson Road, Patiala – 147006
67	**Tendering Authority**	The Registrar, MBSPSU, Patiala, issuing this RFP for and on behalf of the University
68	**Bidder**	Any legal entity submitting a proposal in response to this RFP
69	**Successful Bidder**	The Bidder selected for award of contract (also the System Integrator)

#	Term / Abbreviation	Meaning / Expansion
70	**Go-Live**	The date on which the ERP is placed into productive use for the University

> **Note —** The above list is not exhaustive. Terms defined elsewhere in this RFP (for example, in Section 5 (Technical Requirements) or Section 9 (Terms and Conditions)) shall carry the meaning assigned to them in the relevant Section for the purposes of that Section.

1.7 RFP Fact Sheet

The following Fact Sheet consolidates the principal canonical parameters of this RFP. It is provided for the Bidder's convenience; it does not override the detailed provisions of the respective Sections, which shall govern in the event of any inconsistency.

1.7.1 Key parameters

Key	Value
RFP Title	Request for Proposal (RFP) for the Selection of an Agency for Design, Development, and Implementation of an Enterprise Resource Planning (ERP) System at MBSPSU
Tender Reference No.	**MBSPSU/PUR/ERP/2026/01**
Issued by	**The Registrar, MBSPSU, Patiala** (the "Tendering Authority"), for and on behalf of the University
University address	**The Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab**
Publication & submission	**Live on the Punjab e-Procurement Portal — https://eproc.punjab.gov.in** (sole platform for tender documents, corrigenda and bid submission / opening). NIT / RFP / corrigenda / award additionally published on the **State Public Procurement Portal (https://sppp.punjab.gov.in)** under ss. 28(5) and 43 of the PTPP Act, and the NIT in at least one newspaper (Clause 2.6A). The **University website (https://mbspsu.ac.in) carries a notification only**
Bid authentication	Registered Portal account + **OTP** at final submission (IT Act, 2000 ss. 4/10A/11) together with documents signed & stamped by the authorised signatory (Clauses 2.5.3, 2.6A)
Bid type	**Online, Two-Cover (Two-Bid) e-Tender**
Estimated value of procurement	**₹48,00,000 (Rupees Forty-Eight Lakh only)** — indicative 5-year TCO excluding GST, as approved by the competent authority and as published in the NIT on the Punjab e-Procurement Portal
Selection method	**Quality-and-Cost-Based Selection (QCBS)**
QCBS weightage	**Technical 70% : Financial 30%**

Key	Value
Minimum technical qualifying score	**70 out of 100 marks**
Tender Document Fee (non-refundable)	**₹5,000** (online) — **exempt** for MSEs (valid Udyam) and DPIIT-recognised Startups, per Clause 2.2A of Section 2
Earnest Money Deposit (EMD) / Bid Security	**₹96,000** (Rupees Ninety-Six Thousand only) (within the 2% ceiling on the estimated value of procurement) — online / Bank Guarantee from a scheduled bank; **exempt** for MSEs (valid Udyam) and DPIIT-recognised Startups against a Bid Security Declaration, per Clause 2.2A of Section 2
MSE / Startup relaxations	Relaxed turnover, prior-experience and manpower norms for MSEs (Udyam) and DPIIT-recognised Startups — refer **Clause 2.2A of Section 2**
Performance Bank Guarantee (PBG)	**5% of total contract value** — by Bank Guarantee (valid for the full contract term plus a 3-month claim period) **or account-payee Demand Draft** (Clause 9.3)
Bid validity	**180 days** from the last date of bid submission
Contract term	**Implementation phase (T0 → Go-Live, up to 9 months) + 5 (five) years** post-Go-Live Operations, Maintenance, Support and AMC
Financial evaluation basis	**5-year Total Cost of Ownership (TCO)** derived from the BOQ
Bid signing	Every page of the bid signed and stamped by the **authorised signatory**, supported by a Power of Attorney / Board Resolution (Annexure N)
Jurisdiction	Courts at **Patiala, Punjab**; arbitration under the Arbitration and Conciliation Act, 1996, seat at Patiala
Liquidated Damages	**0.5% of delayed milestone value per week**, subject to a maximum of **10%** of contract value
Uptime SLA	**99.5%** monthly, measured at the application layer

1.7.2 Key dates — the "T" schedule

"T" denotes the date of publication of the NIT and this RFP on the Punjab e-Procurement Portal. All milestones are derived from T. Days are **calendar days**; where a computed date falls on a gazetted holiday in Punjab, the next working day applies. Where any milestone is extended by Corrigendum, **all dependent milestones are extended by the same interval**.

#	Event	Formula	Date and time (IST)
1	Publication / release of NIT + RFP	**T**	*(as published)*
2	Last date for written pre-bid queries (Annexure P format only)	**T + 9**, 05:00 PM	*(as published)*
3	Pre-registration for Pre-Bid Meeting attendance	**T + 12**, 01:00 PM	*(as published)*

#	Event	Formula	Date and time (IST)
4	**Pre-Bid Meeting** (hybrid — University campus / VC)	**T + 13**, 11:00 AM	*(as published)*
5	Issue of Corrigendum / consolidated replies to queries	on or about **T + 20**	*(as published)*
6	**Last date and time for online bid submission**	**T + 42**, 03:00 PM	*(as published)*
7	Opening of Cover-1 (Fee / EMD + Technical)	**T + 43**, 03:30 PM	*(as published)*
8	Technical Presentation and Product Demonstration	**T + 55** to **T + 57**	*(as intimated)*
9	Opening of Cover-2 (Financial)	To be intimated to technically-qualified Bidders	—
10	Award of Contract (LoA)	Within the bid-validity period (180 days)	—

> **Important —** All dates and times are **indicative** and refer to Indian Standard Time (IST). The University reserves the right to modify any date or the schedule by issuing a Corrigendum on the Punjab e-Procurement Portal and the State Public Procurement Portal. Bidders are advised to monitor **https://eproc.punjab.gov.in** (the authoritative source) and **https://sppp.punjab.gov.in** regularly. No separate individual intimation shall be issued.

1.8 Disclaimer

1. This RFP is neither an agreement nor an offer by the University or the Tendering Authority to the prospective Bidders or any other person. The purpose of this RFP is solely to provide interested parties with information that may assist them in the formulation and submission of their proposals. This RFP does not constitute, and shall not be construed as, any obligation, commitment, inducement, representation, or warranty on the part of the University.
2. The information contained in this RFP, and any information subsequently provided to Bidders whether verbally or in documentary form, is provided **in good faith** by or on behalf of the University, on the terms and conditions set out in this RFP and subject to the reservations stated herein. Such information is not intended to be exhaustive, and interested parties are required to make their own enquiries, assumptions, interpretations, and independent assessments.
3. The University, the Tendering Authority, and their respective officers, employees, advisers, and representatives make **no representation or warranty, express or implied**, and shall incur **no liability whatsoever** under any law, statute, rules, or regulations as to the accuracy, reliability, adequacy, or completeness of any information, statement, or assumption contained in, or otherwise made available in connection with, this RFP.
4. The University may, in its discretion — **for reasons to be recorded in writing, and communicated and published to the extent required by the Punjab Transparency in Public Procurement Act, 2019** — and without incurring any liability, at any time: (a) amend, modify, supplement, update, or issue Corrigenda

to this RFP; (b) extend the time or vary the schedule for submission of bids; (c) accept or reject any or all bids, in whole or in part; (d) withdraw, suspend, annul, or cancel this RFP or the entire procurement process; or (e) not proceed with the award of any contract. Subject to the remedies available under the Punjab Transparency in Public Procurement Act, 2019, no Bidder shall have any other claim, right, or remedy against the University arising from any such action.

5. This RFP and the information contained herein are subject to updates, amendments, clarifications, and revisions. The University reserves the right to change any terms and conditions of this RFP at any time prior to the last date of bid submission by way of a Corrigendum published on the University website / online tender portal, which shall form an integral part of this RFP.
6. The Bidder shall bear **all costs and expenses** associated with, or incidental to, the preparation and submission of its bid, participation in the Pre-Bid Meeting, technical presentations, product demonstrations, and any subsequent negotiations or due-diligence process. The University shall **in no case be responsible or liable** for any such costs, expenses, or losses, regardless of the conduct or outcome of the bidding process.
7. Nothing in this RFP is intended to create, and shall not be construed as creating, any binding obligation, contractual relationship, agency, partnership, or joint venture between the University and any Bidder, unless and until a formal written contract is executed between the University and the Successful Bidder.
8. By downloading, accessing, or responding to this RFP, each Bidder shall be deemed to have **unconditionally accepted** the terms of this Disclaimer and of the RFP in their entirety, and to have waived any and all claims in respect thereof. Any and all disputes arising in connection with this RFP shall be subject to the exclusive jurisdiction of the competent **courts at Patiala, Punjab**.

> **Reference —** The provisions of this Disclaimer are supplemented by, and shall be read together with, the reservations of the University set out in Section 2 (Instructions to Bidders) and the General and Special Conditions of Contract in Section 9 (Terms and Conditions).

Section 2 — Instructions to Bidders

This Section sets out the instructions, conditions and procedures governing the preparation, submission, opening and evaluation of bids in response to the **Request for Proposal (RFP) for the Selection of an Agency for Design, Development, and Implementation of an Enterprise Resource Planning (ERP) System at MBSPSU** (Tender Reference No. **MBSPSU/PUR/ERP/2026/01**), issued by **The Registrar, Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala** (the "Tendering Authority"), for and on behalf of the University. These instructions form an integral and binding part of the RFP. In the event of any conflict between these Instructions to Bidders and any other Section of this RFP on a matter of bidding procedure, this Section shall prevail on that procedural matter.

> **Mandatory — where this tender lives.** This tender is hosted **live on the Punjab e-Procurement Portal, https://eproc.punjab.gov.in** (the "Portal"), which is the **sole platform** for downloading the RFP and its Annexures, for all corrigenda, clarifications and pre-bid replies, and for **submission and opening of bids**. The NIT and the RFP are additionally published on the **State Public Procurement Portal, https://sppp.punjab.gov.in**, in discharge of Sections 28(5) and 43 of the PTPP Act, 2019. The **University website, https://mbspsu.ac.in, carries a notification of the tender only** — it is **not** a bidding platform, **not** a source of tender documents, and **not** a channel for submission. **In the event of any difference between the documents on the Portal and anything appearing on the University website, the version on the Portal shall prevail.** All bids shall be submitted online on the Portal only; no offline, physical, e-mail, facsimile or courier submission shall be accepted under any circumstance.

Section at a glance

Clause	Subject
2.1	General instructions & bidder responsibility
2.2	Pre-Qualification / Eligibility Criteria
2.2A	Relaxations & exemptions for MSEs and DPIIT-recognised Startups
2.3	Cost of bidding, Tender Document Fee & EMD
2.4	Two-Cover (Two-Bid) System
2.5	Preparation of bids
2.6	Online submission on the Punjab e-Procurement Portal
2.6A	Publication on the SPPP; authentication & Portal integrity
2.7	Pre-bid meeting & clarifications
2.8	Amendment of RFP / corrigenda
2.9	Bid validity & extension
2.10	Modification & withdrawal of bids

Clause	Subject
2.11	Bid opening
2.12	University's right to accept / reject / cancel
2.13	Fraud, corrupt & collusive practices; conflict of interest
2.14	Evaluation overview
2.15	Grievance redressal & appeals under the PTPP Act, 2019

The indicative schedule for this procurement is set out below. All dates are indicative and are subject to change by corrigendum published on the portal; the RFP Fact Sheet in Section 1 (Introduction & Background) and any corrigendum shall govern.

#	Event	Date & Time
1	Publication / Release of NIT + RFP	**T**
2	Last date for written pre-bid queries (Annexure P format only)	**T + 9**, 05:00 PM
3	Pre-registration for Pre-Bid Meeting attendance	**T + 12**, 01:00 PM
4	**Pre-Bid Meeting** (hybrid — University campus / VC)	**T + 13**, 11:00 AM
5	Issue of Corrigendum / consolidated replies to queries	on or about **T + 20**
6	**Last date & time for online bid submission**	**T + 42**, 03:00 PM
7	Opening of Cover-1 (Fee/EMD + Technical)	**T + 43**, 03:30 PM
8	Technical Presentation & Product Demonstration	**T + 55** to **T + 57** (as intimated)
9	Opening of Cover-2 (Financial)	To be intimated to technically-qualified Bidders
10	Award of Contract (LoA)	Within the bid-validity period

2.1 General Instructions & Bidder Responsibility

2.1.1 The Bidder shall examine all instructions, forms, terms, conditions, specifications and Annexures in this RFP and in every corrigendum issued thereto. Failure to furnish all information required by the RFP, or submission of a bid that is not substantially responsive to the RFP in every material respect, shall be at the Bidder's risk and may result in rejection of the bid without any further reference to the Bidder.

2.1.2 By submitting a bid, the Bidder shall be deemed to have:

- read, understood and unconditionally accepted all terms, conditions, specifications and requirements of this RFP (including all corrigenda and pre-bid clarifications) without deviation or reservation;
- satisfied itself, at its own cost and responsibility, as to the correctness and sufficiency of its bid, including all local conditions, applicable laws, statutory levies and taxes, and all factors bearing on the execution of

the assignment;

- acknowledged that the University shall not be responsible for any assumption, interpretation or conclusion drawn by the Bidder from this RFP.

2.1.3 The Bidder shall bear sole responsibility for the accuracy, completeness, authenticity and legibility of every document, statement and representation submitted with its bid. All information submitted shall be treated as a binding representation and warranty by the Bidder.

2.1.4 No Bidder shall contact any officer or employee of the University on any matter relating to this RFP from the date of publication of the RFP to the date of award of contract, otherwise than through the channels expressly prescribed in Clause 2.7. Any effort by a Bidder to influence the University in the processing of bids or in an award decision may result in rejection of the Bidder's bid.

2.1.5 **Language of communication.** All communication between the Bidder and the University in connection with this RFP, whether before or after bid submission, shall be in English and in writing (through the portal or, where the portal so permits, by uploaded correspondence).

2.1.6 **One bid per Bidder.** Each Bidder shall submit only one bid. A Bidder that submits, or participates in, more than one bid shall cause all bids in which that Bidder has participated to be disqualified. **Consortium bids are not permitted.** An OEM–System Integrator (SI) back-to-back arrangement is permitted only where the primary Bidder is the SI and submits the bid in its own name, supported by a Manufacturer's Authorisation Form (MAF) / back-to-back MoU (refer to Section 10, Annexures & Forms).

> **Important —** The bid, all supporting documents and all correspondence shall be in the exact legal name of the Bidder. The entity that submits and signs the bid shall be the entity that executes the contract; substitution of the contracting entity after bid submission is not permitted.

2.1.7 **Governing procurement law.** This procurement is conducted under, and shall be construed in accordance with, the **Punjab Transparency in Public Procurement Act, 2019 (Punjab Act No. 12 of 2019)** and the rules made thereunder (the "PTPP Act"). The General Financial Rules, 2017, the Government of India procurement manuals, and CVC guidelines are applied as adopted benchmark norms to the extent the PTPP Act and rules are silent, and references to them in this RFP shall be read accordingly.

2.2 Pre-Qualification / Eligibility Criteria

Only Bidders that meet **each and every** pre-qualification (PQ) criterion set out in the table below, as on the last date of bid submission, and that submit the corresponding supporting documents in Cover-1, shall be considered for technical evaluation. The pre-qualification criteria are **mandatory and non-negotiable**; failure to meet any one criterion, or failure to furnish the specified supporting document, shall render the bid liable to outright rejection without technical evaluation.

#	Eligibility Criterion	Minimum Requirement	Supporting Document Required
1	**Legal Entity & Continuity of Operation**	The Bidder shall be a legal entity incorporated / registered in India under the Companies Act, 2013 / Limited Liability Partnership Act, 2008 / Indian Partnership Act, 1932, and shall have been in continuous operation for **at least 3 (three) years** as on the last date of bid submission. *For DPIIT-recognised Startups, the minimum-vintage condition stands waived (refer Clause 2.2A).*	Certificate of Incorporation / Registration; PAN; MoA & AoA / LLP or Partnership Deed; valid GST registration; DPIIT recognition certificate where the Startup waiver is claimed.
2	**Financial Turnover & Net Worth**	**Average Annual Turnover of ≥ ₹50 Lakh**, computed as the average of the last three audited financial years (**2022-23, 2023-24, 2024-25**), from IT / software development / ERP services, with **positive net worth** in the latest audited financial year. *For MSEs (valid Udyam) and DPIIT-recognised Startups: ≥ ₹25 Lakh (refer Clause 2.2A). Where the Bidder (including a DPIIT-recognised Startup availing the vintage waiver) has been in existence for fewer than three completed financial years, the average shall be computed over the audited financial years available since incorporation; CA-certified provisional accounts are permitted for a year whose statutory audit is not yet due.*	Audited Balance Sheets & Profit-and-Loss statements for the three FYs, together with a Chartered Accountant's certificate (with UDIN) certifying turnover (segregated for IT / ERP services) and net worth; Udyam / DPIIT certificate where the relaxation is claimed.
3	**Relevant Experience**	The Bidder shall have successfully implemented / commissioned ERP (or campus / university / institution-management) solutions in **≥ 2 institutions in the last 7 years**, of which **≥ 1 in a Government / Public University or Higher Education Institution**, with **at least one such order of value ≥ ₹20 Lakh**. *For MSEs (valid Udyam) and DPIIT-recognised Startups: relaxed to ≥ 1 successfully completed software implementation (ERP / SIS / portal / campus- or institution-management system) for any institutional client, with no minimum order value (refer Clause 2.2A).*	Copies of Work Orders / Purchase Orders / Contracts, together with corresponding client Completion / Go-Live / Satisfactory-Performance certificates; case-study format per Section 10.
4	**Quality Certifications**	The Bidder shall hold valid **ISO 9001:2015 (Quality Management)** and **ISO/IEC 27001:2022 (Information Security Management)** certifications as on the bid-submission date — these two admit **no relaxation** for any Bidder. The Bidder shall additionally hold a valid **ISO/IEC 20000-1:2018 (IT Service Management)** certification, **or**, in lieu of ISO/IEC 20000-1 only, demonstrate documented and auditable ITSM processes aligned to ISO/IEC 20000-1 together with a written undertaking to obtain the certification within **12 (twelve) months** of award.	Valid certificates from an accredited certification body, showing scope covering software development / IT services and validity as on the bid date. For the ISO/IEC 20000-1 equivalence route: clause-wise mapped ITSM policy / SOPs; at least six months of operating evidence (ticket / change / release logs, internal-audit report or third-party gap assessment); and the signed undertaking to obtain certification within 12 months of award.

#	Eligibility Criterion	Minimum Requirement	Supporting Document Required
5	**Not Blacklisted / Debarred**	The Bidder shall not be blacklisted, debarred, suspended or declared ineligible by any Central / State Government, Public Sector Undertaking, University, statutory body or agency in India as on the last date of bid submission.	Self-declaration / affidavit on ₹100 non-judicial stamp paper (or e-affidavit) duly notarised, in the format at Section 10 (Annexures & Forms).
6	**Statutory Registrations**	The Bidder shall possess a valid **GST registration** and a valid **PAN**.	GST Registration Certificate; PAN card / allotment letter.
7	**Technical Manpower**	The Bidder shall have a minimum of **10 (ten) technical professionals** on its rolls as on the bid-submission date. *For MSEs (valid Udyam) and DPIIT-recognised Startups: minimum 5 (five) technical professionals (refer Clause 2.2A).* In addition, every Bidder shall commit the key personnel specified in Section 6 (per Annexure H).	Self-certification signed by the authorised signatory, supported by PF / ESI records or equivalent statutory proof of employment; Annexure H (key-personnel commitment).
8	**Support Presence**	The Bidder shall have an existing office in India and shall commit to establishing / maintaining a support / project office within the State of Punjab (Patiala preferred) for the duration of the contract.	Proof of existing office (registration / ownership / lease / utility bill) and a signed written undertaking to establish / maintain a Punjab support office during the contract term.
9	**RFP Fee, EMD & Single-Bid Compliance**	The Bidder shall have downloaded the RFP and paid the non-refundable Tender Document Fee and the Earnest Money Deposit (EMD), **or claimed a valid exemption under Clause 2.2A**; shall submit a single bid per bidder; consortium bids are not permitted (OEM–SI back-to-back MoU permitted with the primary bidder as SI).	Proof of online payment of Tender Document Fee (₹5,000) and EMD (₹96,000) / Bank Guarantee — **or** Udyam / DPIIT certificate with Bid Security Declaration (exempt MSE / Startup Bidders); MAF / back-to-back MoU where applicable.

> **Reference —** Bidders shall complete and upload the **Pre-Qualification Compliance Sheet** (mapping each of the nine criteria above to the exact page number of the supporting document within Cover-1) in the format provided in Section 10 (Annexures & Forms).

Clause 2.2A — Relaxations and Exemptions for MSEs and DPIIT-recognised Startups

This procurement is governed by the **Punjab Transparency in Public Procurement Act, 2019** and the rules made thereunder. Within that framework, and by a reasoned decision of the competent authority recorded in the procurement file, the University extends the following relaxations and exemptions, adopting as benchmark norms: the **Public Procurement Policy for Micro and Small Enterprises (MSEs) Order, 2012** (as amended) issued under Section 11 of the MSMED Act, 2006 (tender-document and EMD exemptions for MSEs); **Rule 170 of the General Financial Rules (GFR), 2017** (bid-security exemption); **Rule 173(i) of the GFR, 2017 read with DoE OMs No. F.20/2/2014-PPD(Pt.) dated 25.07.2016 and 20.09.2016** (relaxation of prior-turnover and prior-experience norms — for Startups per the DoE OM dated 25.07.2016 read with GFR Rule 173(i), and for Micro and Small Enterprises per MoMSME Policy Circular No. 1(2)(1)/2016-MA dated

10.03.2016 read with the DoE OM dated 20.09.2016); the applicable **DPIIT notifications**; and the corresponding Government of Punjab industrial and procurement policy. The manpower relaxation and the extension of the tender-fee exemption to DPIIT-recognised Startups are facilitation measures adopted by the University under the same recorded decision; the turnover and experience relaxations rest on the instruments cited above. All relaxations are **subject to the express proviso of GFR Rule 173(i) that quality and technical specifications shall not be diluted**.

#	Parameter	Standard requirement (all Bidders)	MSE — valid Udyam (Micro or Small)	DPIIT-recognised Startup
1	Tender Document Fee (₹5,000)	Payable	**Exempt** — tender document provided free of cost per the MSE Order, 2012	**Exempt**
2	EMD / Bid Security (₹96,000)	Payable	**Exempt** — Bid Security Declaration (Annexure J.2) in lieu	**Exempt** — Bid Security Declaration (Annexure J.2) in lieu
3	Continuity of operation — PQ-1 (≥ 3 years)	≥ 3 years	≥ 3 years (no relaxation)	**Waived**
4	Average annual turnover — PQ-2 (≥ ₹50 Lakh)	≥ ₹50 Lakh	**≥ ₹25 Lakh** (50% relaxation) — computed over the available audited FYs where fewer than three exist (see PQ-2)	**≥ ₹25 Lakh** (50% relaxation) — computed over the available audited FYs where fewer than three exist (see PQ-2)
5	Prior experience — PQ-3	≥ 2 institutions, ≥ 1 Government/HEI, one order ≥ ₹20 Lakh	**≥ 1 successfully completed software implementation (ERP / SIS / portal / campus- or institution-management system) for any institutional client; no minimum order value**	Same as MSE
6	Technical manpower — PQ-7 (≥ 10 on rolls)	≥ 10	**≥ 5**	**≥ 5**
7	Quality certifications — PQ-4 (ISO 9001:2015, ISO/IEC 27001:2022, ISO/IEC 20000-1:2018)	ISO 9001:2015 & ISO/IEC 27001:2022 mandatory; ISO/IEC 20000-1:2018 or the equivalence route per PQ-4 (available to all Bidders)	No separate relaxation — PQ-4 applies equally to all Bidders	No separate relaxation — PQ-4 applies equally to all Bidders
8	Performance Bank Guarantee (5% of contract value, on award)	Payable	**No exemption**	**No exemption**

#	Parameter	Standard requirement (all Bidders)	MSE — valid Udyam (Micro or Small)	DPIIT-recognised Startup
9	Technical qualifying score (70/100), SRS compliance, SLAs and all delivery obligations	Apply in full	**No relaxation**	**No relaxation**

Conditions applicable to all relaxation / exemption claims:

1. The **Udyam Registration Certificate** shall be valid as on the last date of bid submission, shall be **in the name of the bidding entity itself** (not a parent, subsidiary or sister concern), and shall bear an NIC activity classification covering IT / software / computer-related services. Benefits under the MSE Order, 2012 apply to **Micro and Small enterprises only; Medium enterprises are not entitled** to these benefits.
2. The **DPIIT recognition certificate** shall be valid as on the last date of bid submission and shall be in the name of the bidding entity itself.
3. Every relaxation / exemption claim shall be made expressly in the **Pre-Qualification Compliance Sheet (Annexure C)**, with the supporting certificate enclosed in Cover-1. Claims not so made and supported shall be ignored, and the standard criteria shall apply.
4. The relaxations operate at the **pre-qualification stage only**. They confer no advantage, concession or separate treatment at the technical evaluation (Section 8) or financial evaluation stages, at which all Bidders compete on identical terms.
5. **Purchase / price preference:** the price-matching purchase preference contemplated under the MSE Order, 2012 is **not applied** to this procurement, for reasons recorded by the competent authority: (a) the assignment is a **single, indivisible System-Integrator contract** awarded on a composite quality-cost (QCBS) ranking, in which the L1-price-matching mechanism presupposed by the Order cannot operate; (b) no item reserved for MSEs under the Order forms part of this procurement; and (c) the Order binds Central Ministries, Departments and CPSEs and is applied by this University **by adoption**. Facilitation of MSEs is instead provided through the fee and EMD exemptions and the relaxed pre-qualification norms above. This position is recorded for the purposes of audit.
6. Any misdeclaration or misuse of an MSE / Startup claim shall attract the consequences at Clause 2.13 (rejection, EMD forfeiture / Bid Security Declaration sanction, and blacklisting).

> **Note —** Payment-gateway or banking transaction charges, if any, levied by the payment channel are governed by that channel's norms and are distinct from the University's Tender Document Fee.

2.3 Cost of Bidding, Tender Document Fee & Earnest Money Deposit (EMD)

2.3.1 **Cost of bidding.** The Bidder shall bear all costs associated with the preparation and submission of its bid, including the cost of preparing, signing and uploading documents, attending the pre-bid meeting, technical

presentations / product demonstrations, and any site visit. The University shall in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

2.3.2 **Tender Document Fee (non-refundable).** Each Bidder shall pay a **non-refundable Tender Document Fee of ₹5,000 (Rupees Five Thousand only)** online through the Portal's designated payment channel. Proof of payment shall be uploaded in Cover-1. **MSEs holding a valid Udyam registration and DPIIT-recognised Startups are exempt from the Tender Document Fee under Clause 2.2A**; such Bidders shall upload the relevant valid certificate in Cover-1 in lieu of proof of payment. A bid unaccompanied by valid proof of payment of the Tender Document Fee, or by a valid exemption certificate under Clause 2.2A, shall be summarily rejected.

2.3.3 **Earnest Money Deposit (EMD) / Bid Security.** Each Bidder shall furnish an **EMD of ₹96,000 (Rupees Ninety-Six Thousand only)**. The EMD shall be furnished through the Portal, either:

- as an **online payment** through the portal payment gateway; or
- as an unconditional and irrevocable **Bank Guarantee** issued by a scheduled commercial bank in India in favour of **The Registrar, MBSPSU, Patiala**, in the standard format of a scheduled commercial bank, containing all the particulars set out in Annexure J.1 of Section 10, valid for a period not less than **45 (forty-five) days beyond the bid validity period** specified in Clause 2.9.

2.3.4 **Mode of payment & proof.** All payments towards the Tender Document Fee and (where paid online) the EMD shall be effected **online** — through the Portal's payment gateway, or by NEFT / RTGS to the University's designated bank account notified on the Portal / in the NIT. Payment references / UTR numbers / challans shall be uploaded in Cover-1. No cash, and no cheque or demand draft submitted physically, shall be accepted.

2.3.5 **Validity of EMD.** The EMD shall remain valid for a period of not less than **45 (forty-five) days beyond the bid validity period** specified in Clause 2.9. Where the University extends the bid validity under Clause 2.9, the Bidder shall correspondingly extend the validity of its EMD / Bank Guarantee.

2.3.6 **MSE / Startup exemption via Bid Security Declaration.** A Bidder claiming exemption from the EMD as an MSE (valid Udyam — Micro or Small) or DPIIT-recognised Startup under Clause 2.2A shall, in lieu of the EMD, upload in Cover-1 a duly signed and stamped **Bid Security Declaration** in the prescribed format, undertaking that if the Bidder withdraws or modifies its bid during the period of validity, or commits any of the acts in Clause 2.3.7, the Bidder shall be **suspended from being eligible for bidding in any contract with the University for a period of one (1) year**. Failure to attach either the EMD or a valid Bid Security Declaration shall render the bid non-responsive.

2.3.7 **Forfeiture of EMD.** The EMD shall be **forfeited** (and, in the case of a Bid Security Declaration, the sanction in Clause 2.3.6 shall apply) if the Bidder:

- withdraws, modifies or impairs its bid during the period of bid validity specified in Clause 2.9 (or any extension thereof), otherwise than as permitted under Clause 2.10;
- is found to have engaged in any fraudulent, corrupt, collusive or coercive practice, or in any misrepresentation, as described in Clause 2.13;
- fails to accept the correction of arithmetical errors in its bid, where applicable; or
- having been declared the successful Bidder, fails within the stipulated time to: (a) accept the Letter of Award (LoA); (b) execute the contract agreement; or (c) furnish the Performance Bank Guarantee (PBG) of **5% of the total contract value** as required under Section 9 (Terms & Conditions).

2.3.8 **Refund of EMD.** The EMD shall bear no interest. Refund shall be made as follows:

Bidder category	Refund timing
Unsuccessful Bidders (technically disqualified)	After completion of technical evaluation and declaration of technically-qualified Bidders — and in any case within 30 days of the declaration of technically-qualified Bidders.
Unsuccessful Bidders (financially unsuccessful)	Upon completion of the financial evaluation and identification of H1 — and in any case not later than 30 days after award of contract or the expiry of bid validity, whichever is earlier.
Successful Bidder	After the successful Bidder executes the contract agreement and furnishes the Performance Bank Guarantee — within 30 days of acceptance of the Performance Bank Guarantee.

Refund of online-paid EMD shall be processed to the originating account through the portal / University finance mechanism. Where an EMD Bank Guarantee has been furnished, it shall be returned / discharged in accordance with the above timelines.

2.4 Two-Cover (Two-Bid) System

2.4.1 This is an **online Two-Cover (Two-Bid) e-Tender**. Each Bidder shall prepare and upload its bid in two separate electronic covers on the Portal, as defined below. Both covers shall be signed as per Clause 2.5.3 and submitted together, on or before the last date and time for bid submission.

Cover-1 — Technical Bid (including Fee & EMD proof and Pre-Qualification documents)

Cover-1 shall contain, and shall be strictly limited to:

- proof of online payment of the **Tender Document Fee (₹5,000)** — or the valid Udyam / DPIIT certificate for Bidders exempt under Clause 2.2A;
- proof of the **EMD (₹96,000)** — online payment reference / Bank Guarantee / **Bid Security Declaration** with Udyam / DPIIT certificate (for Bidders exempt under Clause 2.2A);
- the **Pre-Qualification / Eligibility documents** for all nine criteria in Clause 2.2 (including any relaxation claims under Clause 2.2A), indexed against the Pre-Qualification Compliance Sheet;
- the **Technical Proposal** — company profile, understanding of requirements, proposed solution and architecture, functional and technical compliance narrative, implementation methodology and project plan, team composition and CVs, case studies, and all Annexure forms required for the technical bid (refer to Section 10);
- the **Functional and Technical Compliance Sheets** (point-by-point compliance against Sections 4 and 5); and
- all covering letters, undertakings, authorisations and declarations required by this RFP, other than the priced BOQ.

Cover-2 — Financial Bid (Bill of Quantities only)

Cover-2 shall contain **only** the duly filled and signed **Bill of Quantities (BOQ) / Financial Bid** in the exact format prescribed in Section 7 (Pricing & Payment Terms) and Section 10 (Annexures & Forms), quoting the **5-year Total Cost of Ownership (TCO)**. Cover-2 shall contain no document other than the BOQ.

> **Important — Any price, rate, amount, financial figure, discount or costing information of any kind appearing anywhere in Cover-1 (the Technical Bid), whether directly or by implication, shall lead to OUTRIGHT REJECTION of the entire bid.** The financial quotation shall appear only in Cover-2 (the BOQ). Bidders shall scrupulously ensure that no financial information leaks into any document, annexure, brochure or compliance sheet placed in Cover-1.

2.4.2 The financial figures shall be quoted only in the BOQ template. Any commercial term, condition or assumption that has a bearing on price and that is stated only in Cover-1 (and not carried into the BOQ) shall be treated as having **no financial value** and shall not entitle the Bidder to any additional payment.

2.5 Preparation of Bids

2.5.1 **Language.** The bid, and all correspondence and documents relating to the bid, shall be in **English**. Supporting printed literature furnished in another language shall be accompanied by an English translation, which shall govern for interpretation.

2.5.2 **Currency.** All financial figures in the BOQ (Cover-2) shall be expressed in **Indian Rupees (INR / ₹)** only. Bids quoted in any other currency shall be rejected.

2.5.3 **Signing of the bid.** The complete bid — both Cover-1 and Cover-2 and every constituent document — shall be **signed and stamped on every page by the Bidder's authorised signatory**, and uploaded as clear, legible PDF scans on the Portal. Documents that are not so signed by the authorised signatory shall be treated as invalid.

2.5.4 **Page-numbering & indexing.** Every page of the bid shall be sequentially page-numbered. Each cover shall carry an **index / table of contents** cross-referencing every document to its page number, so that pre-qualification, technical and compliance items can be readily located and traced. The Pre-Qualification Compliance Sheet and the Functional / Technical Compliance Sheets shall reference exact page numbers.

2.5.5 **Authorised signatory.** The bid shall be signed by a person duly authorised to bind the Bidder, supported by a **Power of Attorney / Board Resolution** authorising such person (refer to Section 10). The same authorised signatory shall sign the bid and every constituent document.

2.5.6 **No conditional, ambiguous or incomplete bids.** The Bidder shall submit an unconditional bid. **Conditional, ambiguous, incomplete or non-committal bids, and bids that take exception to, qualify or deviate from the terms of this RFP, are liable to be rejected.** Overwriting, interlineation, correction or erasure shall be valid only if authenticated by the signature / initials of the authorised signatory (wet-ink, on the page, before scanning). The Bidder shall not alter the RFP text, forms or BOQ structure; only the designated fields shall be completed.

> **Mandatory —** The BOQ template (Cover-2) shall not be renamed, reformatted or restructured, and no rows or columns shall be added or deleted. The BOQ template shall not be structurally altered. The consequence of leaving a line item blank is governed by Section 7 (Clause P-07): a blank against a Part A / Part B line is read as ₹0.00 and binds the Bidder; **every Part C rate is mandatory to quote and is evaluated on the University's fixed notional quantities — a blank Part C rate is read as ₹0.00 per man-day and binds the Bidder**; Part D (Phase-2 Optional) rows are optional to quote.

2.6 Online Submission on the Punjab e-Procurement Portal

All bids shall be submitted **online only** through the **Punjab e-Procurement Portal**, **https://eproc.punjab.gov.in** (the "Portal"). The step-by-step process is as follows:

1. **Register on the Portal.** Register the Bidder organisation on the Portal (**https://eproc.punjab.gov.in**), obtain/attach a valid Class-3 Digital Signature Certificate, furnish the organisation's and the authorised signatory's particulars and contact details, and complete profile verification.
2. **Download the RFP.** Download the complete RFP and all Annexures against Tender Reference No. **MBSPSU/PUR/ERP/2026/01 from the Portal**, and monitor **the Portal** for corrigenda and pre-bid replies. *The University website carries a notification only and is not a source of tender documents.*
3. **Prepare the two covers.** Prepare Cover-1 (Technical, with Fee & EMD proof and PQ documents) and Cover-2 (BOQ only), strictly as defined in Clause 2.4, page-numbered and indexed per Clause 2.5.
4. **Pay Fee & EMD online (or claim exemption).** Pay the Tender Document Fee (₹5,000) and the EMD (₹96,000) through the Portal's payment channel or by NEFT / RTGS per Clause 2.3.4 — or, for MSEs (valid Udyam) and DPIIT-recognised Startups exempt under Clause 2.2A, upload the relevant certificate together with the Bid Security Declaration — and retain the payment references / UTR for upload in Cover-1.
5. **Sign and scan each document.** Have every page of every document signed and stamped by the authorised signatory (Clause 2.5.3) and prepare clear, legible PDF scans for upload.
6. **Upload the covers.** Upload the signed documents into the respective covers on the Portal. The Portal shall hold the two covers separately; **Cover-2 (Financial) shall remain sealed and inaccessible until its scheduled opening** before the evaluation committee.
7. **Submit before the deadline.** Complete final submission on or before **T + 42, 03:00 PM**. The Portal shall not accept any bid after the deadline; the system time of the Portal shall be final and binding.
8. **Obtain system acknowledgement.** On successful submission, download and retain the **system-generated acknowledgement / bid-submission receipt** as proof of submission.

> **Important — No physical, offline, hard-copy, email, facsimile or courier bid shall be accepted under any circumstances.** Bidders are strongly advised to complete submission well in advance of the deadline; the University shall not be responsible for any delay, failure, congestion or interruption in internet connectivity, in the Bidder's systems, or in the Bidder's use of the portal. Bidders may contact the University IT Cell / Portal helpdesk (as notified on the University website) for technical assistance.

Clause 2.6A — Publication, Authentication and Portal Integrity

2.6A.1 **Publication.** The Notice Inviting Tender (NIT), this RFP, every corrigendum, the list of technically-qualified Bidders and the award decision shall be published **simultaneously** on: (i) the **Punjab e-Procurement Portal (https://eproc.punjab.gov.in)** — the authoritative source, on which the tender is hosted live; (ii) the **State Public Procurement Portal (https://sppp.punjab.gov.in)**, in compliance with Sections 28(5) and 43 of the PTPP Act, 2019, with the SPPP reference number quoted in the NIT; (iii) by way of **notification only**, on the **University website (https://mbspsu.ac.in)**, which carries an announcement directing Bidders to the Portal and is neither a source of tender documents nor a channel for submission; and

(iv) for the NIT, additionally in at least one newspaper in the manner prescribed under the Punjab Transparency in Public Procurement Rules, 2022. **In the event of any difference between the Portal and any other site, the Portal shall prevail.**

2.6A.2 **Recorded decision on the submission platform.** The competent authority has, by a reasoned decision recorded in the procurement file with reference to Section 27 of the PTPP Act, 2019, approved the conduct of the electronic bid-submission stage of this procurement on the **Punjab e-Procurement Portal (https://eproc.punjab.gov.in)**, with the safeguards set out in this Clause.

2.6A.3 **Authentication and attribution (IT Act, 2000).** Submission of the bid through the Bidder's **registered Portal account**, re-authenticated by a **one-time password (OTP)** sent to the Bidder's registered mobile number / e-mail at the point of final submission, shall constitute the Bidder's act of authentication. The bid so submitted is an electronic record **attributed to the Bidder as its originator** under Sections 4, 10A and 11 of the Information Technology Act, 2000, read with the signed and stamped documents (Clause 2.5.3) and the Power of Attorney (Annexure N).

2.6A.4 **Integrity of the covers.** The Portal shall: (a) compute and embed a **SHA-256 hash** of every uploaded file in the system-generated acknowledgement (Clause 2.6, step 8), which the Bidder shall retain; (b) **encrypt Cover-2 at rest (AES-256) upon upload**, with the decryption keys held in **dual custody of two designated officers** of the University, neither being a member of the Tender Evaluation Committee alone sufficient to decrypt; (c) permit decryption and opening of Cover-2 **only at the scheduled opening** before the committee, with **tamper-evident access logs** of every administrative and user action preserved for the full retention period for audit; and (d) undergo a **security audit by a CERT-In empanelled or other competent agency before the bid-opening stage**, with the report placed on the procurement file. The MeitY / STQC guidelines for the quality certification of e-procurement systems are adopted as benchmark norms for the Portal.

2.6A.5 **Portal clock and outage protocol.** The Portal clock shall be maintained in Indian Standard Time, synchronised to a national time source, and shall be final and binding. If the Portal is unavailable for more than **sixty (60) minutes in aggregate during the final twenty-four (24) hours** before the submission deadline, the deadline shall stand **extended by at least twenty-four (24) hours** by corrigendum published in the manner stated at Clause 2.6A.1. No bid or part of a bid shall be accepted by e-mail or any channel other than the Portal.

2.6A.6 **Non-repudiation.** By submitting its bid, the Bidder **adopts the scanned signatures on the uploaded documents as its own**, ratifies the submission made through its registered Portal account, and shall not deny the execution, authenticity or integrity of any document whose hash matches the system-generated acknowledgement.

2.7 Pre-Bid Queries, Pre-Bid Meeting & Clarifications

> **Note — the "T" schedule. "T" denotes the date of publication of the NIT and this RFP on the Punjab e-Procurement Portal.** All milestones below are derived from T. Days are calendar days; where a computed date falls on a gazetted holiday in Punjab, the next working day applies. The actual calendar dates corresponding to T are published in the Fact Sheet at Section 1 and on the Portal. Where any milestone is extended by corrigendum, all dependent milestones are extended by the same interval.

2.7.1 Pre-Bid Meeting

In accordance with Section 21(4) of the Punjab Transparency in Public Procurement Act, 2019 ("PTPP Act"), read with the Punjab Transparency in Public Procurement Rules, 2022 and Rule 173 of the General Financial Rules, 2017, the University shall hold a **Pre-Bid Meeting** as follows:

Particular	Details
Date and time	**T + 13, 11:00 AM IST**
Venue (physical)	Committee Room, Administrative Block, Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab
Video-conference option	The meeting shall be held in **hybrid mode**. The VC link and joining instructions shall be published on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in) at least **48 hours** before the meeting, and notified on the University website
Chair	The Registrar, MBSPSU, or an officer nominated by the Registrar, assisted by the Tender Evaluation Committee / technical officers as required

Attendance. Not more than **two (2) representatives per Bidder** shall be permitted to attend (whether physically, by video-conference, or one by each mode). Each representative shall carry — or, for VC attendance, e-mail in advance — an **authorisation letter on the Bidder's letterhead** signed by the authorised signatory, together with a government-issued photo identity document. Bidders intending to attend shall pre-register by e-mail to the address at 2.7.2 by **T + 12, 01:00 PM IST**, stating the names, designations and mode of attendance of their representatives. Attendance is **not mandatory**, but is strongly recommended.

2.7.2 Submission of pre-bid queries

Pursuant to Section 21(1) and (2) of the PTPP Act, any prospective Bidder may, in writing, seek clarifications on this RFP. All pre-bid queries must **reach the University not later than T + 9, 05:00 PM IST**. This is the period specified in the bidding document for seeking clarifications within the meaning of Section 21(2) of the PTPP Act.

Queries shall be submitted:

- **only** in the format at **Annexure P (Pre-Bid Query Format)** of Section 10 — the sole valid format for this procurement;
- in **editable** form (MS Word `.docx` or MS Excel `.xlsx`); scanned images and non-editable PDFs shall not be treated as valid submissions;
- by e-mail to **registrar@mbspsu.ac.in**, with the mandatory subject line **"Pre-Bid Queries — RFP No. MBSPSU/PUR/ERP/2026/01 — [Name of Bidder]"**;
- as **one consolidated file** per Bidder.

No price, rate or other commercial information shall be included in any query.

2.7.3 Responses, clarifications and corrigenda

(a) The University shall issue **consolidated written responses** to all queries received in time (and to such other queries as it may choose to answer), together with the minutes of the Pre-Bid Meeting and any resulting

Corrigendum, **on or about T + 20** — no less than **twenty-one (21) days** in advance of the bid-submission deadline at **T + 42, 03:00 PM IST** — so that all Bidders have sufficient time to take the clarifications into account, in conformity with Section 22(2) of the PTPP Act and Rule 173 of the GFR, 2017.

(b) All responses, minutes and corrigenda shall be published on:

(i) the **Punjab e-Procurement Portal — https://eproc.punjab.gov.in**; (ii) the **State Public Procurement Portal — https://sppp.punjab.gov.in** (Sections 28(5) and 43 of the PTPP Act); and (iii) the **University website — https://mbspsu.ac.in** (by way of notification only; the Portal version prevails).

(c) Responses shall be published **without identifying the Bidder that raised the query**. No individual responses shall be sent to any Bidder. Provided that the published responses, minutes and Corrigenda shall **additionally be intimated by e-mail / portal notification** to all Bidders who submitted queries under 2.7.2 or pre-registered under 2.7.1, without disclosing any querying Bidder's identity; such publication and intimation together constitute due notice under **Section 21(3) and (4)** of the PTPP Act.

(d) Queries received after the deadline, or not submitted in the Annexure P format, or containing commercial information, may not be entertained.

2.7.4 Binding effect

The minutes of the Pre-Bid Meeting, the responses to queries, and any resulting **corrigendum shall be binding on all Bidders** and shall be deemed to form part of this RFP, whether or not a Bidder attended the Pre-Bid Meeting.

> **Note —** Oral statements or clarifications given during the Pre-Bid Meeting shall have **no binding effect** unless and until confirmed in writing through minutes or a corrigendum published on the portals listed at 2.7.3(b).

2.7.5 Communication protocol

Save for (i) written queries under 2.7.2 and (ii) participation in the Pre-Bid Meeting under 2.7.1, Bidders shall not contact or seek to influence any officer, employee, committee member or adviser of the University in relation to this RFP, in line with Clause 2.1.4. Any attempt at canvassing or unauthorised contact shall render the bid liable to rejection, without prejudice to action under Clause 2.13 and Sections 26 and 56 of the PTPP Act.

Table 2.7-A — Pre-bid process schedule

#	Activity	Formula	Date & time	Mode / venue
1	Publication of NIT + RFP	**T**	*(per Fact Sheet)*	**Live on https://eproc.punjab.gov.in**; also published on https://sppp.punjab.gov.in and in ≥1 newspaper; notification on https://mbspsu.ac.in
2	Last date for receipt of pre-bid queries (Annexure P format only)	**T + 9**, 05:00 PM IST	*(per Fact Sheet)*	E-mail to registrar@mbspsu.ac.in

#	Activity	Formula	Date & time	Mode / venue
3	Pre-registration for Pre-Bid Meeting attendance	**T + 12**, 01:00 PM IST	*(per Fact Sheet)*	E-mail to registrar@mbspsu.ac.in
4	**Pre-Bid Meeting**	**T + 13**, 11:00 AM IST	*(per Fact Sheet)*	Hybrid — University campus, Patiala / VC link on portal
5	Publication of consolidated responses, minutes and Corrigendum (if any)	On or about **T + 20**	*(per Fact Sheet)*	Portals listed at 2.7.3(b)
6	Bid-submission deadline	**T + 42**, 03:00 PM IST	*(per Fact Sheet)*	eproc.punjab.gov.in

In case of any conflict between this table and the Fact Sheet at Section 1 as amended by Corrigendum, the latest Corrigendum shall prevail.

2.8 Amendment of RFP / Corrigenda

2.8.1 At any time prior to the last date for bid submission, the University may, for any reason — whether on its own initiative or in response to a clarification sought by a Bidder — **amend, modify, clarify or supplement the RFP by issuing a corrigendum / addendum** on the portal.

2.8.2 Every corrigendum shall be published on the **Punjab e-Procurement Portal (https://eproc.punjab.gov.in)** — the authoritative source — and on the **State Public Procurement Portal (https://sppp.punjab.gov.in)**, and shall be notified on the **University website (https://mbspsu.ac.in)**. Every corrigendum is **binding on all Bidders** and shall be deemed to form an integral part of the RFP. **Bidders are responsible for monitoring the Portal**; where a corrigendum on the Portal differs from anything appearing on the University website, **the Portal version shall prevail**.

2.8.3 To afford Bidders reasonable time to take a corrigendum into account in preparing their bids, the University may, at its sole discretion, **extend the last date for bid submission** and shall publish any such extension on the portal.

2.9 Bid Validity & Extension

2.9.1 Bids shall remain **valid for 180 (one hundred and eighty) days** from the last date for online bid submission. A bid valid for a shorter period shall be treated as non-responsive and rejected.

2.9.2 In exceptional circumstances, prior to the expiry of the bid validity period, the University may request Bidders to **extend the validity** of their bids for a specified additional period. The request and the responses shall be in writing (through the portal). A Bidder may refuse the request without forfeiture of its EMD. A Bidder

agreeing to the request shall not be permitted to modify its bid, but shall be required to **correspondingly extend the validity of its EMD / Bid Security** (refer to Clause 2.3.5).

2.10 Modification & Withdrawal of Bids

2.10.1 A Bidder may **modify, substitute or withdraw** its submitted bid at any time **prior to the last date and time for bid submission**, using the facilities provided on the Portal, provided the modification / substitution / withdrawal is completed within the deadline.

2.10.2 **No bid shall be modified, substituted or withdrawn after the deadline** for bid submission.

2.10.3 Withdrawal, modification or impairment of a bid during the interval between the deadline for bid submission and the expiry of the bid validity period (or any extension agreed under Clause 2.9) shall result in **forfeiture of the EMD** and, for exempt Bidders, the consequences under the Bid Security Declaration (refer to Clause 2.3.7).

2.11 Bid Opening

2.11.1 **Opening of Cover-1.** Cover-1 (Fee/EMD proof + Technical Bid) shall be opened online on the portal on **T + 43 at 03:30 PM**, or as otherwise notified through the portal, by the University's authorised committee. Only bids that are duly submitted, signed as per Clause 2.5.3 and accompanied by valid Tender Document Fee and EMD / Bid Security Declaration (or exemptions under Clause 2.2A) shall be taken up.

2.11.2 **Preliminary examination & pre-qualification.** The committee shall verify the Tender Document Fee, the EMD and the nine pre-qualification criteria (Clause 2.2). Bids that fail any pre-qualification criterion shall be rejected and shall not proceed to technical evaluation.

2.11.3 **Technical evaluation & demonstration.** Bids that pass pre-qualification shall be evaluated under the **QCBS Technical Evaluation Matrix (100 marks)** set out in Section 8 (Evaluation Criteria), including the **Technical Presentation & Product Demonstration** scheduled for **T + 55 to T + 57** (as intimated). Only Bidders scoring **≥ 70 out of 100** and clearing every pre-qualification condition shall be declared **technically qualified**.

2.11.4 **Opening of Cover-2.** Cover-2 (Financial / BOQ) shall be opened online **only for technically-qualified Bidders**, on a date and time **intimated to those Bidders** through the portal. The financial covers of Bidders that are not technically qualified shall remain unopened and sealed on the Portal.

2.11.5 **Composite evaluation & award.** The composite QCBS score shall be computed as **S = 0.70 × St + 0.30 × Sf** (Technical 70% : Financial 30%), and the Bidder with the highest composite score (**H1**) shall be recommended for award. The detailed methodology, financial formula and worked example are set out in Section 8 (Evaluation Criteria).

> **Reference —** Bidders shall note the demonstration window of **T + 55 to T + 57** and shall be prepared to demonstrate the proposed solution end-to-end. Non-participation in the scheduled technical presentation / product demonstration may result in the bid being treated as technically non-responsive.

2.12 University's Right to Accept / Reject / Cancel

2.12.1 Notwithstanding anything else contained in this RFP, the University reserves the right, at its discretion — **for reasons to be recorded in writing, and communicated and published to the extent required by the PTPP Act, 2019** — and without incurring any liability, to:

- accept or reject any bid, in whole or in part;
- annul the bidding process, or reject all bids, at any time prior to award of contract;
- vary the quantity, scope or timeline of the assignment;
- waive any minor informality, non-conformity or irregularity in a bid that does not constitute a material deviation and does not prejudice or affect the relative ranking of any Bidder; or
- hold negotiations only to the extent, with the bidder, and in the exceptional situations permitted under Section 40 of the PTPP Act, 2019 and the rules made thereunder.

2.12.2 No Bidder shall have any claim, cause of action, or right to compensation, damages or costs against the University arising out of the exercise of any of the rights in this Clause, or the rejection of any bid, or the annulment of the bidding process.

2.13 Fraud, Corrupt & Collusive Practices; Conflict of Interest; Consequences

2.13.1 The University requires that Bidders, and their agents, sub-contractors, personnel and representatives, observe the **highest standards of ethics** during the procurement and execution of the contract. For the purposes of this Clause, the following definitions shall apply:

Term	Meaning
Corrupt practice	Offering, giving, receiving or soliciting, directly or indirectly, anything of value to influence the action of a public official in the procurement process or contract execution.
Fraudulent practice	Any act or omission, including a misrepresentation or concealment, that knowingly or recklessly misleads, or attempts to mislead, the University to obtain a financial or other benefit or to avoid an obligation.
Collusive practice	An arrangement between two or more Bidders (with or without the knowledge of the University) designed to establish prices at artificial, non-competitive levels or otherwise to deprive the University of the benefits of free and open competition.
Coercive practice	Impairing or harming, or threatening to impair or harm, directly or indirectly, any person or property to influence the participation of a party in the procurement process or the execution of a contract.

2.13.2 **Conflict of interest.** A Bidder shall not have a conflict of interest that adversely affects, or may reasonably be perceived to adversely affect, this procurement. A Bidder shall be disqualified if it, or any of its affiliates: (a) has been engaged by the University to provide consultancy that led to this RFP, in a manner that confers an unfair advantage; (b) submits more than one bid, whether directly or through affiliates; or (c) has an undisclosed business or family relationship with University personnel involved in the procurement. Bidders shall disclose any actual or potential conflict of interest in their bid.

2.13.3 **Consequences of misrepresentation / prohibited practices.** If, at any time before, during or after the award of contract, it is established that a Bidder has, directly or indirectly through an agent, engaged in any corrupt, fraudulent, collusive or coercive practice, has furnished any false, forged or misleading document or representation, or has an undisclosed conflict of interest, the University shall be entitled, without prejudice to any other right or remedy in law or under this RFP, to any or all of the following:

- reject the bid and **forfeit the EMD** (and invoke the Bid Security Declaration sanction, where applicable);
- terminate the contract (if awarded) and **encash the Performance Bank Guarantee**;
- recover from the Bidder all losses, damages and costs suffered by the University; and
- **blacklist / debar** the Bidder (and, where appropriate, its affiliates) from participating in the University's tenders **for a specified period not exceeding three (3) years**, after affording the Bidder a reasonable opportunity of being heard, in accordance with Sections 26 and 56 of the PTPP Act, 2019 and the rules made thereunder, and report the matter to the appropriate Government authority.

> **Mandatory —** Every Bidder shall submit the **Non-Blacklisting Affidavit** and the **Anti-Corruption, Anti-Collusion & Conflict-of-Interest Declaration** in the formats at Section 10 (Annexures & Forms). Submission of a bid shall constitute the Bidder's unconditional acceptance of the anti-fraud and conflict-of-interest provisions of this Clause.

2.14 Evaluation Overview

2.14.1 This is a **Quality-and-Cost-Based Selection (QCBS)** procurement with a weightage of **Technical 70% : Financial 30%**. Evaluation shall proceed in the following broad stages: (i) preliminary examination (Fee, EMD, responsiveness); (ii) pre-qualification against Clause 2.2; (iii) technical evaluation against the 100-mark matrix, including the product demonstration, with a **minimum qualifying score of 70 out of 100**; (iv) opening and evaluation of the financial bids (BOQ) of technically-qualified Bidders on the basis of the **5-year Total Cost of Ownership (TCO)**; and (v) computation of the composite score and identification of **H1** for award.

2.14.2 The financial score shall be computed as **Sf = (Lowest evaluated quote ÷ Bidder's quote) × 100**, and the composite score as **S = 0.70 × St + 0.30 × Sf** (where St is the raw technical score out of 100). The Bidder with the highest composite score shall be selected.

> **Note —** This Clause is only an overview. The **complete QCBS methodology, the Technical Evaluation Matrix with sub-criteria, demonstration scoring, the financial formula and a worked composite-score example** are set out in **Section 8 (Evaluation Criteria)**, which shall prevail in respect of all evaluation matters.

2.15 Grievance Redressal & Appeals (PTPP Act, 2019)

2.15.1 A Bidder aggrieved by any decision, action or omission of the Tendering Authority in this procurement may seek redressal in accordance with the **Punjab Transparency in Public Procurement Act, 2019** and the rules made thereunder.

2.15.2 **First Appellate Authority.** For the purposes of Section 49 of the PTPP Act, 2019, the officer designated to receive appeals is: **The Vice-Chancellor, The Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab**. Appeals shall be preferred within the period, in the manner, and subject to the conditions prescribed under the Act and rules; any further appeal shall lie as provided therein.

2.15.3 An appeal shall not automatically suspend the procurement process, except to the extent required by the Act or ordered by the appellate authority. Frivolous or vexatious appeals may attract the consequences prescribed under the Act.

> **Reference —** This Clause implements the mandatory appellate-officer disclosure under Section 49(3) of the PTPP Act, 2019. It operates in addition to, and not in derogation of, the University's rights under Clause 2.12.

End-to-End Two-Cover Bid Process — Publication to Award


Publication of NIT + RFP on the Punjab e-Procurement Portal - T
Download RFP / register on eproc.punjab.gov.in
Submit written pre-bid queries by T + 9
Pre-Bid Meeting - T + 13
Corrigendum / replies published - T + 20
Prepare & sign Cover-1 Technical and Cover-2 Financial
Pay Tender Fee + EMD or claim MSE / Startup exemption - upload covers - Portal holds Cover-2 sealed
Online bid submission before T + 42 03:00 PM / get acknowledgement
Open Cover-1 on the Portal - T + 43 03:30 PM
Verify Fee / EMD / Pre-Qualification criteria
Fails PQ
Passes PQ
Bid rejected - EMD refunded
Technical evaluation + Demonstration T + 55 to T + 57
Score below 70 of 100
Score 70 of 100 or above
Technically disqualified - Cover-2 not opened - EMD refunded
Technically qualified
Open Cover-2 BOQ of qualified bidders - as intimated
Compute S = 0.70 x St + 0.30 x Sf
Identify H1 - highest composite score
Award of Contract / LoA within bid validity

Section 3 — Scope of Work

3.1 Overview

This Section defines the complete Scope of Work (the "**Scope of Work**" or "**SoW**") to be delivered by the Bidder selected under this Request for Proposal, Tender Reference No. **MBSPSU/PUR/ERP/2026/01**, for the Design, Development, and Implementation of an Enterprise Resource Planning (ERP) System at **Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala** (the "University").

The selected Bidder (hereinafter also referred to as the "**Selected Agency**", "**System Integrator**", or "**SI**") shall assume **single-point, end-to-end turnkey responsibility** for the conception, delivery, commissioning, and sustained operation of a unified, web-based, mobile-enabled ERP platform covering the entire academic, administrative, financial, sports, and support functions of the University. Turnkey responsibility means that the SI shall deliver a fully functional, tested, integrated, secured, and operational system without recourse to the University for any activity, licence, tool, component, or resource that is reasonably necessary for the system to function as specified — save only for those items expressly enumerated as the University's responsibilities in Section 3.6.

The Scope of Work spans two contiguous phases, consistent with the canonical Contract term:

Phase	Description	Duration
Phase I — Implementation	Requirement study, solution design, development/configuration, integrations, data migration, testing, training, deployment, and Go-Live	**T0 → Go-Live, up to nine (9) months**
Phase II — Operations, Maintenance, Support & AMC	Post-Go-Live hosting support, corrective/adaptive/perfective maintenance, help-desk, upgrades, SLA-bound operations, and Annual Maintenance Contract (AMC)	**Five (5) years** post-Go-Live

The scope enumerated in this Section shall be read together with the Functional Requirements of Section 4 (Functional Requirements), the Technical Requirements of Section 5 (Technical Requirements), the delivery obligations of Section 6 (Project Management & Implementation), the commercials of Section 7 (Pricing & Payment Terms), and the contractual terms of Section 9 (Terms & Conditions). In the event of any apparent gap, the SI shall be deemed responsible for all activities necessary to achieve the stated objectives and a complete, working solution (the "**turnkey principle**").

> **Note —** This Section describes *what* is to be delivered and the boundary of responsibility. The detailed functional and technical specifications that the delivered solution must satisfy are set out in Section 4 (Functional Requirements) and Section 5 (Technical Requirements) respectively, and form part of this Scope of Work by reference.

3.2 Key Objectives

The University seeks, through this engagement, to replace fragmented, manual, and paper-based processes with a single, integrated, secure, and extensible digital platform. The solution proposed and delivered by the Bidder shall demonstrably achieve the following objectives, each of which is enforceable and shall inform the technical evaluation under Section 8 (Evaluation Criteria):

#	Objective	Description
O1	**Centralization / Single Source of Truth**	Consolidate all University data — students, athletes, applicants, faculty, coaches, staff, alumni, academics, sports, finance, and administration — into one authoritative, integrated data repository, eliminating data silos, duplicate entry, and reconciliation effort across departments.
O2	**Automation**	Automate manual, paper-based, and email-driven processes end-to-end — admissions, registration, examinations, fee collection, approvals, procurement, payroll, attendance, hostel, and sports operations — through configurable, rule-based digital workflows with auditable approval chains.
O3	**Transparency & Real-Time Reporting**	Provide role-based, real-time dashboards, drill-down analytics, and comprehensive statutory and management reporting to the University leadership, enabling data-driven decisions and complete traceability of every transaction and approval.
O4	**Superior User Experience**	Deliver an intuitive, modern, responsive, and accessible interface tailored to each user group — students/athletes, faculty/coaches, administrative staff, applicants, alumni, and University administration — usable across desktop and mobile with minimal training.
O5	**Extensibility & Scalability**	Ensure the platform is modular, API-first, and highly extensible so that new modules, programmes, campuses (including future expansion of the University campus), affiliated colleges, and functions can be added over the contract term and beyond without re-architecture.
O6	**Regulatory & Statutory Compliance**	Enable and sustain compliance with the reporting and data requirements of **UGC**, **NAAC** (accreditation / AQAR / SSR data), **NIRF** (ranking data submissions), **AISHE**, and applicable Government of India / Government of Punjab e-governance norms, including the Digital Personal Data Protection Act, 2023.
O7	**Sports-Domain Excellence**	Treat sports-specific capabilities — athlete performance and profile management, sports facility and equipment management, tournament and event management, sports nutrition and sports-medicine/health, coaching plans, and integration with wearables — as first-class, core requirements, in keeping with the University's status as the first specialised Sports University of Punjab.

> **Mandatory —** The Bidder shall, in its Technical Proposal, map its proposed solution against each objective O1–O7 and against the functional and technical requirements of Sections 4 and 5, and shall demonstrate compliance during the Technical Presentation & Product Demonstration (indicative dates **T + 55 to T + 57**, as intimated).

3.3 Solution Approaches Accepted

> **Mandatory — the University is neutral as to approach, but not as to the outcome.** The University shall accept a Custom Development, COTS or hosted / SaaS approach, or a well-justified hybrid. Whichever approach is adopted, the Contract **must** deliver the **uniform licence, intellectual-property and continuity end-state prescribed by Clause 9.5.6 of Section 9** — under which, after the Contract ends for any reason, the University can continue running the Solution indefinitely without further payment, holds or can obtain buildable code, and may have it maintained and further developed by **any vendor of its choosing**. A proposal that does not deliver that end-state in full shall be rejected as **non-responsive**.

The University is technology-neutral as to the delivery approach and shall accept any of the following three approaches, or a well-justified hybrid thereof, provided the delivered solution satisfies every functional, technical, security, performance, and service-level requirement of this RFP and delivers the full Scope of Work on a turnkey basis:

Approach	Description	Bidder's Obligations
(a) Custom Development	A bespoke solution engineered specifically for the University using modern, mainstream, well-supported technologies — for example React/Angular, Node.js, Java, or Python, with relational and/or NoSQL data stores.	The Bidder shall build all modules to the University's processes; deliver full **source code**, build artefacts, and documentation; and assign to the University the Intellectual Property Rights as set out in Section 3.7 and Section 9.
(b) COTS Product Implementation	Implementation and configuration of an established, proven Commercial-Off-The-Shelf education/campus ERP product, customised to the University's workflows.	The Bidder shall disclose and cost all product **licences** — perpetual/enterprise/subscription — transparently in the BOQ; deliver all configuration, customisation, and integration; provide product roadmap and version-upgrade commitments; and satisfy the source-code escrow provisions of Section 9.
(c) SaaS Solution	A fully hosted, cloud-delivered, subscription-based solution operated as a managed service.	The Bidder shall guarantee **data residency within India**, the University's ownership of and unrestricted export rights over all its data, security and compliance per Section 5, service continuity, and a defined exit/data-handover plan per Section 9. **The Bidder shall additionally satisfy Clause 9.5.3.4 by electing, at bid stage, either Route 1 (escrowed single-tenant deployable build) or Route 2 (pre-committed perpetual fallback licence), so as to deliver the uniform continuity end-state at Clause 9.5.6. A hosted / SaaS bid electing and evidencing either Route is fully responsive and may attain maximum marks under every criterion of Section 8.**

Regardless of the approach proposed, the delivered solution shall comply in full with the hosting, data-residency, security, integration, accessibility, and performance requirements of Section 5 (Technical Requirements), and with the service levels of Section 6.

> **Important —** CRITICAL REQUIREMENT (all approaches): Whichever approach is adopted, the delivered system **must** support **custom module integration and development**. Even where a pre-built, licensed COTS product or a SaaS platform is proposed, the University requires the demonstrable, ongoing ability to build, embed, and integrate custom, bespoke modules into the platform — whether by the University's own teams or by third parties — seamlessly within the ERP ecosystem, through a **robust, documented, secured API layer, a microservices architecture, and/or a plugin/extension framework**. A closed, black-box product that cannot be extended through open, documented, versioned APIs or an equivalent plugin architecture is **not acceptable** and shall be liable to rejection under Section 8.

The Bidder shall, in its Technical Proposal, explicitly describe:

1. The extensibility mechanism offered — open REST/GraphQL APIs, event/message-based microservices, webhooks, SDKs, and/or a plugin marketplace — with sample API documentation.
2. How a new, University-specified custom module — for example a new sports-science research workflow — would be developed and integrated post-Go-Live, including data-model access, authentication/authorisation, and UI embedding.
3. Rate limits, sandbox/test environments, versioning policy, and backward-compatibility guarantees for the API/plugin layer.

3.4 Detailed Scope of Services

The Selected Agency shall perform, at minimum, the following services across the Implementation and Operations phases. This enumeration states the minimum and shall not be construed to limit the turnkey obligation of Section 3.1.

Sl.	Service	Description
S1	**Requirement Study & SRS / BBP**	Conduct detailed, on-site requirement-gathering workshops with all stakeholder departments (academics, examinations, finance, sports, hostel, HR, administration, IQAC, affiliated-college cell); study existing processes, formats, statutes, and regulations; and prepare a comprehensive **Software Requirements Specification (SRS)** / **Business Blueprint (BBP)**, including process maps, use-cases, wireframes, data model, integration inventory, and a requirement-traceability matrix mapped to Sections 4 and 5.
S2	**Solution Design & Architecture**	Prepare and obtain sign-off on the detailed solution design — logical and physical architecture, database/data-model design, security architecture, API/integration design, high-availability and disaster-recovery design, UI/UX design system, and non-functional design — consistent with Section 5.
S3	**Development / Configuration / Customisation**	Develop (Custom), configure (COTS/SaaS), and customise all modules of Section 4 — including sports-domain modules — with role-based access, workflow automation, dashboards, reports, and responsive/mobile interfaces; conduct code reviews; and adhere to secure-coding standards.

Sl.	Service	Description
S4	**Third-Party Integrations**	Design, build, and commission all required integrations, including but not limited to the **SBIePay (State Bank of India ePay) payment aggregator** — Aggregator-Hosted model, Double-Verification/Status-Query, Push-Response, DVP settlement, Refund/Cancellation API, asymmetric-key encryption — **SMS/Email gateways**, **biometric attendance** devices, **DigiLocker / National Academic Depository (NAD)**, **UGC / AISHE** portals, and **wearable/IoT sports devices**, per Section 5.
S5	**Data Migration**	Plan and execute the cleansing, mapping, validation, migration, and reconciliation of all legacy and current data — student, staff, financial, academic, and sports records — from existing spreadsheets, files, and legacy applications into the ERP, with a documented migration strategy, mock runs, and University-verified reconciliation reports.
S6	**Testing & Quality Assurance**	Conduct comprehensive **unit, integration, system, performance/load, security, regression, and User Acceptance Testing (UAT)**; furnish test plans, test cases, and defect/closure reports; and obtain documented UAT sign-off from the University prior to Go-Live.
S7	**Training & Capacity Building**	Deliver role-based end-user training and administrator / "train-the-trainer" programmes for helpdesk, faculty, coaches, and staff; provide user manuals, quick-reference guides, e-learning content, and recorded sessions; and support post-Go-Live adoption.
S8	**Deployment & Go-Live**	Provision and configure the production, staging, and DR environments per Section 5; deploy the solution; execute cut-over and Go-Live; and provide an intensive **hypercare** stabilisation period immediately following Go-Live, culminating in Final Acceptance (FAT).
S9	**Operations, Maintenance, Support & AMC (5 years)**	Provide SLA-bound operations, hosting support, help-desk, incident and problem management, corrective/adaptive/perfective maintenance, statutory and regulatory change updates, security patching, minor enhancements, and version upgrades for **five (5) years** post-Go-Live, per Section 6 and the canonical Uptime SLA of **99.5%** monthly, measured at the application layer.
S10	**Documentation & Handover**	Deliver and maintain, throughout the term, complete and current documentation — SRS/BBP, architecture and design documents, source code (as applicable), configuration registers, API documentation, deployment/run-books, security documentation, and user/admin manuals — and, at term-end, a structured exit and knowledge-transfer handover per Section 9.

3.5 Core Deliverables

The Selected Agency shall deliver, at minimum, the following core deliverables. Each deliverable is subject to formal review, testing, and written acceptance by the University on the acceptance basis stated, which shall also govern the release of the corresponding payment milestone under Section 7.

Deliverable	Description	Acceptance Basis
D1 — SRS / Business Blueprint	Comprehensive, signed-off requirements specification and process blueprint with requirement-traceability matrix mapped to Sections 4 and 5.	Formal University review and written sign-off; completeness against Sections 4 & 5.

Deliverable	Description	Acceptance Basis
D2 — Solution Design & Architecture Document	Detailed logical/physical architecture, data model, security, integration, HA/DR, and UI/UX design.	University design-review sign-off; conformance to Section 5.
D3 — Fully Functional ERP Software	The complete, integrated ERP encompassing all modules of Section 4, including sports-domain modules, with role-based access, workflow automation, dashboards, and reporting.	Successful System Test and **UAT sign-off of all modules**.
D4 — Custom-Extension / API Framework	Documented, secured API/microservices/plugin framework enabling ongoing custom module development and integration, per the critical requirement in Section 3.3.	Demonstrated build and integration of a sample custom module; published API documentation.
D5 — Third-Party Integrations	Live, tested integrations — SBIePay, SMS/Email, biometric, DigiLocker/NAD, UGC/AISHE, wearables — per Section 5.	End-to-end integration test pass; SBIePay compliance sign-off per the bank's security format.
D6 — Mobile / Responsive Interfaces	Responsive web / Progressive Web App (PWA) interfaces for **all user roles** (mandatory), plus **one cross-platform hybrid mobile application** (single codebase) covering the priority journeys per TR-TEC-03 of Section 5 — Android release at Go-Live (mandatory); iOS release within **six (6) months** of Go-Live (desirable).	Functional and accessibility testing pass; UAT sign-off for the PWA and Android application; iOS release accepted per its schedule.
D7 — Migrated & Reconciled Data	All legacy/current data migrated, validated, and reconciled into production.	University-verified reconciliation reports; data-integrity checks pass.
D8 — HA & Disaster-Recovery Setup	Configured high-availability production environment and DR arrangement meeting the RPO/RTO of Section 5.	Successful DR failover/restore drill; SLA conformance.
D9 — Test Artefacts	Test plans, cases, results, defect closure and performance results.	Closure of all critical/high defects; Security Testing exit criteria met; TR-PAY-17 audit clearance certificate furnished.
D10 — Training & Documentation	User/admin manuals, technical documentation, training material, and completed training sessions.	Delivery of the documentation set; training-completion records and attendance.
D11 — Source Code / Configuration Access	Full source code (Custom) or complete administrative configuration access and source-code escrow (COTS/SaaS), per Section 3.7 and Section 9.	Verified repository handover / escrow deposit; admin-access verification.
D12 — Go-Live & Final Acceptance	Production Go-Live, hypercare stabilisation, and Final Acceptance (FAT).	Go-Live confirmation, hypercare exit, and FAT certificate.

Deliverable	Description	Acceptance Basis
D13 — Periodic O&M Reports	Quarterly operations, SLA-compliance, security, and enhancement reports across the 5-year term.	Timely submission; SLA achievement per Section 6.

> **Reference —** The mapping of these deliverables to payment is set out in the canonical payment-milestone schedule of Section 7 (Pricing & Payment Terms). Delay in any milestone deliverable shall attract Liquidated Damages at **0.5% of the delayed milestone value per week, subject to a maximum of 10%** of the contract value, per Section 7 and Section 9.

3.6 Out of Scope & University's Responsibilities

The following are outside the SI's scope of supply and shall be the responsibility of the University. The SI shall, however, coordinate, advise, and provide reasonable support to enable the University to discharge these responsibilities in a timely manner. Delay by the SI in requesting or specifying its needs shall not constitute grounds for a University-attributable delay.

#	University Responsibility
U1	**Provision of data & information** — furnish existing records, formats, statutes, regulations, and reference data required for requirement study, configuration, and migration, in the form reasonably available with the University.
U2	**Single Points of Contact (SPOCs)** — nominate a Project Owner and departmental SPOCs empowered to provide requirements, clarifications, reviews, and sign-offs within agreed timelines.
U3	**UAT participation** — depute adequate, informed users to conduct and formally sign off User Acceptance Testing within the agreed test window.
U4	**Campus network & end-user devices** — provide the University's internal LAN/Wi-Fi connectivity at campus premises and the end-user computing devices (desktops, printers, and the civil/electrical provisioning for biometric hardware) required for user access.
U5	**Statutory approvals & policy decisions** — obtain internal administrative/statutory approvals and take policy/business decisions (fee structures, workflow rules, delegation of authority) required for configuration.
U6	**Facilitation & access** — provide reasonable working space during on-site engagements, physical/logical access to relevant premises and systems, and facilitation with third parties (for example, the bank for SBIePay onboarding).

The following are expressly **out of scope** unless separately and expressly agreed in writing: supply of end-user computing hardware and printers; civil, electrical, and physical-security works at University premises; provision of the University's wide-area internet bandwidth to campus; and procurement of biometric/wearable devices where the University elects to supply them (the SI shall nonetheless integrate University-supplied compatible devices).

> **Note —** The SI's obligation to provision, license, and operate all hosting, platform, middleware, database, security, and application components necessary for the solution to function on a turnkey basis (per Section 3.1 and Section 5) is **not** diminished by this Section. Only the specifically enumerated items above are the University's responsibility.

3.7 Deployment, Licensing & Ownership

The solution shall be deployed in production, staging, and disaster-recovery environments conforming to the hosting, data-residency (within India), high-availability, and security requirements of Section 5 (Technical Requirements). The deployment topology shall be proposed by the Bidder consistent with the accepted solution approach — Custom / COTS / SaaS — of Section 3.3.

Licensing. All software licences necessary for the full, uninterrupted use and operation of the solution by the University's users and the affiliated ecosystem — application, database, middleware, and any third-party components — shall be provided by the SI on an **enterprise / unlimited-institutional-user basis**, transparently costed in the BOQ under Section 7. Where a COTS/SaaS approach is proposed, the licensing model (perpetual, enterprise, or subscription), the number and type of licences, and all renewal costs across the five-year term shall be disclosed in full, with no hidden or downstream charges. Licences shall be issued in the name of the University and shall be **perpetual and irrevocable** in accordance with Clauses 9.5.3.1 and 9.5.6; a licence that lapses on expiry or termination of the Contract is **not acceptable**.

Ownership of IP, source code & data. The University shall be, and shall remain, the sole and absolute owner of **all University data** and of all custom-developed software, configurations, customisations, workflows, and reports created for the University under this engagement. For the Custom Development approach, all Intellectual Property Rights and the **complete source code** shall vest in and be assigned to the University. For COTS/SaaS approaches, the underlying licensed product IP may remain with the OEM, but all University-specific customisations and data shall be owned by the University, and the product source code (or, for a hosted/SaaS offering, the deployable build or fallback edition under Clause 9.5.3.4) shall be placed in **escrow** for the University's protection, **releasable on expiry or termination of the Contract as well as on default**, with an express right for the University to appoint a **successor vendor** to maintain and further develop it. The University shall at all times retain unrestricted rights to export and take away its data in open, documented formats.

> **Reference —** These provisions are stated here in brief for scope clarity. The full and governing terms on Intellectual Property Rights, source-code ownership and escrow, data ownership and protection, and licensing are set out in **Section 9 (Terms & Conditions)** and shall prevail in case of any inconsistency.

3.8 High-Level System Context Diagram

The following context diagram depicts the principal user groups and external systems that interact with the **MBSPSU ERP** core. It is indicative of the system boundary and integration surface; the authoritative integration specifications are set out in Section 5 (Technical Requirements).



Note — The bidirectional links denote request-response exchanges — for example, SBIePay payment initiation and settlement/refund confirmation, biometric attendance pull, DigiLocker/NAD record push-pull, and wearable performance-data ingestion. The Bidder shall detail the authentication, encryption, error-handling, and reconciliation mechanism for each integration in its Technical Proposal, consistent with Section 5.

Section 4 — Functional Requirements (Software Requirements Specification: Functional)

This Section constitutes the **Functional Software Requirements Specification (SRS-F)** for the Enterprise Resource Planning (ERP) System to be designed, developed, and implemented at **Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala** under Tender Reference No. **MBSPSU/PUR/ERP/2026/01**. It defines *what* the solution must do. The corresponding *how* — architecture, hosting, security, integrations, and performance — is specified in Section 5 (Technical Requirements). Together, Sections 4 and 5 form the complete SRS against which the Bidder's Functional and Technical Compliance Sheets (Annexure F and Annexure G respectively) shall be evaluated.

The proposed solution shall cover the **entire lifecycle of a student and athlete** and the **complete administrative and academic functions** of the University. Because MBSPSU is the first specialised Sports University of the State of Punjab, the sports-domain modules — athlete performance, sports facilities, sports nutrition and health, and tournaments — are **first-class, mandatory requirements** and not optional add-ons.

> **Note —** This Section is the largest of the RFP by design. Bidders are cautioned to respond to **every** requirement identifier (Req ID) individually in the Functional Compliance Sheet (Annexure F). A blanket statement of compliance for a whole module or suite shall be treated as **Not Complied (NC)** for every constituent requirement.
>
> **Important —** The system shall support custom module integration and development. Even where a licensed Commercial-Off-The-Shelf (COTS) product is proposed, it shall expose an extensible architecture — documented REST/JSON APIs, plug-ins, or a supported customisation framework — so that University-specific modules and future statutory requirements can be accommodated without vendor lock-in and without re-procurement. The detailed architectural mandate is set out in Section 5 (Technical Requirements).

4.1 Overview and How to Respond

4.1.1 Section at a glance

Item	Detail
Purpose	Functional SRS — enumerates every functional requirement the ERP must satisfy
Structure	Cross-cutting requirements (4.2) + seven module suites A–G (4.3) + workflow illustrations (4.4)
Requirement identifiers	Every requirement carries a unique **Req ID** (e.g., `FR-ADM-03`) that maps one-to-one to the Functional Compliance Sheet at **Annexure F**
Bidder's obligation	Respond to each Req ID with a **compliance code** and, where required, a cross-reference to the product screen/document that demonstrates it
Traceability	Req IDs are permanent and shall be carried through the Business Blueprint (BBP), UAT test scripts, and User Acceptance sign-off

4.1.2 Compliance codes (mandatory usage in Annexure F)

The Bidder shall indicate, against every Req ID, exactly **one** of the following compliance codes. The code declared shall be truthful and shall be verified during the Technical Presentation and Product Demonstration (T + 55 to T + 57) and again during User Acceptance Testing (UAT).

Code	Meaning	Interpretation
FC	Fully Complied — out-of-the-box	The requirement is met by the standard, shipped product with no configuration or code change; demonstrable in the base build.
CF	Complied via Configuration	The requirement is met by parameterisation, workflow set-up, master-data entry, or role/menu configuration — **without** source-code change.
CD	Complied via Customisation / Development	The requirement is met only by bespoke development, extension, or integration effort, to be delivered within the project scope and price.
NC	Not Complied	The requirement cannot be met by the proposed solution.

> **Important —** A declaration of **FC** or **CF** that cannot be substantiated live during the Product Demonstration or during UAT shall be treated as a **material misrepresentation**, may attract rejection under Section 2 (Instructions to Bidders), and may invoke Liquidated Damages under Section 7 (Pricing and Payment Terms). All **CD** items shall be delivered at **no additional cost** over the quoted contract value; the Bidder is deemed to have priced them in.

4.1.3 Priority codes

Each requirement is tagged with a **priority code** in its module table. The priority governs the sequence of delivery and the treatment of gaps during evaluation.

Code	Priority	Effect
M	Mandatory	Must be delivered and operational by Go-Live. Non-compliance (**NC**) against a Mandatory requirement is scored adversely under evaluation criterion T3 (Section 8) and, if pervasive, may render the bid technically non-responsive.
D	Desirable	Strongly preferred; contributes positively to the technical score. May be phased with the Tendering Authority's written concurrence.
O	Optional	Value-adding; may be deferred or delivered as an enhancement during the Operations & Maintenance term.

> **Note — Phased delivery.** The University shall implement this scope in two phases within the same contract: **Phase-1 (Go-Live)** comprises all requirements marked **M**. **Phase-2 (months 12–24 post-Go-Live)** comprises the requirements marked **D** in Suites C, D and G and the other Phase-2 items identified below; these shall be quoted as clearly identified optional line items in the BOQ (Part D — Phase-2 Optional Items of the BOQ, per Section 7) and shall be commissioned against the University's written order, subject to budget availability. A requirement's phase does not dilute the Bidder's obligation to demonstrate the platform's capability for it during technical evaluation.
>
> **Reference —** The full list of Req IDs in this Section is reproduced as the response template at **Annexure F (Functional Compliance Sheet)**. Where a numbering conflict is perceived, the Req ID printed in this Section 4 shall prevail.

4.1.4 Reading conventions

Throughout this Section: **"shall"/"must"** denotes a mandatory obligation; **"should"** denotes a recommended capability; **"may"** denotes an optional capability. "The University" means MBSPSU; "the Bidder" means the responding agency; "the solution"/"the ERP" means the software system to be delivered.

4.2 Common / Cross-Cutting Functional Requirements

The requirements in this sub-section are **horizontal**: they apply to and underpin **every** module in Suites A–G. They shall be delivered as **shared, unified platform services** — a single security model, a single workflow engine, a single notification bus, a single document store, and a single audit trail — and **not** as siloed features re-implemented per module. Where a downstream module table repeats a capability (for example, an approval flow or a notification), it is understood to consume these shared services.

Req ID	Requirement	Priority
FR-GEN-01	**Unified Role-Based Access Control (RBAC) and User Management.** The solution shall provide a single, centralised identity store with hierarchical roles, user groups, and fine-grained privileges controllable at module, screen, field, record, and action level. It shall support delegation, temporary role assignment, maker-checker segregation of duties, and de-provisioning on separation.	M
FR-GEN-02	**Single Sign-On (SSO).** A user shall authenticate once and access all authorised modules without re-login. The solution shall support standards-based SSO (SAML 2.0 / OAuth 2.0 / OpenID Connect) and shall be capable of federating with the University's directory and, where applicable, State/Government identity providers, as detailed in Section 5.	M
FR-GEN-03	**Configurable Workflow and Approval Engine.** A single graphical/parameter-driven workflow engine shall drive all approvals across modules, supporting serial, parallel, conditional, and role/amount-based routing, delegation on leave, auto-escalation on SLA breach, recall, and full workflow versioning — all configurable by an authorised University administrator without source-code change.	M
FR-GEN-04	**Role-Based Dashboards.** Each role (Vice-Chancellor, Registrar, Deans, HoDs, Coaches, Finance, faculty, students, athletes, parents, alumni, etc.) shall receive a personalised landing dashboard with role-relevant KPIs, pending-action queues, alerts, and drill-down widgets. Dashboards shall be configurable and refreshed on defined intervals or in near-real-time.	M

Req ID	Requirement	Priority
FR-GEN-05	**Global Search.** A unified, permission-aware search shall span records, documents, and master data across all modules, returning results filtered strictly to the user's authorisation, with faceted refinement and quick-navigation to the source record.	M
FR-GEN-06	**Document Management System (DMS).** A central DMS shall store, version, tag, index, and retrieve documents and scanned artefacts, with check-in/check-out, retention and disposal policy, watermarking, access control inherited from FR-GEN-01, and support for bulk upload and OCR-based indexing.	M
FR-GEN-07	**Multi-Channel Notifications.** A single notification service shall dispatch alerts via **email, SMS, WhatsApp, mobile push, and in-app** channels, driven by configurable multilingual templates, event triggers, user preferences, quiet-hours, and delivery/read receipts, with a resend and failure-audit facility.	M
FR-GEN-08	**Audit Logging.** The solution shall maintain a tamper-evident, immutable audit trail of every create, read (of sensitive data), update, delete, login, permission change, and workflow action — capturing user, role, timestamp, source IP/device, and before/after values — retained and queryable per the retention policy in Section 5.	M
FR-GEN-09	**MIS and Ad-hoc Report Builder.** The solution shall provide standard MIS reports for every module **and** a self-service, drag-and-drop ad-hoc report/query builder allowing authorised users to define, save, schedule, and export reports (PDF/XLSX/CSV) without programming, subject to data-access permissions.	M
FR-GEN-10	**Mobile Access — Responsive Web/PWA and Hybrid App.** All functions for all user roles shall be delivered as fully **responsive web / Progressive Web App (PWA)** interfaces across devices (Mandatory), in alignment with Section 5. In addition, the Bidder shall provide **one cross-platform hybrid mobile application (single codebase)** covering notifications, attendance, fee payment, results, and facility booking — released for **Android by Go-Live (M)** and for **iOS within six (6) months of Go-Live (D)**. Offline data capture should be limited to attendance marking, with automatic synchronisation on reconnection.	M
FR-GEN-11	**Multilingual Support.** At Go-Live, the user interface shall be delivered in **English (M)**, and **printed certificates, receipts, and key public notices shall be issued in English, Punjabi (Gurmukhi), and Hindi (M)**, with the data layer stored in Unicode (UTF-8) to preserve Gurmukhi and Devanagari fidelity. A **full trilingual user interface and notification templates** (English/Punjabi/Hindi, switchable by the user) shall be a **Phase-2 capability (D)** per the phased-delivery note in 4.1.3.	M
FR-GEN-12	**Master-Data Management (MDM).** A single, governed master-data repository (programmes, departments, courses, sports/disciplines, fee heads, GL codes, designations, hostels, vendors, calendar events, etc.) shall serve as the authoritative source consumed by all modules, with maker-checker control, effective-dating, and de-duplication.	M
FR-GEN-13	**University Calendar.** A central, role-aware academic and administrative calendar shall consolidate academic sessions, examinations, holidays, sports fixtures, facility bookings, and events, with subscription/sync (iCal) and automatic feeding of dependent modules and notifications.	M
FR-GEN-14	**Configurable Master Codes and Numbering.** All document/serial numbering (application no., admission no., roll no., receipt no., PO no., file no., grievance ID, etc.) shall be configurable by format, prefix/suffix, and reset cycle, and shall be gap-free and non-repeating.	M

Req ID	Requirement	Priority
FR-GEN-15	**Data Export and Print Framework.** Every list and record view shall support export to PDF/XLSX/CSV and standardised, University-branded printable templates (bilingual where required), configurable without code change.	D

> **Mandatory —** The cross-cutting services in FR-GEN-01 through FR-GEN-14 are all **Mandatory (M)**. A proposed solution that implements any of these as per-module silos rather than as a shared platform service shall be marked down under evaluation criterion T4 (Technical architecture) in Section 8.

4.3 Module Suites A–G

The following seven suites enumerate the module-level functional requirements. Each requirement is atomic and testable and carries a traceable Req ID. Priorities are as defined in 4.1.3.

4.3.1 Suite A — Pre-Admission, Web Presence & Student Information

Suite A governs the University's public digital presence and the complete pre-admission-to-enrolment journey: the outward-facing web portal and CMS, first-contact enquiry handling, the online admission and enrolment engine, and the authoritative Student Information System that becomes the single source of truth for every enrolled student and athlete.

4.3.1.1 UNIVERSITY WEB PORTAL & CONTENT MANAGEMENT SYSTEM — `FR-CMS`

A dynamic, standards-compliant web portal and CMS through which the University publishes information and through which prospective applicants begin their journey, tightly integrated with the ERP so that announcements, merit lists, and events are surfaced in real time.

Req ID	Requirement	Priority
FR-CMS-01	The solution shall provide a browser-based CMS enabling authorised, role-based content authoring and publishing (pages, menus, banners, notices, downloads, image/media galleries) with a maker-checker publishing workflow and content versioning/rollback.	M
FR-CMS-02	The portal shall display **real-time ERP-driven content** — announcements, merit/selection lists, examination notices, event calendars, and results — sourced directly from the ERP without manual re-keying.	M
FR-CMS-03	The portal shall be multilingual (English, Punjabi, Hindi) and shall conform to **WCAG 2.1 Level AA** accessibility and to Government of India GIGW guidelines.	M
FR-CMS-04	The CMS shall provide SEO controls (metadata, friendly URLs, sitemap, structured data) and analytics integration for traffic and engagement reporting.	D

Req ID	Requirement	Priority
FR-CMS-05	The portal shall host secure downloadable forms, tender/notice boards, RTI disclosures, and mandatory statutory/UGC disclosures, with scheduled publish/expire dates.	M
FR-CMS-06	The portal shall provide a secure enquiry/contact capture that feeds directly into the Front Desk & Enquiry CRM (`FR-FD`) as a lead.	M
FR-CMS-07	The CMS shall be responsive across devices and shall degrade gracefully on low-bandwidth connections; media shall be served in optimised formats.	D
FR-CMS-08	The solution shall allow department/faculty micro-sites or sub-sections under central governance and a common template/branding framework.	O

4.3.1.2 FRONT DESK & ENQUIRY CRM — `FR-FD`

A unified customer-relationship layer capturing every first contact — walk-in, telephone, email, web, or WhatsApp — together with campus visitor governance and physical dispatch/receipt logging.

Req ID	Requirement	Priority
FR-FD-01	The solution shall capture and consolidate enquiries from all channels (walk-in, phone, email, web form, WhatsApp) into a single CRM with a unique enquiry ID, source tagging, and duplicate detection.	M
FR-FD-02	The solution shall support lead assignment, follow-up scheduling, reminder alerts, status stages (new/contacted/qualified/converted/closed), and conversion analytics from enquiry to admission.	M
FR-FD-03	The solution shall provide **visitor management** with pre-registration, photo capture, ID recording, host approval, and **gate-pass generation** with QR/barcode, plus check-in/check-out logging.	M
FR-FD-04	The solution shall maintain **postal/courier dispatch and receipt (inward/outward) registers** with tracking numbers, department routing, and acknowledgement capture.	M
FR-FD-05	The solution shall integrate with the multi-channel notification service (FR-GEN-07) for automated enquiry acknowledgements and follow-ups.	D
FR-FD-06	The solution shall provide front-desk dashboards and MIS on enquiry volumes, sources, response times, and conversion funnels.	D
FR-FD-07	The solution shall allow escalation of unattended enquiries per configurable SLA timers.	O

4.3.1.3 ADMISSION & ENROLMENT MANAGEMENT — `FR-ADM`

The end-to-end online admission engine: application capture, fee payment, merit and counselling, reservation compliance, and conversion of a selected applicant into an enrolled student with a permanent identity in the SIS.

Req ID	Requirement	Priority
FR-ADM-01	The solution shall provide programme-wise **online application portals** (BPES, BSS, B.P.Ed, M.P.Ed/MPES, M.Sc. Yoga, PG Diploma in Yoga, and BA/BSc/MSc streams) with configurable, form-builder-driven application forms and eligibility rules.	M
FR-ADM-02	The solution shall support secure **document upload** with format/size validation, and shall verify applicant identity data where feasible against submitted proofs.	M
FR-ADM-03	The solution shall collect **application/admission fees online** through the University's payment gateway (**SBIePay**, per Section 5), with automated reconciliation, receipting, and double-verification of payment status.	M
FR-ADM-04	The solution shall generate **merit/selection lists** on configurable criteria (marks, entrance test, sports proficiency/quota, category), including automated ranking and tie-breaking rules.	M
FR-ADM-05	The solution shall administer **reservation and quota management** in accordance with applicable Government of Punjab and statutory reservation policies (category-wise, sports quota, and other admissible reservations), with real-time seat-matrix tracking.	M
FR-ADM-06	The solution shall support **counselling and seat allocation** (online/offline), waitlist movement, seat acceptance/withdrawal, and fee-payment-triggered confirmation.	M
FR-ADM-07	The solution shall provide **lead tracking and conversion analytics** linking enquiries (FR-FD) to applications to confirmed admissions.	D
FR-ADM-08	Upon admission confirmation, the solution shall **auto-create the student record** in the SIS (FR-SIS) with a unique admission/enrolment number, carrying forward all application data without re-entry.	M
FR-ADM-09	The solution shall support **affiliated-college admission oversight** where the University administers or monitors admissions to affiliated colleges of physical education/sports.	D
FR-ADM-10	The solution shall handle admission cancellation and fee-refund initiation, routed through the configurable workflow engine and the finance module (FR-FIN).	D

4.3.1.4 STUDENT INFORMATION SYSTEM — `FR-SIS`

The authoritative, lifelong digital record of every student and athlete — demographic, academic, athletic, financial-status, and disciplinary — serving as the master reference consumed by all downstream academic, sports, finance, and campus-life modules.

Req ID	Requirement	Priority
FR-SIS-01	The solution shall maintain a **comprehensive digital student profile** covering demographics, contact/guardian data, category, programme/semester, academic history, **sports achievements and discipline/sport played**, health flags, and **disciplinary records**.	M
FR-SIS-02	The solution shall generate **student ID cards** with photograph and configurable layout, integrated with **barcode/QR/RFID** for use across attendance, library, hostel, mess, and facility access.	M
FR-SIS-03	The solution shall support **promotion, detention/retention, semester progression, transfer, and dropout tracking**, with status history and reason codes.	M
FR-SIS-04	The SIS shall serve as the single source of student master data to all other modules via FR-GEN-12, preventing duplicate maintenance.	M
FR-SIS-05	The solution shall maintain a **parent/guardian portal** view of the student's attendance, academics, fees, and notifications, with consent-based access.	D
FR-SIS-06	The solution shall support bulk operations (batch promotion, section allocation, roll-number generation) with maker-checker control.	D
FR-SIS-07	The solution shall maintain document linkage (certificates, proofs, achievements) via the DMS (FR-GEN-06), and support alumni-record transition on graduation into the Placement & Alumni module (FR-PLA).	D
FR-SIS-08	The solution shall enforce data-privacy controls over sensitive student fields (health, disciplinary, POSH-related) consistent with FR-GEN-01 and the DPDP Act, 2023 obligations in Section 5.	M

4.3.2 Suite B — Academic & Learning Management

Suite B operates the academic machinery of the University under the **Choice-Based Credit System (CBCS)**: programme/course structures and outcomes, timetabling across classrooms, laboratories and sports courts, digital learning delivery, and the complete examination and grading lifecycle culminating in transcripts lodged with the National Academic Depository.

4.3.2.1 ACADEMICS MANAGEMENT — `FR-ACAD`

Definition and administration of the academic framework — programmes, courses, syllabi, credits, timetables, faculty workload, and the academic calendar — in full CBCS compliance.

Req ID	Requirement	Priority
FR-ACAD-01	The solution shall define **programmes, departments, and courses under CBCS**, including core/elective/audit courses, credits, course outcomes, and programme outcomes, with mapping and effective-dating per academic regulation.	M
FR-ACAD-02	The solution shall manage **syllabus and lesson-plan** repositories, session planning, and mapping of lesson plans to course outcomes, with delivery-progress tracking.	M
FR-ACAD-03	The solution shall generate the **academic calendar** and integrate it with the University calendar (FR-GEN-13), examinations, and sports fixtures.	M
FR-ACAD-04	The solution shall perform **automated, conflict-free timetable generation** for classrooms, laboratories, and **sports courts/grounds**, respecting faculty availability, room capacity, and facility booking (FR-FAC).	M
FR-ACAD-05	The solution shall support **CBCS elective selection/registration** by students within defined windows, credit limits, and prerequisite checks.	M
FR-ACAD-06	The solution shall manage **faculty allocation and workload** tracking against sanctioned norms, including guest/contract faculty.	M
FR-ACAD-07	The solution shall capture and report **student attendance** (subject-wise/period-wise), integrated with biometric/RFID where deployed, with shortfall alerts to students and parents.	M
FR-ACAD-08	The solution shall support **outcome-based education (OBE)** attainment computation (CO/PO attainment) to feed accreditation reporting (FR-CMP).	D
FR-ACAD-09	The solution shall accommodate the **credit and academic requirements of affiliated colleges** where administered centrally.	O

4.3.2.2 LEARNING MANAGEMENT SYSTEM — `FR-LMS`

Digital delivery of learning content — including sports-specific tactical and technique media — assessments, and virtual classrooms, integrated with the academic structure and student record.

Req ID	Requirement	Priority
FR-LMS-01	The solution shall provide **digital content distribution** (notes, e-books, recorded lectures, and **tactical/technique sports videos**) organised by programme, course, and cohort, with access control and version management.	M
FR-LMS-02	The solution shall support **online assignments, quizzes, and assessments** with question banks, timed tests, auto-grading of objective items, submission tracking, and plagiarism-check integration.	M

Req ID	Requirement	Priority
FR-LMS-03	The solution shall integrate **virtual classrooms** (e.g., Zoom / MS Teams / Webex) for live and recorded sessions, with attendance capture and session archival.	D
FR-LMS-04	The solution shall provide **discussion forums, announcements, and instructor-student messaging** within course contexts, using the notification service (FR-GEN-07).	D
FR-LMS-05	The solution shall track **learner progress and engagement** (content viewed, assessments completed, scores) and surface analytics to faculty and administrators.	D
FR-LMS-06	The LMS shall be fully accessible via the mobile apps (FR-GEN-10) and shall support offline download of permitted content.	D
FR-LMS-07	The LMS shall support **SCORM/xAPI** or equivalent standard content packaging for interoperability.	O
FR-LMS-08	The LMS shall link athlete-specific technique/video content to the Athlete Performance module (FR-ATH) for coach review.	O

4.3.2.3 EXAMINATION & GRADING — `FR-EXAM`

The controlled, secure examination lifecycle from scheduling through conduct, unfair-means handling, double-entry evaluation, result processing, and issuance of transcripts and degrees lodged with the National Academic Depository / DigiLocker.

Req ID	Requirement	Priority
FR-EXAM-01	The solution shall support **examination scheduling**, seating/room-plan generation, invigilation duty rosters, and **admit-card generation** with photograph, QR/barcode, and eligibility (attendance/fee) gating.	M
FR-EXAM-02	The solution shall record **examination-day attendance** and log **Unfair Means Cases (UMC)** with evidence attachment, committee routing, and outcome tracking.	M
FR-EXAM-03	The solution shall support **secure mark/grade entry with double-entry (dual-blind) verification** and reconciliation before finalisation, with role-segregated access to evaluation data.	M
FR-EXAM-04	The solution shall administer configurable **grading systems** — relative, absolute, and rubric-based — and compute **CBCS credits, SGPA, CGPA**, grace rules, and pass/fail per academic ordinance.	M
FR-EXAM-05	The solution shall process **results**, including moderation, revaluation/rechecking requests and fee, supplementary/back-paper handling, and result withholding for dues/discipline.	M

Req ID	Requirement	Priority
FR-EXAM-06	The solution shall generate **transcripts, grade cards, provisional certificates, migration certificates, and degrees** in secure, tamper-evident, University-branded formats with verification QR/barcode.	M
FR-EXAM-07	The solution shall integrate with the **National Academic Depository (NAD) and DigiLocker** for lodging and issuance of verified academic awards and documents.	M
FR-EXAM-08	The solution shall maintain a **verification portal/service** for third-party (employer/institution) validation of certificates and results.	D
FR-EXAM-09	The solution shall manage question-paper workflow with confidentiality controls and, where adopted, encrypted question-paper distribution.	D

> **Reference —** Integration mechanisms and security controls for NAD/DigiLocker, SSO, and the SBIePay gateway referenced above are specified in Section 5 (Technical Requirements) and shall be delivered under the same contract.

4.3.3 Suite C — Sports & Athletic Performance (Custom Domain)

Suite C embodies the University's defining purpose as a specialised Sports University. These modules are **bespoke, first-class requirements**: they instrument athlete development, safeguard athlete health and nutrition, and run the University's tournaments and events. Bidders shall treat this suite as central to the technical evaluation of domain understanding under criterion T3 (Section 8).

4.3.3.1 ATHLETE PERFORMANCE & PROGRESSION — `FR-ATH`

Longitudinal tracking of each athlete's physical metrics, skill progression, and coach-guided development, with video analysis and integration to health, nutrition, and learning modules.

Req ID	Requirement	Priority
FR-ATH-01	The solution shall maintain per-athlete **physical performance metrics** over time — including anthropometry/BMI, VO2 max, strength, speed, endurance, and discipline-specific test batteries — with configurable test protocols and trend charting.	M
FR-ATH-02	The solution shall track **skill-based curriculum and level progression** per sport/discipline, mapping athletes against defined proficiency ladders and competency benchmarks.	M
FR-ATH-03	The solution shall provide **Coach and Athlete portals** delivering personalised progress reports, training plans, targets, and feedback, with role-segregated access.	M
FR-ATH-04	The solution shall support **video-analysis upload, tagging, and annotation** of training/match footage linked to the athlete profile, and shall interoperate with the LMS (FR-LMS-08).	D

Req ID	Requirement	Priority
FR-ATH-05	The solution shall generate **individualised and squad-level performance dashboards and reports** for coaches, HoDs, and University leadership.	M
FR-ATH-06	The solution shall record **training attendance, load, and session logs**, and flag over-training or performance-decline patterns for coach review.	D
FR-ATH-07	The solution shall link performance data to **selection and representation** decisions for University teams and to the Tournament module (FR-TOUR).	D
FR-ATH-08	The solution shall integrate wearable/fitness-device data where available (via API) with the Sports Nutrition & Health module (FR-NUT) for a consolidated athlete view.	D

4.3.3.2 SPORTS NUTRITION & HEALTH — `FR-NUT`

Digital medical, injury, physiotherapy, and nutrition management for athletes, integrated with wearables and with the mess/diet function, safeguarding athlete wellbeing.

Req ID	Requirement	Priority
FR-NUT-01	The solution shall maintain **digital health records** per athlete — medical history, screenings, vitals, immunisation, and clearances — with strict privacy controls per FR-GEN-01 and Section 5.	M
FR-NUT-02	The solution shall support **injury tracking and physiotherapy/rehabilitation logs**, including injury type, date, recovery plan, session notes, and return-to-play clearance.	M
FR-NUT-03	The solution shall enable **personalised diet and nutrition plans**, meal tracking, and calorie/macro targets per athlete, integrated with the Hostel & Mess module (FR-HOS) athlete-diet menus.	D
FR-NUT-04	The solution shall manage **supplement inventory and issuance** to athletes with batch/expiry and compliance logging, integrated with Inventory (FR-INV).	D
FR-NUT-05	The solution shall integrate **wearables/fitness devices via API** for capture of heart-rate, activity, sleep, and recovery data into the athlete health view.	D
FR-NUT-06	The solution shall generate **medical fitness certificates and alerts** (e.g., due screenings, injury flags) to coaches and medical staff via the notification service.	D
FR-NUT-07	The solution shall enforce **role-restricted access** to medical/health data limited to authorised medical, physiotherapy, and coaching personnel, with full audit (FR-GEN-08).	M

4.3.3.3 TOURNAMENT & EVENT MANAGEMENT — `FR-TOUR`

Planning and execution of intramural and extramural sports events — registration, fixtures, live scoring, results, and the logistics of away representation including travel, accommodation, and allowances.

Req ID	Requirement	Priority
FR-TOUR-01	The solution shall schedule **intramural and extramural tournaments and events**, with venue/facility booking (FR-FAC) and calendar integration (FR-GEN-13).	M
FR-TOUR-02	The solution shall support **participant/team registration**, eligibility checks against the athlete record, and category/weight/age-group management.	M
FR-TOUR-03	The solution shall generate **fixtures, brackets, and draws** (knockout, league, round-robin) and shall support seeding.	M
FR-TOUR-04	The solution shall capture **live/real-time scoring and results**, standings, and medal tallies, publishable to the web portal (FR-CMS).	D
FR-TOUR-05	The solution shall manage **travel logistics, accommodation, and allowances/TA-DA** for away representation, integrated with Finance (FR-FIN) and Transport (FR-TRN).	M
FR-TOUR-06	The solution shall record **athlete/team achievements and results** back into the athlete profile (FR-ATH / FR-SIS) for progression and accreditation reporting.	D
FR-TOUR-07	The solution shall support **officials/referee assignment, certificates, and honoraria** processing.	D
FR-TOUR-08	The solution shall provide event dashboards and post-event MIS (participation, results, spend).	O

4.3.4 Suite D — Facility & Resource Management

Suite D governs the University's physical and material resources: the booking and upkeep of sports and general facilities, the procurement-to-issue lifecycle of specialised sports equipment and stores, and an online merchandise storefront.

4.3.4.1 SPORTS FACILITY & COURT BOOKING — `FR-FAC`

Centralised, conflict-free booking and maintenance of grounds, courts, pools, gyms, and general facilities, for internal use and external rental.

Req ID	Requirement	Priority
FR-FAC-01	The solution shall provide a **centralised booking system** for sports grounds, courts, swimming pools, gymnasia, and general facilities (classrooms, halls, labs), with real-time availability.	M
FR-FAC-02	The solution shall enforce **conflict-free scheduling** across practice, coaching, matches, academic use, and external rentals, respecting priority rules and timetable (FR-ACAD).	M
FR-FAC-03	The solution shall support **external/paid rental bookings** with rate cards, approval workflow, invoicing (FR-FIN), and terms/liability capture.	M
FR-FAC-04	The solution shall manage **maintenance scheduling, downtime/blackout marking, and breakdown logging** with alerts to facility staff.	M

Req ID	Requirement	Priority
FR-FAC-05	The solution shall enforce **access control** to bookings by role and shall support QR/RFID-based check-in where deployed.	D
FR-FAC-06	The solution shall provide facility-utilisation dashboards and MIS (occupancy, revenue, downtime).	D
FR-FAC-07	The solution shall notify bookers and staff of confirmations, changes, and cancellations via FR-GEN-07.	D

4.3.4.2 INVENTORY & STORE MANAGEMENT — `FR-INV`

The full procure-to-issue lifecycle for stores and specialised, high-value sports equipment and protective gear, with asset tracking, dead-stock control, and fine/damage recovery.

Req ID	Requirement	Priority
FR-INV-01	The solution shall manage **purchase requisition, quotation/comparative processing, and Purchase Order (PO) generation** through the configurable approval workflow, integrated with Finance (FR-FIN).	M
FR-INV-02	The solution shall maintain **item masters and multi-store stock ledgers** with Goods Receipt Notes, inspection, and GST-compliant recording.	M
FR-INV-03	The solution shall support **issuance and return of expensive sports equipment and protective gear** to athletes/teams/departments, with custodian tracking and due dates.	M
FR-INV-04	The solution shall provide **barcode/QR/RFID-based asset tracking**, stock verification, and location tracking for capital and consumable items.	M
FR-INV-05	The solution shall track **dead stock, obsolescence, and condemnation/disposal** with approval workflow and audit.	M
FR-INV-06	The solution shall apply **damage/loss fines and recovery** to the responsible student/employee, posting to Finance and the student ledger.	M
FR-INV-07	The solution shall manage **reorder levels, minimum/maximum stock alerts**, batch/expiry (e.g., supplements, consumables), and stock ageing.	D
FR-INV-08	The solution shall maintain a **vendor master and vendor-performance** record, feeding procurement decisions.	D
FR-INV-09	The solution shall generate inventory MIS and integrate stock valuation with the financial ledgers.	D

4.3.4.3 E-COMMERCE & MERCHANDISE — `FR-ECOM`

An online storefront for University and sports merchandise, and controlled distribution/issue of kit and uniforms to athletes.

Req ID	Requirement	Priority
FR-ECOM-01	The solution shall provide an **online merchandise store** (jerseys, kits, University-branded goods) with catalogue, cart, and secure checkout via the SBIePay gateway (Section 5).	D
FR-ECOM-02	The solution shall manage **product catalogue, pricing, variants (size/colour), and stock** integrated with Inventory (FR-INV).	D
FR-ECOM-03	The solution shall track **order fulfilment, delivery/pickup status, and returns/refunds**, with customer notifications.	D
FR-ECOM-04	The solution shall track **uniform/kit distribution and issue to athletes and teams**, distinguishing free-issue from paid sale, with entitlement rules.	M
FR-ECOM-05	The solution shall reconcile e-commerce collections to Finance (FR-FIN) with itemised, GST-compliant invoicing.	D
FR-ECOM-06	The solution shall provide sales dashboards and MIS on merchandise revenue and stock movement.	O

4.3.5 Suite E — Finance & Institutional Operations

Suite E is the financial, human-capital and administrative backbone of the University: a complete accounting and fee-management system integrated with the SBIePay gateway, a full-lifecycle HRMS with biometric attendance and automated payroll, and a paperless e-Office for the electronic movement, noting and digitally-signed approval of administrative files.

4.3.5.1 FINANCE & ACCOUNTS — `FR-FIN`

Fee management, receipting, and a complete double-entry accounting system — ledgers, payables/receivables, budgeting, reconciliation, and statutory financial reporting — integrated with every revenue-generating module.

Req ID	Requirement	Priority
FR-FIN-01	The solution shall provide **dynamic fee management** — configurable fee heads, programme/category-wise structures, instalments, **scholarships, concessions/waivers, and late fines** — with student-wise fee ledgers.	M
FR-FIN-02	The solution shall collect fees online through the **SBIePay payment gateway** with **double-verification/status-query and push-response reconciliation**, and shall also record offline/challan/DD collections.	M
FR-FIN-03	The solution shall generate **automated invoices, demand notices, and receipts** (bilingual, GST-compliant where applicable) with configurable numbering (FR-GEN-14).	M
FR-FIN-04	The solution shall maintain a full **double-entry General Ledger with chart of accounts, Accounts Payable, Accounts Receivable, cash/bank books, and journal vouchers** under maker-checker control.	M

Req ID	Requirement	Priority
FR-FIN-05	The solution shall support **budgeting and budgetary control** (allocation, commitment, utilisation, variance) at head/department/project level, with over-budget alerts.	M
FR-FIN-06	The solution shall perform **automated bank reconciliation**, including reconciliation of SBIePay settlement (DVP) files against collections.	M
FR-FIN-07	The solution shall generate **statutory and management financial reports** — Trial Balance, Income & Expenditure/P&L, Balance Sheet, Receipts & Payments, and schedules — per applicable Government/University accounting norms.	M
FR-FIN-08	The solution shall handle **refunds and cancellations** (admission, caution money, merchandise) through the SBIePay refund/cancellation flow and the approval workflow.	M
FR-FIN-09	The solution shall manage **TDS, GST, and other statutory deductions/filings** data and provide export for return filing.	D
FR-FIN-10	The solution shall manage **caution/security deposits, fixed assets/depreciation, and grants/projects** accounting.	D
FR-FIN-11	The solution shall provide a consolidated **finance dashboard** (collections, dues, budget utilisation, cash position) for the Registrar and Finance Officer.	D

4.3.5.2 HRMS & PAYROLL — `FR-HR`

The complete employee lifecycle from recruitment to retirement, with biometric-integrated attendance, leave, and automated statutory payroll.

Req ID	Requirement	Priority
FR-HR-01	The solution shall manage the **complete employee lifecycle** — recruitment, onboarding, confirmation, transfer, promotion, deputation, superannuation/retirement, and exit — with a unified employee master.	M
FR-HR-02	The solution shall capture **attendance integrated with biometric devices (fingerprint/facial)** and RFID, with shift/roster support and regularisation workflow.	M
FR-HR-03	The solution shall administer **leave management** (all leave types, balances, accrual, encumbrance) with multi-level approval workflows and calendar integration.	M
FR-HR-04	The solution shall perform **automated payroll processing** — earnings, deductions, arrears, loans/advances — with configurable pay structures for teaching, non-teaching, and contract staff.	M

Req ID	Requirement	Priority
FR-HR-05	The solution shall compute and manage **statutory deductions** — Income Tax/TDS, **PF, ESI**, professional tax, and pension/NPS — and generate compliant outputs and **payslips**.	M
FR-HR-06	The solution shall maintain **service records, seniority, increments, and pay-fixation** history, and generate service certificates.	M
FR-HR-07	The solution shall support **performance appraisal (including API/CAS for faculty), training records, and grievance** capture for employees.	D
FR-HR-08	The solution shall provide an **employee self-service portal/app** for attendance, leave, payslips, tax declarations, and reimbursements.	D
FR-HR-09	The solution shall manage **recruitment** — vacancy, application, screening, interview scheduling, and offer — with integration into onboarding.	D
FR-HR-10	The solution shall generate HR MIS and statutory registers (muster, PF/ESI returns data, Form-16 inputs).	D

4.3.5.3 E-OFFICE — FILE, NOTING & CORRESPONDENCE MANAGEMENT — `FR-EOFF`

A paperless office system for the University's administrative branches, modelled on the Government of India **e-Office / eFile** paradigm: electronic receipts (dak/tapal), electronic files with noting and drafting, digitally signed approvals, and a records room with retention and archival. This module consumes the shared platform services of 4.2 — the workflow engine (FR-GEN-03), the DMS (FR-GEN-06), numbering (FR-GEN-14), notifications (FR-GEN-07) and the audit trail (FR-GEN-08) — and shall **not** re-implement them.

Req ID	Requirement	Priority
FR-EOFF-01	The solution shall maintain an **electronic receipt (dak/tapal) register** — capture of inward correspondence by scan/upload or e-mail ingestion, with diarisation, unique receipt number (FR-GEN-14), sender/subject metadata, acknowledgement, and marking/forwarding to the concerned branch or officer.	M
FR-EOFF-02	The solution shall support the **electronic file (e-file) lifecycle** — creation under a configurable file-numbering plan (head/sub-head/branch/year), attachment of receipts and correspondence, part-file and linked-file handling, movement between officers, parking, closing, reopening and transfer.	M
FR-EOFF-03	The solution shall provide a structured **noting portion and drafting (green-note / draft-for-approval) portion** per file, with sequential, non-erasable notes attributed to user, role and timestamp, version-controlled drafts, and a side-by-side view of noting and correspondence.	M
FR-EOFF-04	The solution shall route files for approval through the configurable workflow engine (FR-GEN-03) along the University's **hierarchy — Assistant / Superintendent / Deputy or Assistant Registrar / Registrar / Vice-Chancellor** — supporting concurrence routing (e.g., to Finance or Legal), pull-back/recall, delegation during leave, and auto-escalation on pendency.	M
FR-EOFF-05	The solution shall apply **digital signature (DSC / Class-3 token) or Aadhaar-based eSign** to notes, drafts, approvals and issued letters, with signature verification, signatory audit and long-term validity of the signed artefact, per **TR-INT-13** of Section 5 and the Information Technology Act, 2000.	M

Req ID	Requirement	Priority
FR-EOFF-06	The solution shall generate **outward correspondence** — letters, office orders, circulars, notifications and memoranda — from University-branded templates (FR-GEN-15), allot despatch numbers, maintain an **outward/despatch register**, and issue by e-mail or print with proof of despatch.	M
FR-EOFF-07	The solution shall provide a **pendency and disposal dashboard** per officer, branch and file category — files received, in-tray age, average disposal time, overdue and parked files — for the Registrar and the Vice-Chancellor, and shall issue reminders on breach of prescribed timelines.	M
FR-EOFF-08	The solution shall maintain a **records room / archival function** with record-classification (A/B/C/D or equivalent), retention schedule, weeding/destruction proposal and approval, and permanent preservation of records marked for archival, with retrieval by file number, subject or keyword.	D
FR-EOFF-09	The solution shall provide **permission-aware full-text search** across files, notings, correspondence and despatched letters (consuming FR-GEN-05), with saved searches and export of the file cover and noting sheet to PDF.	D
FR-EOFF-10	The solution shall support a **leave/tour and internal-requisition e-file interface**, so that HR requests raised in FR-HR flow into the e-Office noting-and-approval chain rather than on paper, and the approved order is written back to the employee record.	D
FR-EOFF-11	The solution shall permit **linkage of an e-file to any transactional record** in the ERP — a purchase proposal, a grievance case (FR-GRV), an RTI application (FR-RTI), a student or employee record — so that administrative approvals are traceable to the underlying transaction.	D
FR-EOFF-12	The solution shall support **committee and meeting management** for administrative bodies — agenda compilation from files, circulation, attendance, recording of minutes, and tracking of action-taken-reports to closure.	O

> **Note —** e-Office is an **administrative-productivity module built on the shared platform services**, not a separate product. Bidders proposing a discrete third-party e-Office product shall demonstrate single sign-on (FR-GEN-02), a common document store (FR-GEN-06) and a unified audit trail (FR-GEN-08) with the ERP, and shall include any such product's licences and its five-year support within the quoted prices of the BOQ (Section 7) without any additional recurring line.

4.3.6 Suite F — Campus Life & Student Services

Suite F runs the residential and support services that define campus life at a residential University: hostels and mess (with athlete-specific diets), the library, transport and fleet, and the placement-and-alumni continuum that follows the student beyond graduation.

4.3.6.1 HOSTEL & MESS — `FR-HOS`

Hostel allocation, residential attendance and gate-pass control, and mess operations including athlete-specific diets and consumption tracking.

Req ID	Requirement	Priority
FR-HOS-01	The solution shall manage **hostel room allocation** via a room/bed matrix, allotment rules, occupancy, vacate/transfer, and waitlists.	M
FR-HOS-02	The solution shall capture **hostel/resident attendance** and manage **out-pass/gate-pass** issuance and return with warden approval and QR/biometric verification.	M
FR-HOS-03	The solution shall administer **mess fee collection**, integrated with Finance (FR-FIN), including deposit, monthly billing, and rebates for absence.	M
FR-HOS-04	The solution shall manage **dietary menus distinguishing standard and athlete diets**, integrated with the Sports Nutrition module (FR-NUT), and maintain daily menu planning.	M
FR-HOS-05	The solution shall maintain **daily consumption and provisioning logs** and mess-inventory linkage (FR-INV) for stores.	D
FR-HOS-06	The solution shall handle **hostel discipline, complaints, and maintenance requests**, routed via the workflow engine.	D
FR-HOS-07	The solution shall provide warden/administrator dashboards and MIS (occupancy, dues, mess consumption).	D
FR-HOS-08	The solution shall support **visitor and parent-contact** logging for residents.	O

4.3.6.2 LIBRARY — `FR-LIB`

A complete library automation system: cataloguing, OPAC, RFID/barcode circulation, and automated fine and reminder handling.

Req ID	Requirement	Priority
FR-LIB-01	The solution shall support **cataloguing and accessioning** of books, journals, and media, preferably conforming to **MARC21 / standard bibliographic** formats, with an acquisition workflow.	M
FR-LIB-02	The solution shall provide an **OPAC (Online Public Access Catalogue)** searchable by patrons via web and mobile.	M
FR-LIB-03	The solution shall manage **circulation (issue/return/renewal/reservation)** with **RFID/barcode** integration and patron limits by category.	M
FR-LIB-04	The solution shall perform **automated fine calculation** for overdue/lost items and post recoveries to the student/employee ledger (FR-FIN).	M
FR-LIB-05	The solution shall send **automated due-date/overdue reminders** via email/SMS/app (FR-GEN-07).	M
FR-LIB-06	The solution shall support **e-resources/digital library** access and, where subscribed, federated search and link resolution.	D
FR-LIB-07	The solution shall generate library MIS (circulation stats, accession register, stock verification, most-used titles).	D

Req ID	Requirement	Priority
FR-LIB-08	The solution shall integrate patron identity with the student/employee ID (FR-SIS/FR-HR) and access control.	D

4.3.6.3 TRANSPORT & FLEET — `FR-TRN`

Fleet records, statutory compliance, route and transport-fee administration, and GPS tracking, integrated with tournament travel logistics.

Req ID	Requirement	Priority
FR-TRN-01	The solution shall maintain **vehicle records** — registration, ownership, **insurance, PUC, permit, fitness** — with expiry alerts.	M
FR-TRN-02	The solution shall track **maintenance, servicing, fuel consumption, and running logs** per vehicle with cost analysis.	M
FR-TRN-03	The solution shall manage **route allocation, stops, and passenger/student assignment**, and **transport-fee collection** integrated with Finance.	M
FR-TRN-04	The solution shall integrate **GPS/vehicle-tracking** for live location and route adherence, and driver assignment/duty logging.	D
FR-TRN-05	The solution shall support **trip/vehicle requisition and allotment** for tournaments and official travel (integrated with FR-TOUR).	M
FR-TRN-06	The solution shall provide transport dashboards and MIS (utilisation, cost per km, compliance status).	D
FR-TRN-07	The solution shall notify students/staff of route changes, delays, and vehicle assignment.	O

4.3.6.4 PLACEMENT & ALUMNI — `FR-PLA`

The placement and internship pipeline and the lifelong alumni relationship, including networking, events, and fundraising.

Req ID	Requirement	Priority
FR-PLA-01	The solution shall provide a **placement/internship portal** with student profiles/resumes, recruiter registration, job/internship postings, and application tracking.	M
FR-PLA-02	The solution shall manage the **recruitment drive lifecycle** — eligibility filtering, scheduling, shortlisting, offers, and placement records/statistics.	M
FR-PLA-03	The solution shall maintain an **alumni directory and networking** platform with self-service profile updates and consent-based visibility.	M
FR-PLA-04	The solution shall support **alumni events, communications, and fundraising/donation** capture (with online payment via SBIePay), integrated with Finance.	D

Req ID	Requirement	Priority
FR-PLA-05	The solution shall transition graduating students from the SIS (FR-SIS) into the alumni record automatically on convocation/exit.	D
FR-PLA-06	The solution shall generate placement MIS required for accreditation reporting (FR-CMP) — placement rate, median salary, recruiter list.	D
FR-PLA-07	The solution shall track alumni achievements, including sporting achievements, for institutional reporting.	O

4.3.7 Suite G — Governance, Grievance & Regulatory Compliance

Suite G safeguards institutional integrity and statutory compliance: a confidential, multi-committee grievance and redressal system meeting UGC obligations for anti-ragging and POSH; a compliance and analytics engine geared to NAAC, NBA, NIRF, and UGC reporting; a dedicated Right-to-Information management module; and the Internal Quality Assurance Cell (IQAC) workflow that owns the University's AQAR, stakeholder-feedback and quality-audit cycles.

4.3.7.1 GRIEVANCE REDRESSAL — SGRC / ANTI-RAGGING / POSH — `FR-GRV`

A centralised, confidentiality-preserving grievance system that routes complaints to the correct statutory committee — the Student Grievance Redressal Committee, the Anti-Ragging Squad/Committee, or the POSH Internal Complaints Committee — with defined timelines and escalation to the University Ombudsperson, in accordance with UGC regulations.

Req ID	Requirement	Priority
FR-GRV-01	The solution shall provide a **centralised digital grievance portal** for students, staff, and stakeholders to register complaints with a **unique tracking ID**, real-time status, and configurable, pre-defined resolution timelines, aligned to the **UGC (Redressal of Grievances of Students) Regulations**.	M
FR-GRV-02	The solution shall route grievances to the correct forum — **Student Grievance Redressal Committee (SGRC)** for general academic/administrative matters, the **Anti-Ragging** Squad/Committee, or the **POSH Internal Complaints Committee (ICC)** — via a configurable triage/nodal-officer step.	M
FR-GRV-03	The solution shall enforce **strict confidentiality and role-restricted access** for **POSH/ICC** and other sensitive cases, sealing case data to authorised committee members only, with full audit (FR-GEN-08), in accordance with the **Sexual Harassment of Women at Workplace Act, 2013** and UGC/AICTE guidelines.	M
FR-GRV-04	The solution shall support **Anti-Ragging compliance** — capture/tracking of online anti-ragging affidavits/undertakings, Anti-Ragging Squad inspection logs, and incident registers — per UGC anti-ragging regulations.	M

Req ID	Requirement	Priority
FR-GRV-05	The solution shall implement a configurable **escalation matrix** with automatic escalation on timeline breach, and provision for **referral/escalation to the University Ombudsperson** and, where applicable, to Police/statutory authorities.	M
FR-GRV-06	The solution shall permit **anonymous or identity-protected** complaint submission where policy allows, while preserving investigative traceability for authorised officers.	D
FR-GRV-07	The solution shall record the **inquiry process, hearings, findings, action taken, and closure**, with document attachments via the DMS, and issue outcome notifications to the complainant.	M
FR-GRV-08	The solution shall generate **grievance MIS and statutory returns** (category, committee, disposal time, pendency) required by UGC and University authorities.	D

> **Mandatory —** The confidentiality, access-segregation, and audit controls for POSH/ICC and Anti-Ragging cases (FR-GRV-03, FR-GRV-04) are non-negotiable Mandatory requirements. Any leakage of sealed grievance data shall be treated as a serious breach under the confidentiality and data-protection obligations of Section 9 (Terms and Conditions).

4.3.7.2 COMPLIANCE, ACCREDITATION & ANALYTICS — NAAC / NBA / NIRF / UGC — `FR-CMP`

Institutional-performance dashboards and automated generation of accreditation and regulatory datasets in the formats required by NAAC, NBA, NIRF, and UGC.

Req ID	Requirement	Priority
FR-CMP-01	The solution shall provide **real-time institutional dashboards** (enrolment, results, revenue, placement, research, sports achievements) sourced from live ERP data for University leadership.	M
FR-CMP-02	The solution shall **automate compilation of accreditation datasets** in the specific formats required by **NAAC (SSR/DVV, AQAR/IIQA), NBA, NIRF, and UGC**, drawing from the operational modules to minimise manual re-entry.	M
FR-CMP-03	The solution shall maintain a **data repository and evidence linkage** (documents via DMS) supporting each accreditation metric for verification and audit.	M
FR-CMP-04	The solution shall support **AISHE and other statutory returns** data compilation and export.	D
FR-CMP-05	The solution shall compute **outcome-based education (OBE) attainment** and feed CO/PO metrics (from FR-ACAD) into accreditation reporting.	D

Req ID	Requirement	Priority
FR-CMP-06	The solution shall provide a **predictive/trend analytics** layer over institutional data (enrolment trends, dropout risk, fee-collection forecasting) for planning.	O
FR-CMP-07	The solution shall maintain a **compliance calendar** of statutory/regulatory due dates with reminders (FR-GEN-07).	D

4.3.7.3 RTI MANAGEMENT — `FR-RTI`

End-to-end handling of applications under the Right to Information Act, 2005 — registration, routing to the Public Information Officer, timeline tracking, response, appeal, and mandatory proactive disclosure.

Req ID	Requirement	Priority
FR-RTI-01	The solution shall register **RTI applications** (online and offline) with a unique ID, applicant details, fee capture, and **statutory 30-day timeline** tracking under the **RTI Act, 2005**.	M
FR-RTI-02	The solution shall route applications to the relevant **Public Information Officer (PIO)/department**, support internal collation of responses, and record the disposal.	M
FR-RTI-03	The solution shall track **first-appeal and second-appeal** stages with their statutory timelines and outcomes.	M
FR-RTI-04	The solution shall issue **timeline-breach alerts** to PIOs and appellate authorities via the notification service.	M
FR-RTI-05	The solution shall maintain the **proactive/suo-motu disclosure** repository (Section 4 of the RTI Act) publishable to the web portal (FR-CMS).	D
FR-RTI-06	The solution shall generate **RTI MIS and periodic returns** (received, disposed, pending, appeals) for the Central/State Information Commission.	D
FR-RTI-07	The solution shall link RTI responses and evidence to the DMS with access control and audit.	D

4.3.7.4 INTERNAL QUALITY ASSURANCE CELL (IQAC) — `FR-IQAC`

The workflow and governance layer of the University's **Internal Quality Assurance Cell**, constituted as mandated by the UGC and NAAC: custody of criterion-wise quality data, the annual **AQAR** preparation and submission cycle, stakeholder feedback and the **Student Satisfaction Survey**, the Academic and Administrative Audit, and the tracking of quality initiatives and best practices to closure.

Reference — Boundary with `FR-CMP` . `FR-CMP` (4.3.7.2) is the **data and analytics** engine: it aggregates operational data from every module and compiles accreditation datasets and dashboards. `FR-IQAC` is the **process and governance** engine that sits over it: IQAC composition and meetings, the AQAR authoring/verification/submission workflow, feedback instruments, audit cycles, and action-taken tracking. The two shall share a single data layer — IQAC screens shall consume `FR-CMP` datasets directly and shall **not** duplicate data capture or re-key any figure already held in the ERP.

Req ID	Requirement	Priority
FR-IQAC-01	The solution shall maintain the **IQAC constitution and composition** — Chairperson, Coordinator, teaching/non-teaching, management, student, alumni, employer and external-expert members — with tenure, notification/office order, and change history.	M
FR-IQAC-02	The solution shall manage the **AQAR (Annual Quality Assurance Report) cycle** end-to-end: opening of the reporting year, criterion- and metric-wise allocation of data-entry responsibility to departments/custodians, due-date tracking, submission, IQAC verification, approval, and locking of the submitted year.	M
FR-IQAC-03	The solution shall organise quality data by the **NAAC criteria and key indicators (Criteria I–VII, with qualitative and quantitative metrics)**, drawing every derivable figure automatically from the operational modules via `FR-CMP` and flagging metrics that remain to be filled.	M
FR-IQAC-04	The solution shall maintain an **evidence and document repository per metric** on the shared DMS (FR-GEN-06) — supporting documents, links, geo-tagged photographs and data templates — versioned by reporting year and ready for **DVV (Data Validation and Verification)** clarification.	M
FR-IQAC-05	The solution shall administer **online stakeholder feedback** — from students, teachers, parents, alumni and employers — including the **Student Satisfaction Survey (SSS)** on curriculum, teaching-learning, examination and facilities, with configurable questionnaires, defined collection windows, and anonymity where the instrument so requires.	M
FR-IQAC-06	The solution shall **analyse feedback** and publish results — item-wise and aggregate scores, trends across cycles, programme/department/course and teacher-wise views (subject to access control) — and shall record the **action taken on feedback** and its communication to stakeholders.	M
FR-IQAC-07	The solution shall manage **IQAC meetings** — calendar, agenda, circulation, attendance, minutes, and resolutions — and shall track each resolution as an **Action Taken Report (ATR)** item with owner, due date, status and closure evidence.	M
FR-IQAC-08	The solution shall maintain the **Academic and Administrative Audit (AAA)** cycle — audit schedule, department-wise self-appraisal, internal/external auditor observations, non-conformities, corrective actions and re-audit — with a consolidated audit report.	D
FR-IQAC-09	The solution shall maintain a register of **quality initiatives, best practices and institutional distinctiveness**, with objectives, implementation record, outcome/impact evidence and mapping to the relevant NAAC criterion for reuse in AQAR and SSR narratives.	D
FR-IQAC-10	The solution shall maintain the **Institutional / Programme Outcome and Curriculum-review trail** — collection of Course/Programme Outcome attainment from `FR-ACAD` and `FR-EXAM` , Board of Studies review notes, and curriculum revision history with effective session.	D

Req ID	Requirement	Priority
FR-IQAC-11	The solution shall provide an **IQAC dashboard** — AQAR readiness by criterion, pending metrics and custodians, feedback response rates, ATR pendency and audit non-conformities — for the IQAC Coordinator, Registrar and Vice-Chancellor.	M
FR-IQAC-12	The solution shall publish the **IQAC page content to the public web portal** (FR-CMS) — composition, minutes, AQARs, feedback analysis reports and quality policy — under the University's mandatory-disclosure obligations, with an approval step before publication.	D
FR-IQAC-13	The solution shall support the **IIQA / SSR compilation** for accreditation cycles by assembling the approved AQAR series and evidence held under this module into the formats produced by `FR-CMP-02`.	D

4.4 Key Workflow Examples

The following illustrative workflows depict how cross-cutting services and modules interact to deliver four representative University processes. They are indicative of expected behaviour and shall be elaborated by the Bidder in the Business Blueprint; they do not limit the requirements enumerated above.

4.4.1 Admission-to-Enrolment (Sequence)

This flow illustrates the applicant journey from application through fee payment, verification, merit determination, and automatic creation of the enrolled student record in the SIS.



4.4.2 Online Fee Payment via SBIePay (Sequence)

This flow illustrates a fee transaction through the SBIePay aggregator, including the double-verification / status-query and push-response reconciliation mandated for reliable receipting.



> **Reference —** The SBIePay integration model — Aggregator-Hosted flow, asymmetric-key request/response encryption, TLS 1.2, SHA-256 checksum, push-response, status-query/double-verification, DVP settlement reconciliation, refund/cancellation API, and the bank's Technical Information Security and Website Security Audit obligations — is specified in Section 5 (Technical Requirements) and Section 10 (Annexures and Forms).

4.4.3 Grievance Resolution — SGRC / Anti-Ragging / POSH-ICC (State)

This state diagram illustrates confidential intake, triage to the correct statutory committee, investigation, and resolution or escalation to the Ombudsperson, with POSH/ICC handling kept strictly confidential.



4.4.4 Examination Lifecycle (Flowchart)

This flow illustrates the controlled examination lifecycle from scheduling through admit cards, conduct with unfair-means handling, double-entry evaluation, result processing, and issuance of transcripts lodged with the National Academic Depository.



Note — The four workflows above are illustrative of the integrated behaviour expected across cross-cutting services (Section 4.2) and the module suites (Section 4.3). During the Business Blueprint phase, the successful Bidder shall document the complete, University-approved to-be process maps for these and all other in-scope processes, tracing each back to the Req IDs in this Section and to the Functional Compliance Sheet at Annexure F.

Section 5 — Technical Requirements

This Section constitutes the **Technical Software Requirements Specification (SRS-T)** for the Enterprise Resource Planning (ERP) System to be delivered under Tender Reference No. **MBSPSU/PUR/ERP/2026/01**. It defines the non-functional, architectural, security, hosting, integration, performance, accessibility and interoperability requirements that the proposed solution shall satisfy. These requirements are complementary to, and shall be read together with, the functional requirements set out in Section 4 (Functional Requirements) and the Scope of Work in Section 3 (Scope of Work).

Each requirement is assigned a traceable identifier of the form **TR-xxx** (and thematic sub-series **TR-SEC-xx**, **TR-PAY-xx**). The Bidder shall respond to every requirement in the Technical Compliance Sheet (Annexure) with a clear statement of **Complied / Partially Complied / Not Complied** together with a substantiating cross-reference to the proposal. In this Section, "shall" and "must" denote mandatory requirements; "should" denotes recommended requirements; and "may" denotes optional requirements.

> **Note —** Compliance with this Section is evaluated under criterion **T4 (Technical architecture, security, data-migration approach, implementation methodology and exit-readiness — 17 marks)** of the QCBS Technical Evaluation Matrix in Section 8 (Evaluation Criteria). A non-responsive or evasive answer to any mandatory requirement may render the bid technically non-compliant.

Section at a glance

Sub-section	Subject	Key requirement IDs
5.1	Architecture principles	TR-ARC-01 … TR-ARC-12
5.2	Reference technical architecture	TR-ARC-13 … TR-ARC-18
5.3	Technology, browsers & standards	TR-TEC-01 … TR-TEC-10
5.4	Hosting, data residency & infrastructure	TR-HOS-01 … TR-HOS-14
5.5	Security & compliance	TR-SEC-01 … TR-SEC-18
5.6	Payment gateway integration (SBIePay)	TR-PAY-01 … TR-PAY-18
5.7	Other integrations	TR-INT-01 … TR-INT-13
5.8	Performance & scalability	TR-PRF-01 … TR-PRF-08
5.9	Accessibility & usability	TR-ACC-01 … TR-ACC-08
5.10	API & interoperability	TR-API-01 … TR-API-10
5.11	Data migration (technical)	TR-MIG-01 … TR-MIG-10

5.1 Architecture Principles

The solution shall be designed and implemented in accordance with the architectural principles set out below. These principles are expressed as **outcomes**: rows using "shall" are mandatory, while rows using "should" are recommended reference practices. The Bidder shall demonstrate, in the Technical Proposal, how the proposed solution achieves each mandatory outcome.

Req ID	Principle	Requirement
TR-ARC-01	Modular architecture (outcome)	The solution shall have a **modular architecture** organised around functional domains (Student, Admission, Finance, HR/Payroll, Sports/Athlete, Examination, Notification, and others per Section 4). Any architectural style — microservices, SOA, or a well-structured modular monolith — is acceptable, provided it demonstrably achieves the outcomes of this Section: modularity (TR-ARC-04), API-first exposure (TR-ARC-02), multi-tenant capability, horizontal scalability (TR-ARC-06), and no single point of failure at the managed-service level (TR-HOS-03).
TR-ARC-02	API-first	Every functional capability shall be exposed through a well-documented, versioned Application Programming Interface (API) **before or concurrently with** any user interface consuming it. No functionality shall be reachable only through a proprietary or undocumented interface.
TR-ARC-03	Cloud-deployed (outcome)	The solution shall run on **managed cloud services** and shall not depend on any single physical server, hard-coded host, or manual deployment step. Container packaging and orchestration (e.g., OCI-compliant images on Kubernetes or equivalent) **should** be used where consistent with the proposed platform, but are not mandated (see TR-ARC-12).
TR-ARC-04	Modular	The system shall be **modular**, such that individual modules may be enabled, disabled, upgraded, or replaced without recompiling or redeploying unrelated modules.
TR-ARC-05	Loosely coupled	Services shall be **loosely coupled** and shall communicate through well-defined contracts (synchronous REST/GraphQL and/or asynchronous message/event streams). A failure in one non-critical service shall not cascade into total system failure.
TR-ARC-06	Horizontally scalable	Each service tier shall be **horizontally scalable**, i.e., capacity shall be increased by adding instances behind a load balancer rather than by vertical scaling alone. Auto-scaling policies shall be supported.
TR-ARC-07	Stateless services	Application/service tiers shall be **stateless**; session and transient state shall be externalised to a distributed cache or token (e.g., Redis, signed JWT). Any instance shall be able to serve any request, enabling rolling restarts and elastic scaling.
TR-ARC-08	Configuration over code	Environment-specific behaviour (endpoints, credentials, feature flags, business parameters such as fee heads, academic calendar, grading rules) shall be driven by **externalised configuration** and administrator-managed master data, not by hard-coded values requiring a code change and redeployment.
TR-ARC-09	Separation of concerns	The solution shall maintain a clear separation between presentation, business logic, integration, and data-persistence layers.

Req ID	Principle	Requirement
TR-ARC-10	Idempotency & resilience	External-facing and payment-related operations shall be **idempotent**, and services shall implement retry-with-backoff, circuit-breaker, and graceful-degradation patterns.
TR-ARC-11	Monitoring & logging (outcome)	The solution shall provide **centralised logging, monitoring, and alerting** — CSP-native services (e.g., CloudWatch, Azure Monitor, Google Cloud Operations) are acceptable — sufficient to correlate a single transaction end-to-end and to support the SLA reporting of Section 6. A full metrics/distributed-tracing observability stack **should** be provided (see TR-ARC-12).
TR-ARC-12	Reference practices (recommended)	The following are **recommended ("should") reference practices**, not mandatory technology prescriptions: microservices decomposition; container packaging and orchestration (e.g., Kubernetes); **Infrastructure-as-Code (IaC)** with automated CI/CD pipelines; a durable message/event bus; and a full metrics/tracing observability stack. In all cases, deployment and configuration shall be **documented and reproducible**, with no undocumented manual configuration in any environment; the equivalent platform-level engineering practices of a SaaS / COTS OEM satisfy this requirement.

> **Mandatory —** The proposed architecture shall be a **multi-tenant-capable** design able to serve the University and its **affiliated colleges** through logically segregated data domains, so that onboarding a new affiliated college does not require code changes (see also TR-PRF-06).

5.2 Reference Technical Architecture

The reference logical architecture depicted below is **indicative**. The Bidder may propose an equivalent or superior architecture — including a multi-tenant SaaS / COTS platform architecture — provided it fully honours the outcome principles in 5.1; any deviation from the reference shall be explained in the Technical Proposal.

The reference architecture comprises four tiers: (a) **client tier** (browser and mobile apps); (b) **edge tier** (API gateway and load balancer, fronted by WAF/DDoS protection); (c) **services tier** (domain services, with an asynchronous message/event backbone where proposed); and (d) **data tier** (relational database, distributed cache, and object storage), with cross-cutting integration to external systems including the **SBIePay** payment gateway.



> **Reference —** In the reference architecture, the domain service groups map to the individual microservices as follows: **Academic Services** = Student, Admission and Examination services; **Corporate Services** = Finance and HR/Payroll services; **Sports Services** = Athlete and Facility services; **Platform Services** = Notification and Workflow services. The Bidder may propose a finer or coarser service decomposition provided the principles of clause 5.1 are met.

Req ID	Requirement
TR-ARC-13	All inbound traffic shall traverse the edge tier (WAF → load balancer → API gateway); no service shall be directly exposed to the public Internet.
TR-ARC-14	The relational data tier shall run in a **highly-available** configuration — a managed cloud database service with **multi-AZ automated failover** (or an equivalent primary/replica configuration) — consistent with TR-HOS-03.
TR-ARC-15	A **distributed cache** (e.g., Redis) shall externalise session state and cache high-read master data to meet the performance targets of 5.8.
TR-ARC-16	All unstructured artefacts (documents, certificates, photographs, admit cards, athlete media) shall be persisted in **S3-compatible object storage** (AWS S3 / Azure Blob / MinIO), with server-side encryption.

Req ID	Requirement
TR-ARC-17	Asynchronous processing (notifications, reconciliation events, audit events) shall be **reliable as an outcome**: no accepted event shall be silently lost, with at-least-once processing and dead-letter/exception handling. A durable **message/event bus should** be used where consistent with the proposed platform (see TR-ARC-12); equivalent platform-level queuing/background-job mechanisms are acceptable.
TR-ARC-18	The reference architecture in this sub-section supersedes and formally expands the indicative diagram; the Bidder shall submit a detailed deployment (physical) architecture diagram in the Technical Proposal, mapping each logical component to the proposed cloud services.

> **Note — SaaS / COTS equivalence.** For SaaS / multi-tenant COTS proposals, the architecture, hosting, environment, monitoring and security-testing requirements of this Section are satisfied by the **platform-level equivalents**: a shared multi-tenant deployment on a MeitY-empanelled / AWS / Azure / GCP cloud region in India, with logical tenant isolation, the OEM's platform-level HA, backup, security testing and certifications, and the tenant-level controls specified herein. The Bidder shall map each such requirement to its platform equivalent in the Technical Compliance Sheet (Annexure G).

5.3 Technology, Browsers & Standards

Req ID	Requirement
TR-TEC-01	The solution shall be **web-based** and **browser-agnostic**, rendering and functioning correctly on the current and immediately-preceding major versions of **Google Chrome, Mozilla Firefox, Apple Safari, and Microsoft Edge**.
TR-TEC-02	Web interfaces shall be **responsive**, adapting to desktop, laptop, tablet, and mobile viewports without loss of functionality.
TR-TEC-03	The **responsive web / Progressive Web App (PWA)** channel shall be the **mandatory primary channel** for all user journeys. In addition, the solution shall provide **one cross-platform hybrid mobile application built from a single codebase** (Flutter / React Native / Capacitor or equivalent), covering the priority journeys — notifications, attendance, fee payment, results, and facility booking — published under the University's developer accounts: **Android at Go-Live (mandatory)**; **iOS within 6 (six) months of Go-Live (desirable)**.
TR-TEC-04	The solution shall be built on **open standards** (HTTP/HTTPS, HTML5, JSON, OAuth 2.0 / OIDC, SAML 2.0, SMTP, ICS, etc.) and shall avoid any dependency that creates **proprietary vendor lock-in** for the University.
TR-TEC-05	The Bidder shall disclose the complete technology stack (languages, frameworks, runtime, database, cache, container platform, and all third-party/OSS components with their licences). All open-source components shall carry OSI-approved, non-viral licences compatible with the University's ownership and escrow rights in Section 9 (Terms and Conditions).

Req ID	Requirement
TR-TEC-06	The solution shall not require the installation of proprietary browser plug-ins, ActiveX controls, or unsupported client runtimes.
TR-TEC-07	The solution shall support **Unicode (UTF-8)** end-to-end, including storage, processing, search, and printing of Gurmukhi (Punjabi), Devanagari (Hindi), and Latin scripts (see 5.9).
TR-TEC-08	Date, time, currency, and number formats shall follow Indian conventions (IST / UTC+05:30, INR ₹, Indian digit grouping) and shall be configurable.
TR-TEC-09	The mobile application **should** support secure offline data capture for **attendance marking**, with synchronisation on reconnection; in all cases the mobile application shall enforce the same security controls as the web application.
TR-TEC-10	The database platform shall be an enterprise-grade **RDBMS (PostgreSQL or MySQL)** or superior; the Bidder shall state the exact product and edition and confirm it is licence-compliant for the full 5-year term at no additional cost to the University beyond the quoted TCO.

5.4 Hosting, Data Residency & Infrastructure

Req ID	Requirement
TR-HOS-01	The solution shall be deployable on **AWS, Microsoft Azure, Google Cloud Platform (GCP), or a Government-of-India-empanelled cloud service provider under the MeghRaj / GI Cloud initiative**. The Bidder shall name the proposed CSP and region(s).
TR-HOS-02	**ALL data** (production, replica, backup, DR, logs, and analytics) shall be stored and processed **within the territorial boundaries of India**, in data centres compliant with **MeitY (Ministry of Electronics and Information Technology)** guidelines and, where applicable, empanelled under MeitY's cloud empanelment. No data shall be replicated, cached, or backed up to any location outside India.
TR-HOS-03	The production environment shall run on **managed cloud services** within an Indian region, with the production database deployed in a **multi-AZ configuration with automated failover**, such that there is **no single point of failure at the managed-service level** across compute, network, database, or storage tiers.
TR-HOS-04	Disaster Recovery shall be provided through **encrypted daily backups with point-in-time recovery**, replicated to a **second cloud region within India**, from which the service can be restored within the objectives of TR-HOS-05.
TR-HOS-05	The solution shall meet a **Recovery Time Objective (RTO) ≤ 24 hours** and a **Recovery Point Objective (RPO) ≤ 4 hours** for all critical services and data. During **notified admission, examination and result-publication windows**, an **RPO ≤ 1 hour** shall apply, achieved via point-in-time recovery.

Req ID	Requirement
TR-HOS-06	**Automated daily backups** shall be taken of all databases, object storage, and configuration, retained per an agreed schedule (with a documented retention/rotation policy) and stored encrypted within India.
TR-HOS-07	The Bidder shall conduct **at least one backup-restore drill per year**, restoring from backup into a non-production environment, and shall furnish a **written drill report** evidencing achievement of the stated RTO/RPO.
TR-HOS-08	The Bidder shall provide logically segregated environments appropriate to the deployment model. For **SaaS / multi-tenant COTS deployments**, **Production plus one combined UAT/sandbox tenant** — configured to reasonably mirror Production and also serving the integration-testing needs of 5.10 — shall suffice; separate Development environments remain the Bidder's internal concern. For bespoke deployments, segregated **Development, UAT, and Production** environments shall be maintained, with UAT configured to mirror Production.
TR-HOS-09	Production data shall not be copied into non-production environments unless irreversibly **masked/anonymised**; the Bidder shall implement and document data-masking for test data.
TR-HOS-10	The solution shall support **zero-downtime / rolling deployments**; planned maintenance shall be scheduled in agreed low-traffic windows and shall count against the availability SLA only as permitted by Section 6 (Project Management and Implementation).
TR-HOS-11	Network architecture shall implement segmentation (public/private/data subnets), security groups, and least-privilege firewalling; administrative access shall be via bastion/jump-host with MFA only.
TR-HOS-12	The solution shall meet the **Uptime SLA of 99.5% monthly, measured at the application layer**, as defined in the SLA framework of Section 6.
TR-HOS-13	The Bidder shall size the infrastructure for the concurrency and volumetrics of 5.8, and shall provide a capacity/sizing model that scales with the addition of affiliated colleges and growth in enrolment over the contract term.
TR-HOS-14	On expiry or termination, the Bidder shall hand over all data and artefacts within India in open, documented formats and shall securely and verifiably destroy University data from all Bidder-controlled infrastructure per the exit provisions of Section 9.

> **Important —** Any storage, transit, or processing of University data outside India, at any time and for any purpose (including telemetry, support tooling, third-party SaaS sub-processors, or CDN edge caching of personal data), is strictly prohibited unless expressly permitted in writing by the University and lawful under the DPDP Act, 2023. The Bidder shall disclose all sub-processors and their locations.

5.5 Security & Compliance

The solution shall implement defence-in-depth security controls across application, data, infrastructure, and operations. Security is a continuous obligation for the full contract term and is subject to independent audit.

Req ID	Control	Requirement
TR-SEC-01	Encryption in transit	All data in transit shall be encrypted using **TLS 1.2 or higher** (TLS 1.3 preferred); insecure protocols (SSL, TLS 1.0/1.1) shall be disabled. HSTS shall be enforced.
TR-SEC-02	Encryption at rest	All data at rest — databases, backups, object storage, and log stores — shall be encrypted using **AES-256** or stronger.
TR-SEC-03	Authentication & SSO	The solution shall support **Single Sign-On (SSO)** via SAML 2.0 / OAuth 2.0 / OIDC and integrate with the University's identity provider/directory.
TR-SEC-04	Multi-Factor Authentication	**MFA** shall be enforced for all privileged/administrative accounts and shall be configurable for other roles (OTP over SMS/email and TOTP authenticator app, at minimum).
TR-SEC-05	Role-Based Access Control	**RBAC** with the principle of least privilege shall govern all access; roles, permissions, and data-scope shall be administrator-configurable and fully auditable.
TR-SEC-06	Password policy	Configurable password policy: minimum length and complexity, history, expiry, account lockout on repeated failures, and secure salted hashing (e.g., bcrypt/Argon2/PBKDF2). Passwords shall never be stored or logged in clear text.
TR-SEC-07	Session policy	Configurable session timeout, idle logout, concurrent-session control, secure/HttpOnly/SameSite cookies, and server-side session invalidation on logout and privilege change.
TR-SEC-08	Secure coding — OWASP	The solution shall be developed in accordance with **OWASP Top-10** and OWASP ASVS secure-coding practices, protecting against injection, XSS, CSRF, SSRF, insecure deserialization, broken access control, and related classes.
TR-SEC-09	Input validation & output encoding	All inputs shall be validated server-side and outputs contextually encoded; file uploads shall be type/size-restricted and malware-scanned.
TR-SEC-10	Audit trails	The solution shall maintain **comprehensive, tamper-evident audit trails** of all administrative, financial, examination, and data-modification actions (who, what, when, before/after, source IP), retained for a configurable period and exportable for inspection. Audit logs shall be immutable to application users.
TR-SEC-11	ISO/IEC 27001 controls	The solution and the Bidder's delivery/operations shall implement **ISO/IEC 27001:2022 (ISMS)** controls; the Bidder shall hold a valid ISO/IEC 27001 certification (per Section 2 eligibility).

Req ID	Control	Requirement
TR-SEC-12	DPDP Act, 2023	The solution shall comply with the **Digital Personal Data Protection Act, 2023** and rules thereunder — lawful processing, purpose limitation, data-principal rights (access/correction/erasure), consent management, breach notification, and data-minimisation. The Bidder shall act as a Data Processor under a Data Processing Agreement.
TR-SEC-13	Secrets management	All secrets (keys, credentials, tokens, certificates) shall be held in a dedicated **secrets manager / vault** (e.g., HashiCorp Vault, AWS/Azure/GCP KMS + Secrets Manager). No secret shall be hard-coded, committed to source control, or written to logs. Key rotation shall be supported.
TR-SEC-14	Web Application Firewall	A **WAF** shall protect all public endpoints against OWASP-class attacks, with tuned rulesets and virtual patching.
TR-SEC-15	DDoS protection	The solution shall be protected by **network- and application-layer DDoS mitigation** at the CSP/edge.
TR-SEC-16	Vulnerability & patch management	Continuous vulnerability scanning of code, containers, and dependencies (SAST/DAST/SCA) shall be performed, and security patches applied within risk-based SLAs.
TR-SEC-17	Logging, monitoring & alerting	Security events shall be centrally logged and monitored using **CSP-native centralised logging, monitoring and alerting services** (e.g., AWS CloudWatch / Azure Monitor / Google Cloud Operations) or equivalent, with alerting on anomalous/privileged activity; log integrity shall be protected and logs retained for the periods required by the DPDP Act, 2023, audit obligations, and Section 6.
TR-SEC-18	Incident response & data isolation	The Bidder shall operate a documented **security incident-response** process (with defined breach-notification timelines to the University and CERT-In as required), and shall ensure logical isolation of University data from any other tenant/customer.

> **Mandatory —** The University reserves the right to appoint its own CERT-In empanelled auditor to independently verify security posture at any time; the Bidder shall extend full cooperation and access.

5.6 Payment Gateway Integration — SBIePay

The University collects fees, charges, fines, and other receipts online through **SBIePay (State Bank of India ePay)**, the Bank's payment aggregator. The ERP's Finance/Fee module (see Section 4) shall integrate with SBIePay as the primary payment aggregator in accordance with the SBIePay integration specification and the technical/security pre-conditions stipulated by the Bank. This sub-section is normative and enforceable.

> **Reference —** The integration shall conform to the SBIePay merchant/aggregator integration kit and the State Bank of India information-security requirements referenced in TR-PAY-16 and TR-PAY-17. In case of any conflict, the Bank's then-current specification and the University's instructions shall prevail.

5.6.1 SBIePay Functional & Technical Requirements

Req ID	Requirement
TR-PAY-01	The solution shall integrate with SBIePay using the **Aggregator-Hosted (redirect) model**, whereby the payer is securely redirected to the SBIePay-hosted payment page to choose the payment instrument and complete payment, and is returned to the ERP with the transaction outcome.
TR-PAY-02	The solution shall implement the SBIePay **Double-Verification / Status-Query API** to independently verify the true status of every transaction with SBIePay, and shall treat the Bank-confirmed status as authoritative over any client/browser response.
TR-PAY-03	The solution shall support the SBIePay **Push-Response mechanism**, whereby SBIePay asynchronously posts the transaction result to a registered ERP endpoint, in addition to the browser return response; the ERP shall reconcile push, return, and status-query results.
TR-PAY-04	The solution shall support **Delivery-versus-Payment (DVP)** settlement, holding/settling the transaction based on confirmed payment, with a **configurable DVP timeout** after which unconfirmed transactions are handled per the configured rule (auto status-query, mark pending, or void).
TR-PAY-05	The solution shall implement the SBIePay **Refund / Cancellation API** supporting both **full and partial** refunds, with maker-checker authorisation, complete audit trail, and linkage of each refund to its original transaction.
TR-PAY-06	The payment **request and response** payloads, the **Double-Verification/Status-Query** calls, and the **Refund** calls shall be secured using **asymmetric (public/private) key-pair encryption** as specified by SBIePay: the ERP shall encrypt/sign requests with the Bank-provisioned keys and verify Bank responses using the Bank's public key, with the ERP's private key held only in the secrets vault (TR-SEC-13).
TR-PAY-07	All communication with SBIePay shall use **TLS 1.2 or higher**.
TR-PAY-08	Every request/response shall carry a **SHA-256 checksum/hash** for integrity, computed and verified per the SBIePay specification; any checksum mismatch shall cause the transaction to be rejected and flagged.
TR-PAY-09	**PCI-DSS scope minimisation:** the solution **shall NOT store, log, or process** the card number (PAN), cardholder name, card expiry date, CVV/CVV2, full magnetic-stripe/track data, or Sensitive Authentication Data (SAD). Card data shall be captured solely on the SBIePay-hosted page and shall never transit or persist in University/Bidder systems.
TR-PAY-10	The solution shall persist only permissible transaction references (e.g., ATRN/order ID, merchant reference, amount, status, instrument type, masked/last-4 where returned by the Bank, timestamps) for reconciliation and audit.

Req ID	Requirement
TR-PAY-11	The solution shall generate **automated reconciliation** between ERP fee records, SBIePay transaction reports (MIS), and bank credit/settlement files, automatically flagging matched, unmatched, pending, and disputed transactions with an exception-handling workflow.
TR-PAY-12	The solution shall produce **settlement reports** and shall support both **single-account settlement** and **multi-account (split) settlement**, routing configurable fee heads to their designated University bank accounts.
TR-PAY-13	Every payment, verification, refund, and reconciliation event shall be recorded in a tamper-evident audit trail (TR-SEC-10), with idempotent handling (TR-ARC-10) to prevent duplicate charges or duplicate refunds on retries.
TR-PAY-14	The solution shall handle all SBIePay outcomes gracefully — success, failure, pending/awaited, timeout, and user-abandonment — presenting clear payer messaging and never double-debiting; a robust re-query/retry job shall resolve pending transactions automatically.
TR-PAY-15	Payment gateway endpoints, merchant IDs, keys, and DVP/timeout parameters shall be **configuration-driven** (TR-ARC-08) and environment-specific, with distinct credentials for UAT and Production, and shall be testable against the SBIePay UAT/sandbox before Production onboarding.

5.6.2 Bank Onboarding Pre-Conditions

> **Important —** As an explicit pre-condition to SBIePay onboarding and go-live, the solution (and its hosting) shall satisfy the State Bank of India's security due-diligence. The Bidder shall complete and evidence the following at its own cost, and shall not treat these as out of scope.

Req ID	Requirement
TR-PAY-16	The Bidder shall complete and submit the Bank's **Technical Information Security Format** (security questionnaire/self-assessment) and shall meet the security controls stipulated therein as a pre-condition to onboarding.
TR-PAY-17	The solution/website shall clear the Bank-mandated **Website Security Audit**, comprising **Vulnerability Assessment & Penetration Testing (VA/PT)** and an **ASV (Approved Scanning Vendor) scan**, with all required findings remediated, and a valid audit certificate furnished, **before** SBIePay onboarding and go-live. This is a requirement of the Bank as a pre-condition to go-live of the payment integration, which the Bidder shall satisfy at its own cost, in addition to and consistent with the security requirements of TR-SEC-01 to TR-SEC-18.
TR-PAY-18	The Bidder shall keep the above security certifications current for the full contract term (renewing on the Bank's/CERT-In's cycle) and shall promptly remediate any finding that could jeopardise the University's SBIePay merchant/aggregator arrangement.

5.6.3 SBIePay Payment Sequence



5.7 Other Integrations

The solution shall provide standards-based, secure, and configurable integrations with the external systems below. All integrations shall use the API and security controls of 5.5 and 5.10, shall be resilient to third-party downtime, and shall log all exchanges for audit.

Req ID	Integration	Requirement
TR-INT-01	Email gateway	Integration with SMTP / transactional email service providers for system, academic, and financial notifications, with delivery status tracking and templated, multilingual content.
TR-INT-02	SMS gateway	Integration with SMS gateway(s), including **DLT-compliant** sender IDs and templates as per TRAI regulations, for OTPs, alerts, and notifications.
TR-INT-03	Biometric attendance	Integration with **biometric attendance devices** (fingerprint and face-recognition) for student, staff, and athlete attendance, supporting standard device protocols/SDKs and real-time or batch synchronisation.
TR-INT-04	DigiLocker & NAD	Integration with **DigiLocker** and the **National Academic Depository (NAD)** for issuance and verification of certificates, mark-sheets, and academic credentials.
TR-INT-05	AISHE / UGC	Integration/interfacing with the **AISHE (All India Survey on Higher Education)** portal and **UGC** portals for statutory returns and data submission.

Req ID	Integration	Requirement
TR-INT-06	eKYC	**DigiLocker / Aadhaar-based eKYC** for identity verification during admission/enrolment **where lawful**, strictly in compliance with UIDAI regulations, the Aadhaar Act, and the DPDP Act, 2023, with explicit consent and data-minimisation.
TR-INT-07	State scholarship portals	Integration with **Punjab State and national scholarship portals** (e.g., NSP / DBT) for scholarship application, verification, and disbursement reconciliation.
TR-INT-08	IoT athlete monitoring	Integration with **IoT wearables and fitness/health devices** via API for **athlete performance and health monitoring** (heart rate, GPS/distance, load, recovery, etc.), feeding the Sports/Athlete module of Section 4.
TR-INT-09	Accounting / banking	Interfaces to the University's accounting system and bank for settlement/reconciliation files, in addition to the SBIePay flows of 5.6.
TR-INT-10	Payment aggregators (future)	The payment abstraction shall permit configuring additional/alternate aggregators in future without re-architecting, while SBIePay remains the primary aggregator.
TR-INT-11	Resilience & security	Every external integration shall use secured credentials from the vault (TR-SEC-13), enforce timeouts/retries/circuit-breakers (TR-ARC-10), and degrade gracefully when the third party is unavailable.
TR-INT-12	Extensibility	New integrations shall be addable through the API/webhook framework (5.10) and configuration, without changes to unrelated modules.
TR-INT-13	Digital signature & eSign	Integration with **Class-3 Digital Signature Certificates (DSC / USB crypto-token, PKCS#11)** and **Aadhaar-based eSign (CCA-licensed ESP)** for signing notes, drafts, approvals, office orders and issued letters in the e-Office module (**FR-EOFF-05**), and for signing statutory outputs elsewhere in the ERP. The solution shall verify signatures against the CCA India trust chain, embed a verifiable signature in the PDF artefact (PAdES or equivalent), and preserve long-term verifiability of signed records, in conformity with the **Information Technology Act, 2000** and CCA guidelines.

5.8 Performance & Scalability

Req ID	Requirement
TR-PRF-01	The solution shall be sized for **1,000 named daily active users**, shall sustain **500 concurrent active users** without degradation below the stated response targets, and shall provide **burst capacity of 1,000 concurrent users for up to 2 hours** during admission-list and result-publication events — via auto-scaling and/or pre-generated static result pages served through a CDN — with further growth via horizontal scaling (TR-ARC-06) and the capacity model (TR-HOS-13).

Req ID	Requirement
TR-PRF-02	Page/transaction response time shall be **≤ 3 seconds at the 95th percentile** under the specified concurrency, measured for interactive operations (excluding third-party/gateway latency and bulk report generation).
TR-PRF-03	The solution shall sustain **peak load events** — notably the **admission season and examination-result publication** — up to the burst level of TR-PRF-01, without outage or breach of the response target, using auto-scaling, caching, and/or static result pages served through a CDN.
TR-PRF-04	The Bidder shall conduct **load, stress, soak, and spike performance testing at 1,000 concurrent users** during UAT and furnish reports evidencing achievement of TR-PRF-01 to TR-PRF-03 before go-live.
TR-PRF-05	Long-running/bulk operations (result processing, payroll runs, bulk notifications, report exports) shall execute **asynchronously** without blocking interactive users.
TR-PRF-06	The solution shall scale to accommodate **growth in affiliated colleges**, enrolment, and data volume over the 5-year term, per the capacity model (TR-HOS-13), without architectural rework. Capacity expansion beyond the baseline volumetrics of TR-PRF-01 to onboard additional affiliated colleges or enrolment growth shall be effected as a **chargeable expansion** at the unit rates quoted in the Commercial Bid, under the change-control provisions of Section 6.
TR-PRF-07	The solution shall employ caching, connection pooling, query optimisation, indexing, and CDN (for static assets, within India) to meet performance targets efficiently.
TR-PRF-08	Performance and availability shall be continuously monitored (TR-ARC-11) with dashboards and alerting against the SLA thresholds of Section 6.

5.9 Accessibility & Usability

Req ID	Requirement
TR-ACC-01	All web interfaces shall conform to **WCAG 2.1 Level AA**, and mobile apps shall follow the equivalent platform accessibility guidelines.
TR-ACC-02	The solution shall comply with the **Guidelines for Indian Government Websites (GIGW)** and applicable RPwD Act accessibility norms.
TR-ACC-03	The user interface shall be **intuitive, consistent, and role-appropriate**, minimising clicks for common tasks and providing clear navigation, help, and error messaging.

Req ID	Requirement
TR-ACC-04	At Go-Live, the solution shall provide an **English** user interface with full **Unicode (UTF-8)** rendering, and **trilingual (English / Punjabi-Gurmukhi / Hindi)** output on printed certificates, receipts, and key public notices. The full trilingual user interface is a **Phase-2** item per FR-GEN-11 of Section 4 ("should" at Go-Live; mandatory if commissioned in Phase-2) (see TR-TEC-07).
TR-ACC-05	The design shall be **mobile-first / responsive**, ensuring full task completion on mobile devices for student, faculty, and athlete/coach journeys.
TR-ACC-06	Accessibility features shall include keyboard navigability, screen-reader compatibility (ARIA), sufficient colour contrast, resizable text, and accessible forms and error identification.
TR-ACC-07	The Bidder shall provide contextual help, user guides, and in-app assistance in the supported languages.
TR-ACC-08	Accessibility conformance shall be independently verifiable; the Bidder shall furnish a WCAG 2.1 AA / GIGW conformance statement and remediate reported non-conformities.

5.10 API & Interoperability

Req ID	Requirement
TR-API-01	The solution shall expose **documented RESTful and/or GraphQL APIs** for all major business capabilities, with machine-readable specifications (OpenAPI/Swagger for REST; schema/SDL for GraphQL).
TR-API-02	APIs shall be **versioned**, with a documented deprecation policy ensuring backward compatibility so that integrations are not broken by upgrades.
TR-API-03	The solution shall provide **webhooks / event subscriptions** enabling external systems to receive real-time notifications of defined events (e.g., payment confirmed, admission finalised, result published).
TR-API-04	APIs shall enforce **rate-limiting and throttling** per client/key to protect availability, with clear quota and error semantics.
TR-API-05	API access shall be secured via **OAuth 2.0 / OIDC / signed API keys**, scoped by least privilege, with per-client credentials from the vault.
TR-API-06	The Bidder shall provide a **sandbox / test environment** with representative test data and mock endpoints for the University and its integration partners to develop and certify integrations.
TR-API-07	API documentation shall be published on an accessible developer portal and kept current with each release.
TR-API-08	APIs shall support standard content types (JSON), consistent error models, pagination, filtering, and idempotency keys for state-changing operations.

Req ID	Requirement
TR-API-09	The solution shall support **bulk/batch data exchange** (secure file/SFTP or batch APIs) for high-volume interfaces such as reconciliation and statutory returns.
TR-API-10	All APIs and interfaces shall be owned by, and transferable to, the University consistent with the IPR/escrow provisions of Section 9, with no interoperability locked behind proprietary licences.

5.11 Data Migration — Technical Requirements

The Bidder shall migrate legacy data into the ERP as part of implementation. This sub-section states the technical requirements; the migration methodology, responsibilities, and sign-off gates are detailed in Section 6 (Project Management and Implementation).

Req ID	Requirement
TR-MIG-01	The Bidder shall migrate data from **legacy sources** including spreadsheets, existing/legacy applications, and **digitised paper records**, covering student, admission, finance, HR/payroll, examination, and sports/athlete data as scoped.
TR-MIG-02	The Bidder shall prepare a **Data Migration Plan** including source inventory, field-level **data-mapping** (source-to-target), transformation rules, sequencing, and a rollback strategy, for University approval before execution.
TR-MIG-03	The Bidder shall perform **data cleansing** — de-duplication, standardisation, correction of format/encoding errors (including Unicode/Gurmukhi normalisation), and handling of missing/invalid values — with an auditable log of changes.
TR-MIG-04	The Bidder shall perform automated **data validation** (schema, referential integrity, business-rule, and reconciliation-count checks) at extract, transform, and load stages, and shall report exceptions.
TR-MIG-05	The Bidder shall execute at least one, and preferably multiple, **mock/trial migration runs** in a non-production environment, with results reviewed by the University before the final cut-over run.
TR-MIG-06	Post-migration **reconciliation reports** shall evidence completeness and correctness (record counts, control totals, sample verification) against source systems.
TR-MIG-07	Migrated data shall be subject to formal **University sign-off** as a gate to go-live; no go-live shall occur on unverified migrated data.
TR-MIG-08	All migration tooling, scripts, and mappings shall be documented and handed over to the University, and shall not embed hard-coded secrets.
TR-MIG-09	Migration shall preserve data confidentiality throughout (encryption in transit/at rest, access control, and secure disposal of intermediate extracts), consistent with 5.4 and 5.5 and the DPDP Act, 2023.
TR-MIG-10	The Bidder shall provide a documented **cut-over plan** (with freeze window, roll-forward, and rollback) and shall maintain the legacy data in read-only reference form for an agreed period after go-live.

Note — The requirements of this Section 5 are cumulative with, and do not limit, the functional requirements of Section 4, the SLA and implementation obligations of Section 6, the commercial terms of Section 7, and the contractual conditions (IPR, escrow, data protection, exit) of Section 9. Where any requirement herein is stricter than a general provision elsewhere, the stricter requirement shall govern for technical compliance.

Section 6 — Project Management and Implementation

> **Note —** This Section defines the mandatory project-management, implementation, training, testing, Service-Level and Operations & Maintenance (O&M) obligations of the Bidder. It shall be read together with Section 3 (Scope of Work), Section 4 (Functional Requirements), Section 5 (Technical Requirements), Section 7 (Pricing and Payment Terms) and Section 9 (Terms and Conditions). In the event of any conflict, the more stringent obligation upon the Bidder shall prevail.

Section at a glance

Item	Summary
Delivery model	Phased, iterative, hybrid-Agile implementation with staged go-live
Implementation duration	**T0 (Kick-off) → Go-Live: up to 9 (nine) months**
Post-Go-Live term	**5 (five) years** Operations, Maintenance, Support & AMC
Uptime commitment	**99.5% per calendar month**, measured at the application layer (excluding pre-approved maintenance windows)
Liquidated Damages	**0.5% of delayed milestone value per week**, capped at **10%** of contract value
Governance	University PMU / Steering Committee and Bidder core team; joint change control
Acceptance	Sign-off gates at SRS/BBP, SIT, UAT, Bank Website Security Audit clearance (TR-PAY-17), Go-Live and Final Acceptance (FAT)

6.1 Implementation Methodology

PM-MTH-01. The Bidder shall adopt a proven, documented implementation methodology based on an **Agile or hybrid-Agile** delivery model, executed in an **iterative and incremental** manner with **phased module go-live** permitted. Purely sequential (rigid single-shot waterfall) delivery is **not** acceptable.

PM-MTH-02. The methodology shall combine the discipline of a phase-gated lifecycle (defined milestones, deliverables and formal sign-off gates as per clauses 6.2 and 6.7) with the responsiveness of iterative development (time-boxed sprints/iterations, regular working-software demonstrations, and continuous stakeholder feedback).

PM-MTH-03. The Bidder shall, within **fifteen (15) working days** of the Letter of Award (LoA) / T0, submit a **Project Management Plan (PMP)** for the University's approval, covering at minimum: work-breakdown structure (WBS), detailed micro-plan/schedule, sprint/iteration plan, resource-loading and staffing calendar, communication plan, risk & issue register, quality-management plan, configuration- and change-management plan, and a RACI matrix.

PM-MTH-04. The Bidder shall conduct **fortnightly progress reviews** and **monthly Steering-Committee reviews**, and shall maintain a single shared project workspace/tracker (issue log, decision log, risk register,

action items) accessible to the University Project Management Unit (PMU) throughout the engagement.

PM-MTH-05. All requirements, design elements, test cases and deliverables shall be **traceable** through a **Requirements Traceability Matrix (RTM)** maintained from SRS/BBP sign-off to Final Acceptance, using the requirement identifiers defined in Section 4 and Section 5.

> **Important —** The methodology proposed in the Technical Bid forms part of the evaluated response under criterion **T4** (technical architecture, security, data-migration & implementation methodology) of the QCBS Technical Evaluation Matrix (Section 8) and, once accepted, becomes contractually binding.

6.2 Implementation Phases

PM-PHS-01. The implementation shall be executed through the phases set out below. Phases may overlap where the Agile/iterative model permits, but each phase shall culminate in the stated Outputs/Deliverables, which are subject to University review and acceptance.

Phase	Key Activities	Outputs / Deliverables
P1. Initiation & Planning	Team mobilisation; project charter; kick-off workshop; governance & communication setup; environment & tooling readiness; baseline schedule & risk register	Project Charter; approved **Project Management Plan (PMP)**; WBS & micro-plan; RACI; risk & communication plan; RTM shell
P2. Requirement Study & SRS / Business Blueprint	As-is study; stakeholder workshops per module suite; to-be process mapping; gap-fit analysis; finalisation of functional & technical requirements	**Signed-off SRS / Business Blueprint (BBP)**; process maps; gap-fit register; configuration decisions; updated RTM
P3. Solution Design	Architecture design; high- & low-level design; database & data model; UI/UX design; integration & interface design; security-by-design	**HLD**, **LLD**, data model, UI/UX prototypes, **Interface Control Documents (ICD)**, security design document
P4. Development / Configuration	Iterative build/configuration in time-boxed sprints; unit testing; code reviews; sprint demos; build & release automation	Working, unit-tested modules per sprint; build/deployment scripts; sprint demo records; developer documentation
P5. Integrations	Build & configure integrations — payment gateway **SBIePay**, SMS/e-mail, DigiLocker/UIDAI where applicable, government/statutory portals, biometric/attendance, LMS and similar	Configured & tested interfaces; ICD closure; integration test evidence
P6. Data Migration	Legacy data discovery; cleansing; mapping; extract-transform-load (ETL); mock migrations; reconciliation & validation	**Data-Migration Plan**; cleansed datasets; migration scripts; mock-run reports; reconciliation & sign-off certificate
P7. System Integration Testing (SIT)	End-to-end integrated testing across modules & interfaces; defect logging & closure; regression testing	SIT test plan, test cases, execution & defect reports; SIT exit report

Phase	Key Activities	Outputs / Deliverables
P8. User Acceptance Testing (UAT)	UAT environment provisioning; test-case walkthrough; business-scenario validation by University users; defect triage & fixes	UAT test plan & scripts; UAT defect log; **UAT Sign-off Certificate**
P9. Training	Train-the-Trainer; role-based end-user training; e-learning content; manuals & material distribution	Training plan & calendar; user & admin manuals; e-learning modules; attendance & assessment records
P10. Go-Live / Cutover	Cutover plan & rehearsal; production deployment; final data migration; smoke testing; rollback readiness	Cutover/rollback plan; production environment; go-live checklist; **Bank Website Security Audit clearance certificate (TR-PAY-17)**; **Go-Live Certificate**
P11. Hypercare / Stabilisation	Intensive on-site/remote support; floor-walking; rapid defect resolution; performance tuning; knowledge transfer	Hypercare exit report; as-built documentation; **Final Acceptance (FAT) Certificate**

PM-PHS-02. Phased go-live of module suites (as grouped in Section 4) is acceptable, provided each go-live tranche independently satisfies the SIT/UAT/security acceptance gates of clause 6.7 and does not degrade the availability or integrity of previously commissioned modules.

PM-PHS-03. The successful sign-off of key phase deliverables is directly linked to the payment milestones set out in Section 7 (Pricing and Payment Terms).

6.3 Project Timeline

PM-TML-01. The Bidder shall complete the full implementation — from Kick-off (**T0**) to production **Go-Live** — within a period **not exceeding nine (9) months**, followed by a hypercare/stabilisation period and a **five (5)-year** Operations, Maintenance, Support & AMC term as per the contract structure defined in Section 1 and Section 7.

PM-TML-02. The indicative master schedule is depicted below. The Bidder shall submit a detailed, dated micro-plan during Phase P1; the dates below are relative to T0 (contract kick-off) and are indicative for bid-response purposes.



> **Note —** The Gantt chart above is indicative. Overlap of Development, Integrations, SIT and Training reflects the hybrid-Agile model. The Operations, Maintenance & AMC bar represents the continuous 5-year O&M term commencing at Go-Live and running concurrently with, then beyond, the hypercare period.

PM-TML-03. Delay in achieving any milestone attributable to the Bidder shall attract **Liquidated Damages of 0.5% of the delayed milestone value per week (or part thereof)**, subject to an aggregate cap of **10% of the total contract value**, as elaborated in Section 7 and Section 9.

6.4 Project Governance and Team

6.4.1 University-side governance

PM-GOV-01. The University shall constitute a two-tier governance structure:

1. **Project Steering Committee (PSC)** — chaired by a senior officer nominated by the Registrar, comprising the Project Sponsor, functional heads and the Bidder's Project Manager (in attendance). The PSC provides strategic direction, approves scope-change requests, resolves escalations, and formally accepts major milestones.
2. **Project Management Unit (PMU)** — the University's day-to-day counterpart team, including a University Project Coordinator, module owners/functional SPOCs, and the IT/infrastructure lead. The PMU reviews deliverables, coordinates UAT and training, and manages business readiness.

6.4.2 Bidder-side team

PM-GOV-02. The Bidder shall deploy a **two-tier project team**: (a) a **core team deployed full-time for the implementation phase**, led by a full-time **Project Manager** who shall be the single point of accountability to

the University; and (b) **named specialist resources** engaged part-time (minimum **20% allocation** during the phases relevant to their role), as set out in clause 6.4.3. Key personnel shall not be substituted without the University's prior written consent; any replacement shall be of **equal or higher** qualification and experience.

PM-GOV-03. The governance and reporting relationships are depicted below.



6.4.3 Key personnel

PM-GOV-04. The Bidder shall provide, at minimum, the key personnel set out below, structured in two tiers. CVs shall be submitted in the format at the Annexure (team/CV format) and are evaluated under criterion **T5** of the Technical Evaluation Matrix (Section 8).

(a) Core team — deployed full-time for the implementation phase:

Role	Minimum Qualification	Minimum Experience	No.
Project Manager (may also act as Functional Lead)	B.E./B.Tech/MCA/MBA	7 years IT/ERP; ≥ 2 years as PM of full-lifecycle ERP/campus implementations	1
Functional / Implementation Consultants	Graduate/PG in relevant discipline	4 years in ERP / higher-education functional consulting — academics, finance, HR, admissions and similar	2
Technical / Integration Engineer	B.E./B.Tech/MCA	4 years across the proposed technology stack, API/middleware & payment-gateway integrations (including gateways such as **SBIePay**) and data migration/ETL & reconciliation	1

(b) Named specialist resources — part-time, with a minimum 20% allocation during the phases relevant to their role:

Role	Minimum Qualification	Minimum Experience	No.
Solution Architect	B.E./B.Tech/MCA/M.Tech	6 years; ≥ 2 years architecting enterprise/ERP solutions	1
Security Specialist (Information Security / Data Protection)	B.E./B.Tech/MCA	6 years in application security & compliance (ISO/IEC 27001, DPDP Act 2023)	1

Role	Minimum Qualification	Minimum Experience	No.
QA / Test Lead	B.E./B.Tech/MCA	6 years in software QA, SIT/UAT management & test automation	1

(c) Post-award nominated roles — not bid-stage named personnel. The following roles are **not** required to be named, and no CV is required for them, at the bid stage. They remain **binding obligations of the Successful Bidder** and shall be nominated in writing, with CVs meeting the stated minima, for the University's acceptance before commencement of the phase relevant to each role. Substitution is subject to the same conditions as apply to named specialist resources.

Role	Minimum Qualification	Minimum Experience	No.	Nominate by
Training Lead	Graduate/PG	6 years in end-user training, courseware & change management for enterprise rollouts	1	Commencement of the training phase
Support Lead	B.E./B.Tech/MCA	6 years in application support, helpdesk & SLA-based service delivery	1	Go-Live

For the avoidance of doubt, the obligations attaching to these roles elsewhere in this RFP are **unaffected** — in particular, the **Support Lead** remains the level **L2** escalation point in the SLA escalation matrix and shall be available full-time from Go-Live throughout the O&M term (and may be a shared / help-desk resource), and the **Training Lead** remains responsible for the training and capacity-building deliverables.

> **Mandatory —** The **Project Manager** shall be **on the Bidder's own payroll** (not sub-contracted), shall remain deployed full-time for the implementation phase, and shall not be substituted without the University's **prior written consent**. Documentary proof (PF/ESI/appointment) shall be furnished on demand. Named specialist resources may be **OEM or contracted staff**, subject to express disclosure of the engagement basis in Annexure H. The **Support Lead** (nominated post-award under (c) above) shall be available full-time from Go-Live through the O&M term and may be a **shared/help-desk resource**.
>
> **Note —** The two-tier roster above is the authoritative key-personnel list referenced by PQ-7 (Section 2), Rubric T5 (Section 8) and Annexure H (Section 10). Roles may be combined in one individual where the competencies demonstrably overlap — in particular, the Project Manager may double as Functional Lead — **except that the Project Manager and the QA / Test Lead shall be distinct individuals**. MSEs and DPIIT-recognised Startups (Clause 2.2A of Section 2) may propose consultant / contracted specialists for any of the named specialist (part-time) roles, with express disclosure of the engagement basis in Annexure H.

6.5 Deliverables and Documentation

PM-DOC-01. The Bidder shall prepare, maintain and hand over the deliverables listed below. All documents shall be version-controlled, delivered in editable source format and PDF, and become the property of the University (subject to the IPR/source-code and escrow provisions of Section 9).

#	Deliverable	Phase
D-01	Project Management Plan (PMP), WBS, micro-plan, risk & communication plan	P1
D-02	**Software Requirements Specification (SRS) / Business Blueprint (BBP)**	P2
D-03	Requirements Traceability Matrix (RTM) — maintained to FAT	P2–P11
D-04	**High-Level Design (HLD)** and **Low-Level Design (LLD)**	P3
D-05	Database schema / data-dictionary; data model	P3
D-06	**Interface Control Documents (ICD)** for all integrations	P3, P5
D-07	Security design & compliance document (ISO/IEC 27001 / DPDP Act 2023 alignment)	P3
D-08	**Data-Migration Plan** and reconciliation reports	P6
D-09	Test plans, test cases, execution logs & reports (Unit, SIT, UAT, performance, accessibility)	P4–P8
D-10	**User Manuals** and **Administrator/Operations Manuals** (role-based)	P9
D-11	Training material, e-learning content & assessment records	P9
D-12	**Source code, build scripts, configuration & deployment artefacts** (with escrow as per Section 9)	P10
D-13	Cutover & rollback plan; Go-Live checklist & Go-Live Certificate	P10
D-14	**As-built documentation** & system-configuration baseline	P11
D-15	Hypercare exit report; Final Acceptance (FAT) Certificate	P11
D-16	O&M/AMC service plan, SOPs, backup & DR runbooks	O&M

PM-DOC-02. No milestone shall be deemed complete, and no linked payment shall become due, until the associated deliverables have been submitted and formally accepted by the University PMU/PSC.

6.6 Training and Change Management

PM-TRN-01. The Bidder shall design and deliver a comprehensive, **role-based training and change-management programme** covering all user categories: administrative & finance staff, faculty, examination/academic staff, students, coaches/sports staff, IT administrators and University management.

PM-TRN-02. The programme shall include:

1. **Train-the-Trainer (ToT):** structured training of a nominated University core team so that the University can independently train new/incremental users after handover.
2. **Role-based end-user training:** module- and role-specific hands-on sessions on a training environment loaded with representative data.
3. **Administrator/technical training:** system administration, configuration, security, backup/restore and troubleshooting for University IT staff.

4. **E-learning:** self-paced modules, recorded walkthroughs and video tutorials accessible through the system/LMS.
5. **Documentation:** role-based user manuals, quick-reference guides, admin manuals and FAQs, in printable and online form.
6. **Floor-walking at Go-Live:** on-site hand-holding and desk-side support during the initial go-live/hypercare period.

PM-TRN-03. The Bidder shall implement a **change-management and adoption plan** including stakeholder communication, awareness campaigns, readiness assessment, and **adoption tracking** (usage/log-in metrics, transaction volumes, help-ticket trends) reported monthly through the hypercare and early O&M period until agreed adoption thresholds are met.

PM-TRN-04. Training effectiveness shall be measured through attendance records and post-training assessments; the University may require re-delivery, at no additional cost, of any session where assessment outcomes fall below the agreed threshold.

6.7 Testing and Acceptance

PM-TST-01. The Bidder shall define and execute a multi-level test strategy, with formal **sign-off gates** at each level. No phase shall progress until its exit criteria are met and evidence is accepted by the University.

Test level	Objective	Responsibility	Gate / Exit criterion
Unit Testing	Verify individual components/modules	Bidder	100% of planned unit tests executed; no open Critical/High defects
System Integration Testing (SIT)	End-to-end integrated flows across modules & interfaces	Bidder (witnessed by PMU)	All critical scenarios pass; zero open Critical/High defects; SIT exit report accepted
User Acceptance Testing (UAT)	Business validation against SRS/BBP	University users (Bidder support)	UAT scripts passed; **UAT Sign-off Certificate**; zero open Critical/High defects
Security Testing	Automated vulnerability scanning (SAST / DAST / SCA) and secure-configuration review	Bidder	No open High/Critical vulnerabilities; compliance with the Section 5 security requirements
Performance / Load Testing	Validate concurrency, response time & scalability	Bidder	Meets performance benchmarks in Section 5 under peak/projected load
Accessibility Testing	Conformance to accessibility standards (WCAG 2.1 AA / GIGW)	Bidder	Documented conformance; no blocking accessibility defects

PM-TST-02. Defects shall be classified by severity (Critical / High / Medium / Low) and tracked to closure in the shared defect log. **Go-Live shall not be approved while any Critical or High-severity defect remains**

open.

PM-TST-03. Final Acceptance (FAT) shall be granted only after: (a) successful Go-Live of all in-scope modules; (b) completion of data migration with reconciliation sign-off; (c) closure of hypercare with system stability demonstrated over the agreed stabilisation window; (d) furnishing of the Bank-mandated Website Security Audit clearance certificate required by **TR-PAY-17 of Section 5**; and (e) handover of all deliverables under clause 6.5 including as-built documentation and source code/escrow.

> **Important —** Acceptance by the University shall not relieve the Bidder of its warranty, SLA, or O&M obligations, nor of liability for latent defects.

6.8 Service Level Agreement (SLA)

PM-SLA-01. During the hypercare period and the entire **5 (five)-year** O&M/AMC term, the Bidder shall meet the Service Levels defined below. Service Levels are measured monthly and reported in the monthly service report.

PM-SLA-02. The Bidder shall guarantee a **system availability (uptime) of 99.5% per calendar month**, measured at the application layer, excluding pre-approved maintenance windows.

PM-SLA-03. Incident severity, response and resolution targets, and penalties for breach, are as follows. "Response" is the time to acknowledge and commence work; "Resolution" is the time to restore normal service (including an acceptable workaround, with a permanent fix to follow).

Severity	Definition	Response Time	Resolution Time	Penalty for breach
Critical (Sev-1)	System down or unusable; payment flow (e.g., SBIePay) broken; data loss/corruption; security breach — no workaround	**1 business hour** (4 hours outside business hours, via on-call telephone)	**8 hours** (restoration or acceptable workaround)	1.0% of quarterly O&M fee per hour of delay beyond target, up to 10% per incident
High (Sev-2)	Major function/module degraded or unavailable to many users; no acceptable workaround	**4 business hours**	**Next business day**	0.5% of quarterly O&M fee per hour of delay beyond target, up to 7.5% per incident
Medium (Sev-3)	Minor defect; function impaired for a subset of users; workaround available; moderate business impact	**1 business day**	**5 business days**	0.25% of quarterly O&M fee per day of delay beyond target, up to 5% per incident
Low (Sev-4)	Query, cosmetic defect or minor enhancement request; low/no business impact	**2 business days**	**10 business days** or next scheduled release	0.1% of quarterly O&M fee per day of delay beyond target, up to 2.5% per incident

> **Note — Aggregate SLA-penalty cap.** The aggregate of all SLA penalties / service credits levied in any quarter shall not exceed **10% of that quarter's O&M/AMC invoice value**. Where the cap is reached in **three (3) consecutive quarters**, the University may treat the persistent failure as a **material breach** for the purposes of Section 9 (termination for default). The same delay or breach shall not be penalised twice under both the Liquidated-Damages and SLA heads (see Section 7, Clause 7.8 and Section 9, Clause 9.10).

PM-SLA-04. Uptime penalty. For each **0.5% (or part thereof) shortfall** below the 99.5% monthly uptime commitment, a penalty of **1% of the quarterly O&M fee** shall be levied, subject to the aggregate SLA-penalty cap defined above. Sustained or repeated breach may constitute an event of default.

PM-SLA-05. Helpdesk & ticketing. The Bidder shall provide a **web-based helpdesk/ticketing portal** (with e-mail and telephone channels) for logging, tracking, escalating and reporting on incidents and service requests, accessible to authorised University users, with an automated SLA-clock, notifications and audit trail.

PM-SLA-06. Support window. Standard support shall be available on **University working days, 09:00–18:00 IST**. Outside this window, **Critical (Sev-1)** incidents may be reported through a published **on-call telephone number**, with the out-of-hours response target of clause PM-SLA-03. **Pre-scheduled extended coverage (including weekends)** shall be provided during **notified admission counselling, examination and result-publication windows**, and during go-live/cutover, as agreed in advance with the University PMU.

PM-SLA-07. Escalation matrix. The Bidder shall maintain and publish a named escalation matrix as below; the University reserves the right to escalate directly at any level.

Level	Bidder contact	University contact	Trigger
L1	Support Engineer / Helpdesk	Module SPOC	Ticket logged
L2	Support Lead	University Project Coordinator	Response/Resolution target at risk or breached
L3	Project Manager / Delivery Head	PMU Head	Repeated breach or Sev-1 unresolved within target
L4	Bidder's Senior Management	Registrar / PSC	Major/prolonged outage or default

6.9 Operations & Maintenance / AMC (5 Years)

PM-OAM-01. The Bidder shall provide comprehensive Operations, Maintenance, Support and AMC services for a period of **5 (five) years** commencing from Go-Live, paid **quarterly** as per the payment schedule in Section 7. The O&M scope shall include, at minimum:

1. **Corrective maintenance** — diagnosis and rectification of defects, bugs and failures within the SLA targets of clause 6.8.
2. **Adaptive maintenance** — modifications to keep the system operational amid changes to statutory/regulatory requirements, operating environment, browsers, OS, or integrated third-party systems (e.g., changes mandated by the payment aggregator **SBIePay**, UGC, or government portals).

3. **Preventive maintenance** — proactive health checks, log/performance monitoring, capacity review, housekeeping and tuning to pre-empt failures.
4. **Perfective maintenance** — usability, performance and functional refinements arising from operational feedback.
5. **Patch & security management** — timely application of security patches, OS/middleware/framework updates and vulnerability remediation.
6. **Minor enhancements** — accommodation of an agreed quantum of minor change requests (e.g., new reports, forms, workflow tweaks) within the O&M effort; major enhancements to be handled through change control (Section 7 and Section 9).
7. **Version upgrades** — supply and deployment of product/platform version upgrades, security releases and roll-ups to keep the system on a supported version throughout the term, at no additional licence cost.
8. **Database administration** — DB tuning, indexing, archival/purging, integrity and growth management.
9. **Backup & DR monitoring** — verification of scheduled backups, restore drills, and DR readiness per Section 5, with periodic restoration testing.
10. **Security re-assessment** — continuous vulnerability scanning and risk-based patching in accordance with **TR-SEC-16 of Section 5**, and the incident-response obligations at **TR-SEC-18**.
11. **Quarterly service reviews** — formal governance reviews of SLA performance, incidents, risks, capacity, security posture and the enhancement backlog, with the University PMU/PSC.

PM-OAM-02. The Bidder shall provide **monthly service reports** (uptime, incident/SLA compliance, ticket ageing, backup/patch status, security posture) and **quarterly review reports**, and shall maintain up-to-date operational runbooks and SOPs throughout the O&M term.

> **Note —** All product licences, third-party subscriptions and platform components required to keep the system fully operational and supported for the entire 5-year term shall be included in the Bidder's 5-year Total Cost of Ownership (TCO) as quoted in the BOQ (Section 7). No additional charge shall be admissible on this account during the contract term.

6.10 Transition and Exit Management

PM-EXT-01. Upon expiry or termination of the contract, the Bidder shall provide **transition and exit-management** services to ensure continuity of operations and orderly handover to the University or its nominated successor agency, at no degradation of service.

PM-EXT-02. In brief, the Bidder shall: hand over all data (in open, documented formats), source code, configurations, credentials, documentation and knowledge; provide a documented exit/transition plan and a hand-holding/reverse-knowledge-transfer period; and continue services until effective transition. **The detailed transition and exit-management obligations, timelines, and the associated safeguards are set out in Section 9 (Terms and Conditions).**

6.11 Warranty and Post-Implementation Support Model

PM-WAR-01. The Bidder shall provide a **comprehensive warranty** covering the entire delivered solution — custom code, configuration, integrations and migrated data integrity — from the date of Go-Live. During the warranty period, all defects, non-conformities and failures shall be rectified by the Bidder at **no additional cost**, under the SLA targets of clause 6.8.

PM-WAR-02. Where the warranty period and the 5-year O&M/AMC term run concurrently, the more favourable obligation to the University shall apply; the O&M/AMC coverage of clause 6.9 shall in no case reduce the Bidder's warranty liability.

PM-WAR-03. The post-implementation support model shall comprise: (a) an initial **hypercare/stabilisation** period of intensive support immediately after Go-Live; (b) continuous **SLA-governed O&M support** through the helpdesk/ticketing portal for the 5-year term; (c) **named support personnel** including a Support Lead and Project Manager as escalation points; and (d) **on-site support** as required during critical operational cycles (admissions, examinations, fee collection, results and convocation).

PM-WAR-04. The Bidder shall warrant that, at handover, the system is free of malicious code, undocumented "back-door" access, and unauthorised third-party dependencies, and that all components are on vendor-supported, patchable versions consistent with the security requirements of Section 5.

> **Mandatory —** The obligations of this Section are enforceable through the Liquidated Damages, SLA penalties and Performance Bank Guarantee mechanisms defined in Section 7 and Section 9, and are integral to the University's acceptance of the delivered solution.

Section 7 — Pricing and Payment Terms

This Section prescribes the manner in which the Bidder shall quote its commercial offer, the mandatory format of the Bill of Quantities (BOQ), the basis on which the financial offer will be evaluated, the payment schedule linked to accepted deliverables, the treatment of taxes and statutory levies, and the penalties and liquidated damages applicable under the resulting Contract. This Section shall be read together with **Section 6 (Project Management and Implementation)** for Service Level Agreement (SLA) definitions, **Section 8 (Evaluation Criteria)** for the QCBS financial-scoring methodology, and **Section 9 (Terms and Conditions of Contract)** for the Performance Bank Guarantee and general commercial conditions.

> **Note —** All references in this Section to the "commercial bid", "financial bid", "price bid" or "Cover-2" mean the sealed, signed Financial Bill of Quantities uploaded as **Cover-2 (Financial Cover)** of the Two-Cover (Two-Bid) e-Tender on the **Punjab e-Procurement Portal (https://eproc.punjab.gov.in)**.

7.1 General Pricing Instructions

The following instructions are mandatory and govern the entire commercial offer. Non-compliance with any of them may render the bid liable to rejection.

Ref	Instruction
P-01	All prices shall be quoted in **Indian Rupees (INR / ₹) only**. Quotations in any other currency shall not be accepted.
P-02	Every price shall be quoted **both in figures and in words**. Where a figure and its corresponding words differ, **the amount stated in words shall prevail**.
P-03	All quoted prices shall be **inclusive of all costs** required to deliver, implement, operate, maintain and support the ERP System for the full Contract term — including but not limited to manpower, software, tools, licences, sub-licences, travel, boarding, lodging, documentation, third-party/OEM charges, consumables, insurance, bandwidth (where vendor-managed), overheads and margin — **except Goods and Services Tax (GST)**, which shall be shown separately as prescribed in **Clause 7.6**.
P-04	Quoted prices shall be **firm and fixed** for the entire Contract term (Implementation phase plus five (5) years of Operations, Maintenance, Support and AMC) and shall **not be subject to any escalation** on any ground whatsoever, save only for statutory changes in taxes and duties as provided in **Clause 7.7**.
P-05	**No financial figure, price, rate, discount, cost element or any indication of the commercial offer shall appear anywhere in the bid except in Cover-2 (Financial Cover).** Any disclosure of price information within Cover-1 (the Fee/EMD or Technical Cover), or within any technical document, presentation, brochure or covering letter, shall result in **summary rejection of the entire bid**.
P-06	The commercial offer shall be **unconditional**. Conditional, ambiguous, or assumption-laden prices (for example, prices contingent on quantities, exchange rates, or future events) shall not be accepted, and such bids are liable to be treated as non-responsive.

Ref	Instruction
P-07	The Bidder shall quote against **every line item of Part A and Part B** of the Bill of Quantities. A blank, dashed, or "included elsewhere / inclusive" entry against a mandatory Part A or Part B line item shall be construed as **the item being offered free of charge (₹0.00)** and the University shall be entitled to the deliverable at no additional cost, without any right of the Bidder to claim otherwise. **Part C rows are mandatory to quote and are evaluated on the University's fixed notional quantities**; a blank Part C rate shall be construed as ₹0.00 per man-day and shall bind the Bidder. Part D (Phase-2 Optional) rows are optional to quote; a blank Part D row means the item is not offered and shall not be read as ₹0.00.
P-08	Prices shall be quoted **exclusive of GST but inclusive of all other taxes, duties, cesses and statutory levies**. The Bidder shall not be entitled to any reimbursement on account of any tax, duty or levy that it has failed to include, other than GST.

Arithmetic-correction rule. In the event of any arithmetic error or inconsistency in the BOQ, the offer shall be corrected by the University in accordance with the following order of precedence, and the Bidder shall be bound by the corrected amounts:

1. Where the **unit price** and the **line total** differ, the **unit price shall prevail** and the line total shall be corrected — **unless** the evaluation committee judges there to be an obvious misplacement of the decimal point in the unit price, in which case the **line total shall prevail** and the unit price shall be corrected.
2. Where the amount stated **in figures** and the amount stated **in words** differ, the amount stated **in words shall prevail** — **unless** the amount in words is itself the product of an arithmetic error apparent on the face of the BOQ, in which case the amount as corrected under the other rules of this Clause shall prevail.
3. Where the **summation of the line items** differs from the stated **Grand Total**, the **corrected line-item sum shall prevail** over the stated Grand Total — whether that Grand Total is expressed in figures or in words — and the Grand Total shall be corrected accordingly.

This rule is identical to, and shall be read with, **Clause 8.7.2 of Section 8 (Evaluation Criteria)**, which governs in the event of any doubt.

> **Important —** If the Bidder does not accept the correction of errors made in accordance with the arithmetic-correction rule above, its bid shall be **rejected** and its Earnest Money Deposit (EMD) may be forfeited in accordance with **Section 2 (Instructions to Bidders)**.

7.2 Components of the Commercial Bid

The commercial offer shall be built up from the cost components set out below. Each component shall be classified as **One-time** (a non-recurring charge incurred during the Implementation phase) or **Recurring** (a charge repeating annually over the five (5) year post-Go-Live period). The Bidder shall map its solution — whether based on a **Custom-built**, **Commercial-Off-The-Shelf (COTS)** or **Software-as-a-Service (SaaS)** approach — onto these components, quoting ₹0.00 against any line that is genuinely not applicable to its chosen approach.

C#	Cost Component	Nature	Description
C1	**Software Licence / Subscription**	One-time or Recurring	Perpetual licence fees for COTS products, or annual SaaS/subscription charges, for all software required to deliver the functional and technical scope, sized for the full concurrent and named user base and all modules of **Section 4 (Functional Requirements)**. Where the model is subscription/SaaS, this is quoted as a recurring annual charge.
C2	**Implementation & Customisation**	One-time	Requirement study, System Requirements Specification / Business Blueprint, design, configuration, development, customisation, build, testing, UAT support, Go-Live and hypercare for all modules.
C3	**Data Migration**	One-time	Extraction, cleansing, transformation, validation, loading and reconciliation of all legacy and historical data into the ERP System, including migration tooling and dry-run cycles.
C4	**Third-Party Integrations, including SBIePay**	One-time	Design, development, testing and certification of all integrations, including the **SBIePay (State Bank of India ePay)** payment-gateway integration (Aggregator-Hosted model, Double-Verification/Status-Query, Refund/Cancellation, asymmetric-key encryption), SMS/e-mail gateways, biometric/attendance devices, DigiLocker/UGC/AISHE and any other interface specified in **Section 5 (Technical Requirements)**.
C5	**Training**	One-time	Role-based end-user training, administrator/train-the-trainer training, training material, user manuals and knowledge-transfer as specified in **Section 6**.
C6	**Hosting & Infrastructure**	Recurring × 5 years	Where hosting is **vendor-managed**, the annual charge for cloud/data-centre hosting, compute, storage, bandwidth, security, backup and Disaster Recovery (DR), data-resident in India, for each of the five (5) post-Go-Live years. Quote ₹0.00 for each year if hosting is University-provided.
C7	**Operations, Maintenance, Support & AMC**	Recurring × 5 years	Annual charge for corrective, adaptive, perfective and preventive maintenance, help-desk and support, patching, upgrades, SLA compliance and on-site/remote O&M for each of the five (5) post-Go-Live years, payable quarterly per **Clause 7.5**.
C8	**Change-Request Rate Card**	Evaluated on fixed notional quantities (per man-day, by role)	Blended per-man-day rates by role, used solely to price future out-of-scope change requests raised under the change-control procedure of **Clause 9.13 of Section 9**. As stated in **Clause 7.3** and **Clause 7.4**, Part C is **evaluated on the University's fixed notional quantities** and is **included** in the evaluated Total Cost of Ownership.

> **Note —** The classification of a component as One-time or Recurring, and the number of recurring years (five), is fixed by this RFP and shall not be altered by the Bidder. A Bidder offering a pure SaaS model shall reflect its subscription as a recurring charge under C1/B.1 and shall not double-count the same charge under C6 or C7.

7.3 Bill of Quantities (BOQ) Format

The Bidder shall submit its financial offer strictly in the format of the Bill of Quantities reproduced below. The BOQ is organised into four parts — **Part A (One-time costs)**, **Part B (Recurring costs)**, **Part C (Change-request rate card, evaluated on notional quantities)** and **Part D (Phase-2 Optional Items, not evaluated)** — followed by a **Grand Total** row that expresses the evaluated **5-Year Total Cost of Ownership (TCO)**.

> **Mandatory —** The machine-fillable version of this BOQ is issued as **Annexure I (Financial Bid / BOQ Format)** in the Excel/BOQ file published with this RFP on the University website / online tender portal, and **that machine-fillable version shall be the sole and exclusive basis of the financial evaluation** under **Section 8**. The table reproduced below is indicative of structure and content only; in the event of any conflict, the Annexure I BOQ prevails. The Bidder shall not add, delete, re-order, re-label or reformat any row or column of Annexure I.

Legend for the "Nature" column: OT = One-time; R = Recurring. The "Years" column indicates the multiplier applied to a recurring unit price (1 for one-time items; 5 for the five-year recurring items).

Part A — One-Time Costs

Sl	Cost Component	Nature (One-time / Recurring)	Unit / Qty	Unit Price (₹)	Years	Total Amount (₹)
A.1	Software Licence — perpetual COTS licences, all modules, full user base	One-time (OT)	Lot / 1		1	
A.2	Implementation & Customisation — study, SRS/BBP, build, configuration, testing, Go-Live, hypercare	One-time (OT)	Lot / 1		1	
A.3	Data Migration — extraction, cleansing, transformation, load, reconciliation	One-time (OT)	Lot / 1		1	
A.4	Third-Party Integrations incl. **SBIePay** payment gateway, SMS/e-mail, biometric, DigiLocker/UGC	One-time (OT)	Lot / 1		1	
A.5	Training — role-based end-user, administrator / train-the-trainer, manuals	One-time (OT)	Lot / 1		1	
	Sub-Total Part A — One-Time Costs (OT)					**= Σ A.1 … A.5**

Part B — Recurring Costs (per year × 5 years)

Sl	Cost Component	Nature (One-time / Recurring)	Unit / Qty	Unit Price (₹)	Years	Total Amount (₹)
B.1	Software Subscription / SaaS charge — only if the offer is subscription-based; else ₹0.00 — the five recurring years are the five years post-Go-Live; subscription / licence / environment charges for the implementation phase (T0 to Go-Live) are deemed included in the one-time Part A prices	Recurring (R)	Per year		5	**= Unit × 5**
B.2	Hosting & Infrastructure — cloud/DC, compute, storage, bandwidth, backup, DR; vendor-managed, else ₹0.00	Recurring (R)	Per year		5	**= Unit × 5**
B.3	Operations, Maintenance, Support & AMC — O&M / AMC	Recurring (R)	Per year		5	**= Unit × 5**
	Sub-Total Part B — Recurring Costs over 5 years (R)					**= Σ B.1 … B.3**

> **Note —** For Part B, the Bidder shall quote a single firm and fixed **per-year Unit Price** for each recurring line. The same firm annual rate applies uniformly to each of the five (5) years — no year-on-year escalation is permitted (see **Clause 7.7**). The Total Amount for each recurring line is the Unit Price multiplied by five (5).

Part C — Change-Request Rate Card (per man-day, by role — evaluated on notional quantities)

Sl	Role / Resource Category	Nature	Notional Qty (evaluation only)	Unit Price excl. GST (₹ per man-day)	Evaluated Total (₹)
C.1	Project Manager	Evaluated on notional qty	**10** man-days		
C.2	Solution / Technical Architect	Evaluated on notional qty	**10** man-days		
C.3	Business Analyst / Functional Consultant	Evaluated on notional qty	**25** man-days		
C.4	Senior Software Engineer / Developer	Evaluated on notional qty	**30** man-days		
C.5	Software Engineer / Developer	Evaluated on notional qty	**40** man-days		
C.6	Database Administrator / DBA	Evaluated on notional qty	**10** man-days		

Sl	Role / Resource Category	Nature	Notional Qty (evaluation only)	Unit Price excl. GST (₹ per man-day)	Evaluated Total (₹)
C.7	Quality Assurance / Test Engineer	Evaluated on notional qty	**20** man-days		
C.8	Trainer / Documentation Specialist	Evaluated on notional qty	**15** man-days		
	EVALUATED TOTAL PART C — 160 notional man-days, excl. GST — carried to the Grand Total		**160**		

Important — The Part C rate card is **evaluated**. The **notional quantities are fixed by the University solely for financial evaluation**, so that change-request rates are competed rather than quoted freely; they create **no commitment, minimum order or entitlement** whatsoever. Quoting against every role is **mandatory**; a blank rate shall be construed as ₹0.00 per man-day and shall bind the Bidder. Actual drawdown is only against Change Requests approved in writing under the change-control procedure of **Clause 9.13 of Section 9**, and is capped at **10% of the Part A (implementation-phase) contract value per contract year**. Rates are firm and fixed for the Contract term.

Part D — Phase-2 Optional Items (not evaluated)

Sl	Phase-2 Optional Item (cross-ref)	Nature	Firm Lump-Sum Price (₹)
D.1	Athlete video-analysis — upload, tagging, annotation (**FR-ATH-04**)	Phase-2 Optional	
D.2	Tournament live scoring & real-time standings (**FR-TOUR-04**)	Phase-2 Optional	
D.3	E-commerce / merchandise storefront with fulfilment & returns (**FR-ECOM-01–03**)	Phase-2 Optional	
D.4	Personalised nutrition & meal tracking (**FR-NUT-03**)	Phase-2 Optional	
D.5	Full trilingual user interface — Punjabi & Hindi (**FR-GEN-11**)	Phase-2 Optional	

Note — Part D prices are firm and fixed for the Contract term, are quoted in Cover-2, and are **NOT counted in the evaluated 5-Year TCO or the financial score**. The University may commission any Part D item within 24 months of Go-Live per §4.1.3 of Section 4, at the quoted price, under the change-control procedure. A blank Part D row means the item is not offered and shall not be read as ₹0.00.

Grand Total — 5-Year Total Cost of Ownership

Ref	Description	Total Amount (₹) — in figures	In words
	Sub-Total Part A — One-Time Costs		
	Sub-Total Part B — Recurring Costs (5 years)		
	Evaluated Total Part C — Change-Request Rate Card (160 fixed notional man-days)		
	GRAND TOTAL — Evaluated 5-Year TCO (Part A + Part B + Evaluated Part C), exclusive of GST		

> **Mandatory —** The **Grand Total** figure above — being **Sub-Total Part A + Sub-Total Part B + Evaluated Total Part C**, exclusive of GST and exclusive of Part D — is the single evaluated figure carried forward to the financial scoring in **Section 8 (Evaluation Criteria)**. It shall be quoted in both **figures and words**; in case of any discrepancy, the words shall prevail.

7.4 Total Cost of Ownership (TCO)

The **Total Cost of Ownership (TCO)** is the total price payable by the University to acquire, implement, host (where vendor-managed), operate, maintain and support the ERP System over the five (5) year post-Go-Live period, and is the basis of the financial evaluation.

Definition. The evaluated 5-Year TCO comprises all one-time (non-recurring) costs incurred during the Implementation phase, plus all recurring costs over the five (5) year Operations, Maintenance, Support and AMC period, plus the Part C rate card evaluated on the University's fixed notional quantities, exclusive of GST and exclusive of the Part D optional items.

Formula.

> **TCO (5 years) = One-time Costs + (Software Subscription / SaaS per year × 5) + (Hosting per year × 5) + (O&M / AMC per year × 5) + (Part C rates × the University's fixed notional quantities)**

Expressed in terms of the BOQ parts of **Clause 7.3**:

> **TCO = Sub-Total Part A (One-time) + Sub-Total Part B (Recurring over 5 years) + Evaluated Total Part C (rate card × the University's fixed notional quantities)**
>
> **Mandatory — Evaluated TCO is not Contract Value.** The **Evaluated 5-Year TCO** (Part A + Part B + Evaluated Part C) is used **solely** to compute the Financial Score `Sf` and the composite ranking under Section 8. **"Contract Value"**, wherever used in this RFP and in the Agreement — including for the **Performance Bank Guarantee (5%)**, the **liquidated-damages ceiling**, the **aggregate liability cap** and the **milestone payment base M1–M6** — means **Sub-Total Part A + Sub-Total Part B only**, being the amounts the University is committed to pay. The Part C notional quantities are an evaluation device and create **no payment obligation**; amounts actually payable under Part C arise only on Change Requests approved under Clause 9.13 of Section 9 and are **additional** to the Contract Value, within the cap stated at Clause 7.3.
>
> where Sub-Total Part B = (Software Subscription/SaaS per year × 5) + (Hosting & Infrastructure per year × 5) + (O&M / AMC per year × 5).



The evaluated 5-Year TCO (the BOQ Grand Total, after application of the arithmetic-correction rule of **Clause 7.1**) is used to compute the Bidder's financial score in accordance with **Section 8**, using the formula **Sf = (Lowest evaluated TCO ÷ Bidder's evaluated TCO) × 100**, which is then combined with the technical score in the Quality-and-Cost-Based Selection (QCBS) composite score **S = 0.70 × St + 0.30 × Sf**.

> **Note —** GST is **not** included in the evaluated TCO for the purpose of financial scoring, because it is a statutory pass-through payable at the prevailing rate. GST shall, however, be paid by the University over and above the quoted prices as provided in **Clause 7.6**.

7.5 Payment Schedule

All payments shall be made in Indian Rupees, on the basis of **accepted deliverables** duly certified by the University's authorised officer, against a valid GST-compliant invoice, and shall be **contingent upon the Performance Bank Guarantee (PBG) being in force** for the full Contract term plus the claim period (refer **Clause 7.9** and **Section 9**). No advance payment shall be made. The following milestone schedule is the canonical and binding payment plan for the Contract:

#	Milestone / Deliverable	Payment (% of total Contract value)
M1	Project kick-off + sign-off of the SRS / Business Blueprint (BBP)	**10%**
M2	Delivery, configuration & integration of all modules (build complete)	**15%**
M3	Successful User Acceptance Testing (UAT) sign-off of all modules	**20%**
M4	Go-Live + completion of data migration + completion of end-user training	**15%**
M5	Exit of hypercare / Final Acceptance Test (FAT) sign-off	**5%**
M6	Operations, Maintenance, Support & AMC — paid **quarterly** across 5 years	**35%**
	Total	**100%**

Conditions governing payment.

1. Each implementation-phase payment (M1–M5) shall be released only against the **formal written acceptance** of the corresponding deliverable by the University, in accordance with the acceptance criteria of **Section 6**.
2. The O&M/AMC component (M6 — 35%) shall be paid in **equal quarterly instalments in arrears** over the twenty (20) quarters of the five (5) year post-Go-Live period, subject to the Bidder's compliance with the SLAs of **Section 6** and after deduction of any SLA penalties and liquidated damages then due under **Clause 7.8**.
3. Every payment shall be net of applicable **Tax Deducted at Source (TDS)** and net of any liquidated damages, SLA penalties or other recoveries lawfully due from the Bidder.
4. Payment shall ordinarily be released within **thirty (30) working days** of receipt of an undisputed, correct and complete invoice together with all supporting acceptance documents. Where the Successful Bidder is a registered **micro or small enterprise**, payment shall in any event be made within **forty-five (45) days** of acceptance as required by Section 15 of the MSMED Act, 2006, failing which interest is payable under Section 16 of that Act.

> **Reference —** The definition of each milestone deliverable, its acceptance criteria, the SLA parameters, and the uptime commitment (**99.5% monthly**, measured at the application layer) are set out in **Section 6 (Project Management and Implementation)**. The PBG conditions are set out in **Section 9 (Terms and Conditions of Contract)**.

7.6 Taxes and Duties

Ref	Provision
TX-01	**Goods and Services Tax (GST)** shall be quoted and shown **separately** and shall be **paid extra** by the University at the rate prevailing on the date of supply/invoice. GST is **not** included in the quoted prices and is **not** part of the evaluated TCO. The Bidder shall be a registered GST assessee and shall raise valid, GST-compliant tax invoices to enable the University to avail input tax credit where applicable.
TX-02	**Tax Deducted at Source (TDS)** and any other withholding tax shall be **deducted at source** by the University from each payment at the rates prescribed under the Income-Tax Act, 1961 and any other applicable law, and a TDS certificate shall be issued to the Bidder.
TX-03	**All other taxes, duties, cesses, levies and statutory charges** (other than GST) — whether central, state or local, and whether existing or newly imposed but referable to the Bidder's cost of performance — shall be **deemed to be included** in the quoted prices, and no separate claim on their account shall be entertained.
TX-04	The Bidder shall be solely responsible for the correct assessment, collection, deposit and reporting of all taxes payable by it, and shall keep the University fully indemnified against any demand, penalty or interest arising from the Bidder's default in this regard.

7.7 Price Validity and Escalation

1. The commercial offer (Cover-2) shall remain **valid for acceptance for 180 (one hundred and eighty) days** from the last date of bid submission, in line with the bid validity prescribed in **Section 2**. The University may request an extension of validity; refusal to extend shall not entail forfeiture of the EMD.
2. The quoted prices, once accepted, shall be **firm and fixed for the entire Contract term** (Implementation phase plus five (5) years of O&M/AMC) and shall **not be subject to any escalation, revision or price adjustment** on any ground — including inflation, currency fluctuation, wage revision, change in input or licence costs, or increase in scope of effort — save only as provided in Clause 7.7(3).
3. The **sole** permitted adjustment is a change arising **directly from a statutory variation in taxes and duties** (for example, a change in the GST rate, or the introduction or abolition of a statutory levy) occurring after the bid due date. Any such variation shall be to the account of the University — whether as an additional payment (in the case of an increase) or as a saving (in the case of a decrease) — and shall be settled against documentary proof of the statutory notification. No other head of escalation shall be admissible.

> **Important —** Any bid that quotes prices subject to escalation, price variation, or currency-linked adjustment (other than the permitted statutory-tax variation above) shall be treated as **conditional** and is liable to be rejected as non-responsive under **Clause 7.1 (P-06)**.

7.8 Penalties and Liquidated Damages

Delays and service shortfalls shall attract liquidated damages (LD) and SLA penalties as set out below. These are agreed genuine pre-estimates of loss, are recoverable without proof of actual loss, and are without prejudice to the University's other rights under the Contract.

7.8.1 Liquidated Damages for delay

If the Bidder fails to achieve any milestone by its scheduled date for reasons **not attributable to the University** or to a Force Majeure event, the University shall levy liquidated damages as follows:

Parameter	Value
LD rate	**0.5% of the value of the delayed milestone** per completed week (or part thereof) of delay
Maximum (cap)	**10% of the total Contract value**
Recovery	Deducted from the milestone payment due, from any other sum payable, or from the Performance Bank Guarantee

Worked illustration. If the UAT milestone (M3, 20% of a ₹48,00,000 contract = ₹9,60,000) is delayed by three (3) weeks, LD = 0.5% × ₹9,60,000 × 3 = **₹14,400**, subject always to the overall cap of 10% of the Contract value.

Liquidated Damages and SLA penalties are subject to the aggregate caps and the recovery framework set out in **Section 9** (Clauses 9.10 and 9.17); the same delay or breach shall not be penalised twice under both LD and SLA heads.

7.8.2 SLA penalties (operations phase)

During the five (5) year O&M/AMC period, **SLA penalties shall be levied in accordance with the SLA framework of Section 6 (Project Management and Implementation)** — covering, inter alia, the uptime commitment (**99.5% monthly**, measured at the application layer), incident-response and resolution times, and help-desk performance. SLA penalties shall be recovered from the relevant quarterly O&M/AMC instalment (Milestone M6).

7.8.3 Consequence of reaching the LD cap

Liquidated damages for delay and SLA penalties are distinct heads of recovery. Where the **cumulative liquidated damages reach the 10% cap** of the Contract value, the University shall be entitled — in addition to recovering the capped amount — to treat the Bidder as being in **material default** and to **invoke the**

termination provisions of Section 9 (Terms and Conditions of Contract), including invocation of the Performance Bank Guarantee and engagement of an alternative agency at the Bidder's risk and cost.

> **Note —** The levy of liquidated damages or SLA penalties, or the exercise of the University's right of recovery, shall not relieve the Bidder of its obligation to complete performance, nor shall it operate as a waiver of any other remedy available to the University in law or under the Contract.

7.9 Performance Security Note

The successful Bidder shall, prior to signing the Contract, furnish **performance security (PBG) equal to 5% (five per cent) of the total Contract value** — either as a Bank Guarantee in the prescribed format from a scheduled commercial bank, **valid for the full Contract term plus a three (3) month claim period**, or as an **account-payee Demand Draft** in favour of "The Registrar, The Maharaja Bhupinder Singh Punjab Sports University", payable at Patiala (refer Clause 9.3 of Section 9). All payments under **Clause 7.5** shall be conditional upon the PBG being valid and subsisting. The PBG may be invoked, in whole or in part, to recover liquidated damages, SLA penalties, or any other sum due from the Bidder, including on termination for default.

> **Reference —** The detailed conditions governing the Performance Bank Guarantee — including its format, invocation, extension, reduction, and return — are set out in **Section 9 (Terms and Conditions of Contract)**, and the PBG proforma in the Annexures. The Earnest Money Deposit (EMD) and Tender Document Fee provisions are set out in **Section 2 (Instructions to Bidders)**.

Section 8 — Bid Evaluation Criteria (QCBS)

This Section sets out the complete methodology by which bids received against Tender Reference No. **MBSPSU/PUR/ERP/2026/01** will be examined, evaluated and ranked, and the manner in which the successful Bidder (H1) will be selected for award of contract. It shall be read together with **Section 2 (Instructions to Bidders)**, which governs bid preparation and submission, and **Section 7 (Pricing & Payment Terms)**, which governs the Bill of Quantities (BOQ) and the Total Cost of Ownership (TCO). In the event of any inconsistency between the summary of evaluation given in Section 2 and the detailed provisions of this Section 8, **this Section 8 shall prevail**.

> **Note —** Terms in initial capitals not defined here carry the meaning assigned to them in Section 1 (Definitions & Abbreviations) or the RFP Fact Sheet in Section 1. "St" denotes the raw Technical Score out of 100; "Sf" denotes the Financial Score out of 100; "S" denotes the Composite (final) Score; "TCO" denotes the 5-year Total Cost of Ownership evaluated from the BOQ.

8.1 Evaluation overview and the QCBS principle

8.1.1 Section at a glance

Item	Provision
Selection method	**Quality-and-Cost-Based Selection (QCBS)**
Bid type	Online, Two-Cover (Two-Bid) e-Tender hosted **live on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in)** — the sole platform for tender documents, corrigenda, clarifications and bid submission / opening. NIT, RFP and corrigenda additionally published on **https://sppp.punjab.gov.in**; the University website carries a **notification only**
QCBS weightage	**Technical 70% : Financial 30%**
Technical matrix	100 marks, criteria **T1–T7** (see 8.4)
Minimum technical qualifying score	**70 out of 100 marks** (see 8.6)
Financial evaluation basis	**5-year Total Cost of Ownership (TCO)** from the BOQ (Cover-2)
Financial score	**Sf = (Lowest evaluated TCO ÷ Bidder's TCO) × 100**
Composite score	**S = 0.70 × St + 0.30 × Sf**
Award	Highest Composite Score **S** = **H1** = selected Bidder

Item	Provision
Number of covers opened	Cover-2 (Financial) opened **only** for Bidders qualifying at ≥ 70/100

8.1.2 The QCBS principle

The University shall select the Bidder that offers the **best value for money** — that is, the optimum combination of technical quality and cost — rather than merely the lowest-priced offer. This is achieved under the **Quality-and-Cost-Based Selection (QCBS)** method, in which each responsive and qualified Bidder is assigned:

1. a **Technical Score (St)**, out of 100 marks, measuring the quality, capability, experience and demonstrated fitness of the offer against the Technical Evaluation Matrix at 8.4; and
2. a **Financial Score (Sf)**, out of 100 marks, derived from the Bidder's evaluated 5-year TCO relative to the lowest evaluated 5-year TCO among qualified Bidders.

These two scores are combined in a fixed **70 : 30** ratio (technical : financial) to produce a single **Composite Score (S)**. The Bidder with the highest Composite Score is ranked **H1** and recommended for award, subject to the tie-breaking, negotiation and award provisions at 8.9.

> **Mandatory —** The QCBS weightage of **Technical 70% : Financial 30%**, the minimum technical qualifying score of **70/100**, and the composite formula **S = 0.70 × St + 0.30 × Sf** are fixed for this procurement and shall not be varied for any Bidder under any circumstances.
>
> **Reference —** The competent authority has, by a recorded decision, classified this selection as a **consultancy-type, knowledge-based service engagement** (the consultancy-led design–develop–implement selection of a System Integrator) under the **Manual for Procurement of Consultancy & Other Services, 2017**, under which QCBS with a 70:30 quality-cost weightage is the standard method, read with the Punjab Transparency in Public Procurement Act, 2019; the DoE General Instructions (OM No. F.1/1/2021-PPD dated 29.10.2021) are applied as benchmark norms. The QCBS 70:30 weightage and the 70/100 qualifying score are fixed accordingly and recorded in the procurement file.

8.1.3 The four-stage evaluation funnel

Evaluation proceeds through four sequential, elimination-based stages. A bid must clear each stage to be considered at the next. Failure at any stage results in the bid being set aside without further evaluation, and (in the case of a Stage 1–3 failure) the Financial Cover (Cover-2) of that Bidder **shall not be opened**.



Reference — The indicative schedule for these stages is set out in the Key Dates table of Section 1 / Section 2: opening of Cover-1 on **T + 43, 03:30 PM**; Technical Presentation & Product Demonstration on **T + 55 to T + 57** (as intimated); opening of Cover-2 (Financial) on a date to be intimated to technically-qualified Bidders only.

8.2 Stage 1 — Preliminary examination and responsiveness

Immediately upon opening of **Cover-1** (Fee/EMD + Technical) on the notified date, the Tender Evaluation Committee (TEC) constituted by the Registrar shall carry out a preliminary examination to determine whether each bid is **substantially responsive** — that is, whether it conforms to all mandatory formal requirements of the RFP without material deviation, reservation or omission.

8.2.1 Preliminary examination checklist

The following shall be examined on a **Pass / Fail** basis. Each item marked "Rejection" as its effect of failure is a mandatory qualifying condition; failure of any one such item renders the bid **non-responsive** and liable to summary rejection.

#	Item examined	Requirement	Effect of failure
P1	Tender Document Fee	**₹5,000** (non-refundable) paid online through the portal — **or** a valid Udyam (MSE) / DPIIT Startup exemption claimed per Clause 2.2A of Section 2	Rejection
P2	Earnest Money Deposit (EMD) / Bid Security	**₹96,000** submitted online / valid BG from a scheduled bank — **or** a valid Bid Security Declaration together with the Udyam / DPIIT certificate, for an MSE / Startup exempted per Clause 2.2A of Section 2	Rejection
P3	EMD validity	Valid for not less than **45 days beyond bid validity** (i.e., bid validity **180 days** + 45 days) — Not applicable to Bidders furnishing a valid Bid Security Declaration under Clause 2.2A / Clause 2.3.6 in lieu of EMD; the Declaration remains binding for the full bid-validity period and any extension.	Rejection
P4	Bid signing	Every page of both covers **signed and stamped by the authorised signatory** as per Clause 2.5.3 of Section 2	Rejection
P5	Authorisation	Valid Power of Attorney / Board Resolution authorising the signatory (Annexure form)	Rejection (curable clarification at TEC discretion)
P6	Bid validity	Bid unconditionally valid for **180 days** from the last date of submission	Rejection
P7	Single bid	Only **one bid** submitted by the Bidder; no consortium bid (OEM–SI back-to-back MoU permitted with the primary Bidder as SI)	Rejection
P8	Cover discipline — **no price in Cover-1**	Cover-1 (Technical) contains **no price, rate, amount or any indication of the financial offer** in any form	**Rejection**
P9	Completeness	All mandatory forms, annexures, certificates, affidavits and undertakings required by the RFP are enclosed, signed and stamped	Rejection (subject to 8.2.3)
P10	Conditional / qualified bids	Bid is **unconditional**; contains no counter-condition, deviation schedule of a material nature, or reservation	Rejection

> **Important —** Under the Two-Cover system, the presence of **any** financial figure, price, rate, discount indication or BOQ value within the Technical Cover (Cover-1) shall render the entire bid liable to **outright rejection**. The financial offer must be contained **exclusively** within Cover-2 (Financial), in the prescribed BOQ format of Section 7 / Annexure. This rule is strict and admits no exception.

8.2.2 Materiality

A deviation, reservation or omission is **material** if (a) it affects in any substantial way the scope, quality or performance of the required ERP System; or (b) it limits in any substantial way, inconsistent with the RFP, the University's rights or the Bidder's obligations; or (c) its rectification would unfairly affect the competitive position of other Bidders. Material deviations shall not be waived or cured.

8.2.3 Clarifications and minor infirmities

The TEC **may**, at its sole discretion and in the interest of a competitive process, seek written clarification from a Bidder or permit rectification of a **minor, non-material** infirmity of a formal nature (e.g., a missing signature on a covering page, or a legible but unstamped copy of an otherwise submitted document). Such clarification:

- shall be sought and furnished **in writing** through the portal within the time stipulated by the TEC;
- shall **not** permit any change to the substance, price, or competitive standing of the bid; and
- shall **not** be used to make a non-responsive bid responsive.

Bids found substantially responsive at Stage 1 shall proceed to Stage 2.

8.3 Stage 2 — Pre-Qualification (eligibility) evaluation

Each substantially responsive bid shall be evaluated on a strict **Pass / Fail** basis against the Pre-Qualification (Eligibility) Criteria set out in **Section 2.2**. These criteria are **not scored**; they are threshold conditions. A Bidder **must satisfy every one** of the criteria below, supported by the specified documentary evidence, to advance to the Technical Evaluation (Stage 3). Failure to meet **any single** criterion, or failure to furnish the supporting document, shall result in disqualification, and the Bidder's Cover-2 shall **not** be opened.

8.3.1 Pre-Qualification pass/fail checklist

PQ #	Pre-Qualification criterion (restated from Section 2.2)	Documentary evidence required	Result
PQ-1	**Legal entity** incorporated/registered in India (Companies Act 2013 / LLP Act / Partnership) and in **continuous operation ≥ 3 years** as on the bid-submission date — *vintage waived for DPIIT-recognised Startups per Clause 2.2A*	Certificate of Incorporation / Registration; GST & PAN; DPIIT certificate where claimed	Pass / Fail

PQ #	Pre-Qualification criterion (restated from Section 2.2)	Documentary evidence required	Result
PQ-2	**Average Annual Turnover ≥ ₹50 Lakh** (average of the last three audited FYs 2022-23, 2023-24, 2024-25) from IT / software development / ERP services, **and positive net worth** in the latest FY — *MSE (Udyam) / DPIIT Startup: ≥ ₹25 Lakh per Clause 2.2A — where fewer than three completed FYs exist (including Startups availing the vintage waiver), the average is computed over the audited FYs available since incorporation (CA-certified provisional accounts permitted for a year whose audit is not yet due)*	Audited financials + **CA certificate** (UDIN); Udyam / DPIIT certificate where claimed	Pass / Fail
PQ-3	**Experience:** successfully implemented/commissioned ERP (or campus / university / institution-management) solutions in **≥ 2 institutions in the last 7 years**, of which **≥ 1 in a Government / Public University or Higher Education Institution**, with **at least one order of value ≥ ₹20 Lakh** — *MSE (Udyam) / DPIIT Startup: ≥ 1 completed institutional software implementation, any value, per Clause 2.2A*	Work orders + client completion / satisfaction certificates	Pass / Fail
PQ-4	**Certifications (mandatory):** valid **ISO 9001:2015** and **ISO/IEC 27001:2022 (ISMS)** — no relaxation; plus valid **ISO/IEC 20000-1:2018 (ITSM) or** documented, auditable ITSM processes aligned to ISO/IEC 20000-1 with an undertaking to obtain certification within 12 months of award	Valid certificate copies (issuing body, scope, validity); equivalence-route Bidders: mapped ITSM policy/SOPs + ≥6 months' operating evidence + 12-month certification undertaking	Pass / Fail
PQ-5	**Not blacklisted / debarred** by any Central/State Government, PSU, or University/agency as on the bid date	Affidavit on ₹100 stamp paper / e-affidavit (Annexure)	Pass / Fail
PQ-6	Valid **GST registration** and **PAN**	GST certificate; PAN card	Pass / Fail
PQ-7	**Manpower:** minimum **10 technical professionals** on rolls — *MSE (Udyam) / DPIIT Startup: minimum 5 per Clause 2.2A* — plus commitment of the Section 6 key personnel (Annexure H)	Self-certification + PF/ESI proof; Annexure H	Pass / Fail
PQ-8	**Support presence:** existing office in India and written commitment to establish/maintain a support/project office within Punjab (Patiala preferred) during the contract	Undertaking + proof of existing office	Pass / Fail
PQ-9	Purchased/downloaded the RFP; paid tender fee & EMD **or claimed a valid exemption under Clause 2.2A**; single bid per Bidder; **no consortium** (OEM–SI back-to-back MoU permitted with primary Bidder as SI)	Portal record; fee/EMD proof or Udyam / DPIIT certificate + Bid Security Declaration; OEM MoU if applicable	Pass / Fail

> **Important —** Pre-Qualification is a gate, not a scale. A Bidder either qualifies or is eliminated. Relaxation claims under **Clause 2.2A** (MSE / DPIIT Startup) are verified at this Stage against the Udyam / DPIIT certificates enclosed in Cover-1; unsupported claims are ignored and the standard criteria applied. **PQ-4 is a mandatory pass/fail condition for all Bidders:** ISO 9001:2015 and ISO/IEC 27001:2022 admit no relaxation, and ISO/IEC 20000-1:2018 may be satisfied **either** by certification **or** by the documented equivalence route stated in PQ-4; the depth and currency of the certification portfolio is separately credited under criterion **T6** of the Technical Evaluation (see 8.4). Any misrepresentation or forged/false document detected at this or any later stage shall, in addition to rejection, attract forfeiture of EMD and action under the anti-fraud provisions of Section 2 and Section 9.

Only Bidders that **Pass all** of PQ-1 to PQ-9 shall proceed to Stage 3.

8.4 Stage 3 — Technical Evaluation (100 marks)

The Technical Evaluation quantifies the quality of each qualified bid on a scale of **100 marks** across seven criteria (**T1–T7**). The Tender Evaluation Committee (assisted by such technical/domain experts as the University may co-opt) shall award marks against each criterion **strictly in accordance with the scoring rubrics** set out in 8.4.2. All marks awarded shall be recorded, reasoned in writing, and preserved as part of the evaluation record for audit.

8.4.1 Technical Evaluation Matrix (100 marks)

The following matrix is the authoritative Technical Evaluation Matrix for this procurement and is binding.

Code	Criterion	Max Marks
T1	Bidder's financial strength and organisational standing	10
T2	Relevant experience — ERP / education-sector implementations, with weightage for Government / PSU / University clients	25
T3	Understanding of requirements, proposed solution fit, functional compliance, SSO & integrations	15
T4	Technical architecture, security, data-migration approach, implementation methodology and exit-readiness	17
T5	Key personnel / proposed team (CVs, qualifications and demonstrated delivery experience)	10
T6	Certifications & quality maturity (ISO)	3
T7	Product demonstration & technical presentation	20
	Total	**100**

> **Note —** The raw Technical Score **St** is the arithmetic sum of the marks awarded under T1 through T7 (maximum 100). St is used both to determine technical qualification (≥ 70; see 8.6) and, for qualified Bidders, as the technical input to the Composite Score (see 8.8). Marks are **not** normalised; St is the absolute score out of 100.

8.4.2 Detailed scoring rubrics

Each criterion is scored using its dedicated rubric below. Where a rubric prescribes bands, the Bidder shall be placed in the single highest band whose conditions are fully satisfied by verifiable evidence. Marks for any criterion shall not exceed the "Max Marks" for that criterion.

RUBRIC T1 — BIDDER'S FINANCIAL STRENGTH AND ORGANISATIONAL STANDING (MAX 10)

Sub-criterion	Basis (Annexure D, CA-certified; Annexure B)	Marks
T1.1 Average annual turnover from IT/software/ERP services, FY 2022-23 to FY 2024-25	≥ ₹100 Lakh = 6; ₹75–<100 Lakh = 4.5; ₹50–<75 Lakh = 3; MSE / DPIIT-Startup qualifying at ₹25–<50 Lakh = 2	**6**
T1.2 Net worth	Positive in each of the last 3 audited FYs = 1; positive in the latest FY only = 0.5	**1**
T1.3 Continuous operation in the IT / ITeS / ERP business (years since incorporation or commencement of business, whichever is later, per the certificate of incorporation/registration at Annexure B)	≥ 10 years = 3; 7–<10 years = 2.25; 5–<7 years = 1.5; 3–<5 years = 0.75; DPIIT-recognised Startup in operation <3 years (age-waiver availed under Clause 2.2A) = 0.75	**3**
	Total T1	**10**

RUBRIC T2 — RELEVANT EXPERIENCE: ERP / EDUCATION-SECTOR IMPLEMENTATIONS (MAX 25)

Only citations in **Annexure E** supported by **both** a work order **and** a client completion/satisfaction certificate shall be counted (maximum 6 citations: up to 4 ERP, ERP-module or campus-automation implementations and up to 2 other institutional software projects for a University, HEI, research or comparable institution). **Evidence cited for T2.3 and T2.4 is additional to the six-citation cap above.** A Bidder availing the relevant-experience relaxation at Clause 2.2A is scored on the same ladders as every other Bidder; the lowest rungs of T2.1 and T2.3 are provided so that such a Bidder competes for marks rather than being placed beyond the qualifying score by the operation of the ladders themselves.

Sub-criterion	Marks ladder	Marks
T2.1 Number of completed implementations of an **ERP, any ERP module, or campus-automation system** in **educational, research or any comparable institutions** in the last 7 years. *An "ERP module" means, by way of illustration and not of limitation, a Website with Content Management System (CMS), Library Management System, Human Resource Management System (HRMS) or Payroll System, Examination Management System, Student Information or Admission Management System, Fee Collection and Accounting System, Hostel, Inventory or Facility Management System, or any comparable institutional application, whether deployed singly or as part of an integrated suite*	**1 (the relaxed minimum available to an MSE / DPIIT-recognised Startup under Clause 2.2A) = 2**; 2 (the general minimum) = 4; 3 = 7; ≥ 4 = 10	**10**
T2.2 Of the above, implementations for **Government / PSU / Public University / Government-aided HEI / Government research institution** clients	1 (minimum) = 4; 2 = 6; ≥ 3 = 8	**8**
T2.3 Value of the highest single completed order executed by the Bidder for an **Education / University ERP, an ERP of any other kind or sector** (including a commercial, industrial, healthcare, government or enterprise ERP), **any ERP module, a campus-automation system, or any other IT / ITeS** engagement — including software design, development, customisation or implementation, systems integration, application maintenance, or IT-enabled managed services — **for a client of any type**, whether or not an educational, research or Government institution. Evidenced by a work order **and** a completion or client-satisfaction certificate; the citation relied on here need not be one of the six capped citations, and the same engagement may also be cited under T2.1 or T2.2 where it independently qualifies	**Below ₹20 Lakh (available where the Clause 2.2A relaxation is availed, under which no minimum order value applies) = 0.5**; ≥ ₹20 Lakh = 2; ≥ ₹35 Lakh = 3; ≥ ₹50 Lakh = 4	**4**
T2.4 Prior engagement with a **sports-sector institution** — a sports university, the Sports Authority of India or a State sports authority, a national or State sports federation, a sports-science institute, or a university or institution discharging athletics / sports-management functions — comprising either **(a)** design, development or implementation of sports-domain application modules (athlete performance or talent management, tournament or competition management, sports facility booking, sports nutrition or injury management), or **(b)** website, web-portal or web-application development, setup or management	Either (a) or (b), evidenced by a work order **and** a completion or client-satisfaction certificate = 3; none = 0	**3**
	Total T2	**25**

RUBRIC T3 — UNDERSTANDING OF REQUIREMENTS, SOLUTION FIT AND FUNCTIONAL COMPLIANCE (MAX 15)

Sub-criterion	Basis	Marks
T3.1 Coverage of **Mandatory (M)** functional requirements across Suites A–G, per Annexure F	% of M-requirements marked FC or CF: ≥ 98% = 6; 95–<98% = 5; 90–<95% = 4; 80–<90% = 2.5; 70–<80% = 1; <70% = 0. *(CD items are permitted but attract no marks under this row; NC on any M item is scored adversely and may also affect responsiveness under Section 4.)*	**6**

Sub-criterion	Basis	Marks
T3.2 Fit to the **sports-domain Suite C** (FR-ATH, FR-NUT, FR-TOUR) and demonstrated understanding of MBSPSU's context as a State sports university (BPES / B.P.Ed / M.P.Ed programmes, athlete lifecycle, tournaments)	Banded scale (see 8.4.3)	**4**
T3.3 SSO, security model and **integration approach**: SBIePay (aggregator-hosted, double-verification, DVP reconciliation, refunds), DigiLocker/NAD, AISHE/UGC, DLT-compliant SMS/e-mail, biometric attendance, wearables/IoT; SSO (SAML/OAuth/OIDC), MFA, RBAC	Banded scale	**3**
T3.4 Quality of requirement analysis and fit-gap; minimal customisation burden and **NIL / immaterial deviations** (Annexure O)	Banded scale	**2**
	Total T3	**15**

RUBRIC T4 — TECHNICAL ARCHITECTURE, SECURITY, DATA MIGRATION, IMPLEMENTATION METHODOLOGY AND EXIT-READINESS (MAX 17)

Sub-criterion	Basis (Annexure G; Annexure Q; Sections 5, 6 and 9)	Marks
T4.1 Architecture and hosting. The Solution shall be hosted either **(a)** on a cloud service provider empanelled by MeitY, or on the MeghRaj / NIC National Cloud; or **(b)** on **any other cloud service provider or platform** — of any architecture, whether region-based, distributed or edge-native — which the Bidder demonstrates satisfies **all** of: (i) all University data, including backups and disaster-recovery copies, stored and processed within the territory of India; (ii) high availability across at least two independent failure domains (Availability Zones or equivalent) serving the primary workload; (iii) disaster recovery in a second, geographically separate location within India, achieving **RTO ≤ 24 hours and RPO ≤ 4 hours**; (iv) current ISO/IEC 27001 and SOC 2 Type II (or equivalent) third-party assurance covering the services offered; and (v) binding contractual commitments on data residency, University audit rights, and exit and data return. **Marks are awarded on the architecture and evidence presented, and not on the identity, name or brand of the provider**; limb (b) is not a lesser route and attracts the same marks as limb (a) where the criteria are met. Also assessed: API-first, stateless services; PWA plus hybrid mobile app (Android at Go-Live)	Banded scale	**5**
T4.2 Security and data protection: TLS 1.2+ / AES-256, secure-SDLC practice with continuous vulnerability scanning (SAST / DAST / SCA) and risk-based patching, the SBIePay payment-security controls of TR-PAY-06, TR-PAY-08 and TR-PAY-09 (asymmetric request/response encryption, SHA-256 checksum verification, and PCI-DSS scope minimisation — no storage, logging or processing of PAN, CVV or Sensitive Authentication Data); ISMS practice under ISO/IEC 27001:2022, **DPDP Act 2023** compliance as Data Processor, breach-notification readiness; and **edge / perimeter protection — CDN, Web Application Firewall, DDoS mitigation, bot management and rate limiting** — sized for admission, examination and result-publication peak loads	Banded scale	**3**
T4.3 Data-migration methodology per Section 5: profiling, cleansing, legacy digitisation, mock migrations, reconciliation and sign-off	Banded scale	**3**

Sub-criterion	Basis (Annexure G; Annexure Q; Sections 5, 6 and 9)	Marks
T4.4 Implementation methodology, work plan and timeline realism within the 9-month T0 → Go-Live window: phase plan P1–P11, SRS/BBP, SIT/UAT/FAT gates, training and change management, risk plan	Banded scale	**3**
T4.5 Exit-readiness and continuity assurance. The depth of the Bidder's programme for **proving** that the continuity end-state at Clause 9.5.6 will work in practice. **No marks are awarded for the intellectual-property, licence or escrow entitlement itself** — that entitlement is granted identically by every Bidder under Clause 9.5.6 and is a condition of responsiveness, attracting neither marks nor penalty. Only quantified, unconditional commitments score; unquantified, conditional or "as mutually agreed" offers score zero. All commitments are binding on award	**Cumulative, 0.5 each. (a) Independent build-and-run verification** — the deposited code / deployable build is built from scratch and run as a working instance by the escrow agent or a University-nominated verifier, without the SI's hands-on assistance, certified in writing: at Go-Live **and** at least once every year of the O&M term = 0.5; at Go-Live **and** once more during the term = 0.25; at Go-Live only = 0. **(b) Deposit cadence with the escrow agent's technical verification certificate** — on each major release **and** at intervals ≤ 6 months = 0.5; on each major release **and** ≤ 12 months = 0.25; on each major release only = 0. **(c) University developer enablement** — University personnel trained and competency-assessed to build, deploy, configure and modify the Solution: ≥ 8 personnel **and** ≥ 80 hands-on laboratory hours = 0.5; ≥ 6 **and** ≥ 60 hours = 0.25; fewer = 0. **(d) Rehearsed reverse transition** — restore of the delivered / escrowed build plus a complete data export into a University-controlled environment with a University-witnessed functional test: two rehearsals (one by end of Year 3, one in Year 5) **with** SI-borne defect remediation and re-test = 0.5; two rehearsals without remediation-and-re-test = 0.25; one rehearsal only = 0. **This criterion is attainable in full by every delivery approach — Custom Development, COTS, and hosted / SaaS under either Route of Clause 9.5.3.4**	**2**

Sub-criterion	Basis (Annexure G; Annexure Q; Sections 5, 6 and 9)	Marks
T4.6 Demonstrated clearance of a Bank-mandated Website Security Audit. Whether the Bidder has **previously obtained**, for a payment-gateway integration it delivered, a valid clearance of a **Bank-mandated Website Security Audit comprising Vulnerability Assessment & Penetration Testing (VA/PT) and an ASV (Approved Scanning Vendor) scan** — being the audit that TR-PAY-17 of Section 5 makes a pre-condition to SBIePay onboarding and go-live for this procurement. Evidenced by the audit clearance certificate, or a letter from the bank or the empanelled auditor, naming the site or application audited and the date, issued within the **last five (5) years**. *A Bidder without such prior clearance is not disadvantaged in eligibility and remains fully responsible for obtaining the audit under TR-PAY-17; this sub-criterion credits only the demonstrated experience of having passed it.*	Prior clearance held and evidenced = 1; none = 0	**1**
	Total T4	**17**

RUBRIC T5 — KEY PERSONNEL / PROPOSED TEAM (MAX 10)

Scored from the Annexure H CVs; personnel commitments are binding under Clause 6.4.3 of Section 6.

> **Note — Professional certifications are not required and attract no marks under this criterion.** No individual professional or vendor certification — including PMP, PRINCE2, CISA, CISSP, CEH, ISTQB, TOGAF, ITIL and any OEM or product certification — is a qualification requirement, a scoring factor or a tie-breaker. Key personnel are assessed solely on **years of relevant experience and demonstrated delivery track record** evidenced in the Annexure H CVs. A Bidder shall be neither advantaged nor disadvantaged by the presence or absence of any such certification, and the Tender Evaluation Committee shall disregard certifications in awarding marks under T5.1 to T5.5. *(This Note does not affect the organisational quality certifications required at PQ-4 or scored under T6.)*

Sub-criterion	Marks ladder	Marks
T5.1 Project Manager — one (1), full-time, on the Bidder's own payroll (Clause 6.4.3(a); minimum 7 years IT/ERP with ≥ 2 years as PM of full-lifecycle ERP/campus implementations)	≥ 8 years IT/ERP experience **and** has managed **≥ 2** full-lifecycle ERP or campus-automation implementations to Go-Live as Project Manager = 3; ≥ 8 years and **1** such implementation = 2.5; meeting the stated minimum (≥ 7 years) = 2. *Experience beyond 8 years attracts no additional marks*	**3**

Sub-criterion	Marks ladder	Marks
T5.2 Functional / Implementation Consultants (2)	1 mark each: ≥ 5 years ERP / higher-education functional experience = 1; 3–<5 years = 0.5	**2**
T5.3 Technical / Integration Engineer	Demonstrated payment-gateway (SBIePay or equivalent aggregator) **and** data-migration experience = 2; one of the two = 1	**2**
T5.4 Solution Architect — **one (1)** only, part-time with minimum 20% allocation (Clause 6.4.3(b); minimum 6 years including ≥ 2 years architecting enterprise/ERP solutions)	≥ 8 years **and** ≥ 2 institutional ERP architectures = 2; ≥ 8 years with 1 such architecture, or 6–<8 years with ≥ 2 = 1.5; meeting the stated minimum = 1. *Experience beyond 8 years attracts no additional marks*	**2**
T5.5 Named part-time specialists — **two (2) only**: **Security Specialist** (information security / data protection) and **QA / Test Lead** (shall be a distinct individual from the Project Manager). Each minimum 6 years in the relevant discipline and minimum 20% allocation. *The Training Lead and Support Lead are not bid-stage named-personnel requirements; they remain contractual obligations of the Successful Bidder under Clause 6.4.3(c) and are nominated before the relevant phase*	Both named with compliant profiles and CVs at Annexure H = 1; one of the two = 0.5; neither = 0	**1**
	Total T5	**10**

RUBRIC T6 — CERTIFICATIONS AND QUALITY MATURITY (MAX 3)

ISO 9001:2015 and ISO/IEC 27001:2022 are pre-qualification requirements (PQ-4) and attract no marks here.

Sub-criterion	Marks ladder	Marks
T6.1 ISO/IEC 20000-1:2018 (IT Service Management)	Valid certificate = 2; equivalence route with a 12-month certification undertaking = 1	**2**
T6.2 Any one additional relevant certification (e.g. ISO 22301, ISO/IEC 27701, SOC 2)	Held = 1	**1**
	Total T6	**3**

RUBRIC T7 — PRODUCT DEMONSTRATION AND TECHNICAL PRESENTATION (MAX 20)

Scored live at the demonstration held under 8.5. The mark-wise allocation is at 8.5.4.

Sub-criterion	Scenario (live, on the Bidder's own environment / sandbox)	Marks
T7.1 Admission-to-enrolment for B.P.Ed / M.P.Ed (application → merit/trial → fee → enrolment → SIS record)	Live walk-through	**3**
T7.2 Online fee payment through a payment-aggregator flow equivalent to SBIePay, including double-verification / status-query and reconciliation	Live walk-through	**3**
T7.3 Examination lifecycle: registration → marks entry → moderation → result → transcript (DigiLocker / NAD-ready)	Live walk-through	**3**
T7.4 Athlete performance and sports-domain capability (tests, benchmarks, progression, injury / nutrition linkage)	Live walk-through	**3**
T7.5 HRMS and Payroll run	Live walk-through	**3**
T7.6 Role-based dashboards, RBAC administration, audit trail, mobile / PWA experience	Live walk-through	**3**
T7.7 Quality of the technical presentation, comprehension of MBSPSU's requirements, and responses to the Committee's questions	Assessed by the Committee	**2**
	Total T7	**20**

8.4.3 Banded scale — definition of the bands

Where a sub-criterion of Rubric T3 or Rubric T4 is marked **"Banded scale"**, the Tender Evaluation Committee shall place the Bidder in the **single highest band whose conditions are fully satisfied** by verifiable evidence in the bid, and shall award the corresponding percentage of that sub-criterion's maximum marks. Marks are recorded to two decimal places.

Band	Award	Test to be satisfied
Excellent	**100%** of the sub-criterion's marks	Fully responsive on every element of the sub-criterion; the response is **specific to MBSPSU** (its programmes, scale, sports-domain context and named integrations) rather than generic; every material claim is evidenced by a document, design, named tool or worked artefact in the bid
Good	**75%**	Responsive on every element; evidenced, but partly generic or with minor gaps that do not affect delivery
Adequate	**50%**	Meets the RFP's stated requirement on the substantial majority of elements; thin or partly unevidenced in places; would require University direction during execution
Weak	**25%**	Addresses the sub-criterion but with material gaps, unevidenced assertions, or an approach that carries evident delivery risk
Not addressed	**0%**	Absent, or so generic as to demonstrate no engagement with the requirement

Converting members' bands into the Bidder's mark. Each member of the Committee shall independently place the Bidder in a band for each banded sub-criterion. The Bidder's mark for that sub-criterion is the **arithmetic mean of the members' band percentages**, applied to the sub-criterion's maximum and recorded to **two decimal places**. The same rule governs every banded sub-criterion of Rubrics T3 and T4, as Clause 8.5.4 governs T7.

> **Mandatory —** Each member of the Committee shall record, against every banded sub-criterion, the band awarded **and a brief written reason** citing the page or annexure relied on. Claims unsupported by evidence in the bid shall be treated as **Not addressed**. Marketing material, unquantified assurances and statements of intent are not evidence.

8.5 Product demonstration and technical presentation

8.5.1 Purpose

The product demonstration and technical presentation enable the University to **verify, in a live environment, the claims made in the technical proposal** — particularly functional compliance (T3), architecture and security behaviour (T4), and product depth (T7). It is a mandatory, scored component of the Technical Evaluation.

8.5.2 Conduct

- Bidders that **pass Stages 1 and 2** shall be invited, in writing through the portal, to present and demonstrate their proposed solution on the notified dates (**T + 55 to T + 57**, as intimated).
- The demonstration shall be conducted **live** by the Bidder on the Bidder's own working instance/environment (a working product, not slideware), before the Tender Evaluation Committee and co-opted experts, at the University or through an approved online mode.
- Each Bidder shall be given a fair and equal time window and an identical scenario brief. The University may record the proceedings for the evaluation record.
- The Bidder shall present its evaluated **key personnel** (T5) at the demonstration. Marks shall be awarded by the Committee/panel and averaged.

8.5.3 Scenarios to be demonstrated

The Bidder shall demonstrate, at minimum, the following end-to-end scenarios drawn from the University's operating context:

1. **Admission** — an applicant journey from application through eligibility and merit/selection to enrolment (including a sports/physical-education programme such as B.P.Ed / M.P.Ed).
2. **Fee payment via the payment gateway** — an online fee-collection transaction through the **SBIePay** aggregator (Aggregator-Hosted flow), including payment initiation, status query / double-verification, and receipt/reconciliation.
3. **Examination result** — result processing and publication for a course/semester, including grade/marks entry, moderation, and student result access.

4. **Athlete performance** — capture and analysis of athlete/sports performance data (e.g., fitness/performance metrics, training records, competition results) with dashboards.
5. **HR / Payroll** — an employee-lifecycle step and a payroll run (attendance/leave to salary processing) for university staff.
6. **Dashboards & analytics** — role-based management dashboards (e.g., Vice-Chancellor / Registrar / HoD views) drawing across modules.

> **Note —** The demonstration must substantiate the Functional Compliance Sheet submitted under T3. Any requirement claimed "Fully Complied" that cannot be demonstrated live may be re-scored under T3 and shall attract the lowest score for the relevant head under T7.

8.5.4 Allocation of the 20 demonstration marks (T7)

The 20 marks under T7 are allocated **scenario by scenario**, as set out in Rubric T7 at 8.4.2 and reproduced below. Each of the six live scenarios carries **3 marks**; the remaining **2 marks** are awarded for the quality of the presentation and the Bidder's responses to the Committee's questions.

Ref	Head	Marks
T7.1	Admission-to-enrolment for B.P.Ed / M.P.Ed	3
T7.2	Online fee payment through an SBIePay-equivalent aggregator flow, with double-verification and reconciliation	3
T7.3	Examination lifecycle through to a DigiLocker / NAD-ready transcript	3
T7.4	Athlete performance and sports-domain capability	3
T7.5	HRMS and Payroll run	3
T7.6	Role-based dashboards, RBAC administration, audit trail, mobile / PWA	3
T7.7	Quality of technical presentation, comprehension of requirements, responses to questions	2
	Total T7	**20**

> **Mandatory —** The demonstration must be conducted on the Bidder's **own environment with representative sample data**. A **canned, slide-only demonstration** of any of the scenarios T7.1 to T7.6 shall score **zero** for that scenario. A capability marked **FC** or **CF** in Annexure F but shown to be absent during the demonstration constitutes a **material misrepresentation**, entailing disqualification and forfeiture of the EMD.

Each member of the Committee shall score each Bidder independently against T7.1–T7.7; the Bidder's T7 score is the arithmetic mean of the members' totals, computed to two decimal places and capped at 20.

8.6 Minimum technical qualifying score

The minimum technical qualifying score is **70 out of 100 marks (St ≥ 70)**.

> **Mandatory —** A Bidder whose raw Technical Score **St is below 70/100 shall be treated as technically disqualified**. Such a Bidder shall not proceed to the Financial Evaluation, and its **Financial Cover (Cover-2) shall not be opened** and shall be returned/retained unopened as per portal procedure. Only Bidders scoring **St ≥ 70** and having cleared **every** Pre-Qualification condition (Stage 2) are eligible for financial opening.

The University shall communicate the outcome of the Technical Evaluation, and the list of technically-qualified Bidders, prior to the opening of Cover-2. The date and time of Cover-2 opening shall be intimated to the technically-qualified Bidders, who (or whose authorised representatives) may attend.

8.7 Stage 4 — Financial Evaluation

The Financial Cover (**Cover-2**) shall be opened **only** for Bidders that are technically qualified under 8.6.

8.7.1 Opening and reading of financial bids

- Cover-2 of each technically-qualified Bidder shall be opened online on the notified date and time, in the presence of attending Bidders' representatives.
- The quoted BOQ figures, as read out / recorded from the portal, shall form the basis of evaluation, subject to arithmetic correction.
- The figures in the uploaded **Annexure I BOQ (Cover-2)** are authoritative. Any portal-entered summary figures are for convenience only; in the event of a discrepancy, the uploaded Annexure I (as corrected under 8.7.2) shall prevail.

8.7.2 Arithmetic correction

The financial bids shall be checked for arithmetical errors, which shall be corrected as follows:

1. Where there is a discrepancy between the **unit price** and the **line total** obtained by multiplying the unit price by the quantity/years, the **unit price shall prevail** and the line total shall be corrected — unless, in the opinion of the Tender Evaluation Committee, there is an obvious misplacement of the decimal point in the unit price, in which case the **line total as quoted shall prevail** and the unit price shall be corrected.
2. Where there is a discrepancy between figures and words, the amount in words shall prevail — unless the amount in words is itself the product of an arithmetic error apparent on the face of the BOQ, in which case the amount as corrected under rules (1) and (3) shall prevail.
3. Where there is a discrepancy in the summation of line items, the **individual line items (as corrected above) shall prevail** and the total shall be corrected; the corrected line-item sum shall prevail over the stated Grand Total, whether the Grand Total is expressed in figures or in words.

This Clause states the single authoritative correction rule for this RFP; Clause 7.1 of Section 7 mirrors and defers to it.

The **corrected** total shall be binding on the Bidder. If a Bidder does not accept the correction, its bid may be rejected and its EMD forfeited.

8.7.3 Evaluation on 5-year TCO

The **evaluated bid value** for each technically-qualified Bidder is its **5-year Total Cost of Ownership (TCO)**, computed from the Bill of Quantities at Annexure I as:

> **Evaluated 5-year TCO = Sub-total Part A (one-time costs) + Sub-total Part B (recurring costs × 5 years) + Evaluated Part C (rate card priced on the University's fixed notional quantities)**

all **exclusive of GST**. GST is shown separately as memorandum information, is payable at actuals against valid tax invoices, and is **not counted for evaluation or ranking**.

> **Note — Part C.** The Part C man-day rate card is evaluated on the **fixed notional quantities prescribed by the University at Annexure I**, so that change-request rates are competed rather than quoted freely. Those quantities are fixed **solely for evaluation** and create **no commitment, minimum order or entitlement** whatsoever; actual drawdown is only against Change Requests approved under Section 9, capped as provided in Section 7. **Part D (optional / Phase-2 items) is priced but is NOT included in the evaluated TCO**, and is orderable at the University's discretion at the quoted rates.

The Bidder ranked **lowest on the evaluated 5-year TCO is designated L1** for the purposes of the financial score.

8.7.4 Financial score (Sf)

Each technically-qualified Bidder is assigned a Financial Score out of 100:

Sf = (Lowest evaluated 5-year TCO ÷ Bidder's evaluated 5-year TCO) × 100

- The lowest-TCO (L1) Bidder receives **Sf = 100**. All other Bidders receive proportionately lower Sf.
- Sf shall be computed to **two decimal places**.

8.8 Composite score and final ranking

8.8.1 Composite formula

For each technically-qualified Bidder, the Composite Score is computed as:

S = 0.70 × St + 0.30 × Sf

where **St** is the raw Technical Score out of 100 (8.4) and **Sf** is the Financial Score out of 100 (8.7.4). The Composite Score **S** shall be computed to **two decimal places**.

The Bidder securing the **highest Composite Score S** is ranked **H1** and shall be recommended for award of contract, subject to 8.9.

8.8.2 Worked example (illustrative only)

The following worked example, using three illustrative Bidders, demonstrates the computation. The figures are hypothetical and are provided solely to illustrate the method; they do not bind the University.

Bidder	Technical Score St (/100)	Evaluated 5-yr TCO (₹)	Financial Score Sf = (Lowest TCO ÷ TCO) × 100	Composite S = 0.70 × St + 0.30 × Sf	Rank
Bidder A	88	₹48,60,000	(43,20,000 ÷ 48,60,000) × 100 = **88.89**	0.70 × 88 + 0.30 × 88.89 = **88.27**	**H1**
Bidder B	82	₹43,20,000 (lowest)	(43,20,000 ÷ 43,20,000) × 100 = **100.00**	0.70 × 82 + 0.30 × 100.00 = **87.40**	H2
Bidder C	76	₹45,90,000	(43,20,000 ÷ 45,90,000) × 100 = **94.12**	0.70 × 76 + 0.30 × 94.12 = **81.44**	H3

Reading the result: All three illustrative Bidders cleared the technical threshold (St ≥ 70), so all three financial covers were opened. Bidder B quoted the lowest TCO and therefore earned the maximum financial score (Sf = 100), yet Bidder A — despite a higher price — earned the **highest Composite Score (88.27)** on the strength of its superior technical score, and is selected as **H1**. This illustrates the core QCBS outcome: the best combined value of quality and cost prevails over the lowest price alone.

> **Note —** All computations in the actual evaluation shall be carried out to two decimal places, using the corrected TCO figures (8.7.2) and the recorded technical scores (8.4). The University's computation of St, Sf and S, as recorded in the evaluation report, shall be final.

8.9 Tie-breaking, negotiation and award of contract

8.9.1 Tie-breaking

Where two or more Bidders obtain an **identical Composite Score S** (to two decimal places), the tie shall be resolved in the following order of precedence:

1. **Higher raw Technical Score (St)** shall prevail — consistent with the quality-led intent of QCBS.
2. If still tied, the Bidder with the **higher score under T7 (product demonstration)** shall prevail.
3. If still tied, the Bidder with the **higher score under T2 (relevant experience)** shall prevail.
4. If still tied, the Bidder with the **lower evaluated 5-year TCO** shall prevail.

8.9.2 Negotiation policy

Under QCBS, price is a competed parameter and, as a rule, **price negotiation shall not be conducted**. However:

- The University **may** hold clarificatory discussions with the H1 Bidder to finalise the scope, delivery plan, SLAs and contractual terms, provided these do not alter the essential requirements of the RFP or the basis of evaluation.
- Price negotiation, if any, shall occur **only in the exceptional situations, with the bidder, and subject to the conditions prescribed under Section 40 of the Punjab Transparency in Public Procurement Act, 2019** and the rules made thereunder (CVC guidelines being applied as adopted benchmarks), with the

justification recorded in writing; and shall not result in the finally negotiated price exceeding the H1 Bidder's originally quoted TCO.

- Should negotiation with the H1 Bidder fail to yield an acceptable outcome, the University shall ordinarily annul the process and re-invite bids, in line with CVC guidance that counter-offers to or negotiations with other bidders amount to fresh tendering; award to any bidder other than H1 shall be made only where, and to the extent, expressly permissible under the PTPP Act, 2019, the rules made thereunder and the applicable CVC guidelines, for reasons recorded in writing.

8.9.3 Award of contract

- The University shall issue a **Letter of Award (LoA)** to the successful (H1) Bidder within the bid-validity period.
- Award is conditional upon the H1 Bidder furnishing the **performance security (PBG) of 5% of the total contract value** — as a Bank Guarantee (valid for the full contract term plus a 3-month claim period) or an account-payee Demand Draft per Clause 9.3 of Section 9 and executing the contract, in accordance with Section 9.
- The EMD of the successful Bidder shall be dealt with as provided in Section 2 / Section 9; the EMDs of unsuccessful Bidders shall be released as per the applicable timelines.
- The University reserves the right — for reasons to be recorded in writing, and communicated and published to the extent required by the PTPP Act, 2019 — and without incurring any liability, to accept or reject any or all bids, to annul the bid process, or to modify the requirements at any stage prior to award, in accordance with the Instructions to Bidders.

> **Mandatory —** The entire evaluation — from preliminary examination through composite ranking and award — shall be conducted transparently, recorded in a reasoned evaluation report signed by the Tender Evaluation Committee, and preserved with all supporting worksheets and scoring sheets for audit and for scrutiny by the competent authorities. The decision of the University, taken on the recommendation of the Committee, shall be final and binding.

Section 9 — General and Special Conditions of Contract

This Section sets out the General and Special Conditions of Contract ("**GCC/SCC**" or the "**Conditions**") that shall govern the relationship between **Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala** (the "**University**" / "**Purchaser**") and the successful Bidder (the "**Successful Bidder**", "**System Integrator**" or "**SI**") selected pursuant to Tender Reference No. **MBSPSU/PUR/ERP/2026/01**. These Conditions form an integral and binding part of the RFP and of the resulting Contract, and shall be read together with all other Sections and Annexures of this RFP.

By submitting a bid, the Bidder unconditionally accepts these Conditions in their entirety. Upon award, these Conditions shall be incorporated into, and enforceable under, the Agreement executed between the University and the Successful Bidder.

> **Note —** In this Section, "shall" and "must" denote mandatory and enforceable obligations; "should" denotes a recommendation; and "may" denotes an option. In the event of any conflict between these Conditions and any other Section of the RFP, the order of precedence set out in Clause 9.1.3 shall apply.

Section at a glance

Clause	Subject
9.1	Definitions, contract documents and order of precedence
9.2	Award, Letter of Award and execution of the Agreement
9.3	Performance Bank Guarantee (PBG)
9.4	Contract term, commencement, renewal and extension
9.5	Intellectual property, source code and escrow
9.6	Confidentiality and non-disclosure
9.7	Data protection and privacy (DPDP Act, 2023)
9.8	Warranty and defect liability
9.9	Indemnification
9.10	Limitation of liability
9.11	Insurance
9.12	Sub-contracting and assignment
9.13	Change control and change-request procedure
9.14	Force Majeure

Clause	Subject
9.15	Termination
9.16	Exit management and transition
9.17	Penalties, recoveries and set-off
9.18	Dispute resolution, arbitration and jurisdiction
9.19	Conflict of interest, code of integrity and integrity pact
9.20	Statutory and regulatory compliance
9.21	Notices, amendment, waiver, severability and entire agreement

9.1 Definitions, Contract Documents and Order of Precedence

9.1.1 Definitions

Unless the context otherwise requires, capitalised terms used in these Conditions shall have the meanings assigned to them below; terms not defined here shall have the meaning assigned to them elsewhere in this RFP (including Section 1, *Introduction and Background*).

Term	Meaning
Agreement / Contract	The master services agreement executed between the University and the Successful Bidder, together with all its schedules, annexures and the incorporated RFP documents, giving effect to the award under this RFP.
University / Purchaser	Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala, a State (Government) University established under the Maharaja Bhupinder Singh Punjab Sports University Act, 2019 (Punjab Act No. 11 of 2019), acting through the Registrar.
Tendering Authority	The Registrar, MBSPSU, Patiala, for and on behalf of the University.
Successful Bidder / System Integrator / SI	The Bidder to whom the Contract is awarded pursuant to the QCBS process under this RFP.
Letter of Award (LoA)	The written communication issued by the Tendering Authority notifying the Successful Bidder of the award of the Contract.
Effective Date	The date of signing of the Agreement by both Parties, or such other date as may be expressly stated in the Agreement.
Go-Live	The date on which the ERP System, having successfully completed User Acceptance Testing (UAT) and data migration, is formally accepted by the University and released for productive use by end-users, as certified by the University.
Deliverables	All software, source code, configurations, documentation, data, reports, training materials and other outputs to be delivered by the SI under the Contract.

Term	Meaning
Solution / ERP System	The Enterprise Resource Planning system, including all bespoke/custom-developed components, Commercial-Off-The-Shelf (COTS) components, integrations, hosting and services delivered under this RFP.
University Data	All data, records, content, metadata, configuration and information owned, generated, collected, processed, stored or supplied by, for, or on behalf of the University, including personal data of students, athletes, employees and other data principals.
Custom Development	Software, modules, code, scripts, configurations and artefacts specifically designed, developed or materially customised for the University under this Contract.
COTS	Commercial-Off-The-Shelf / pre-existing proprietary software product licensed (not bespoke-developed) as part of the Solution.
Background IP / Pre-existing IP	Intellectual property owned or licensed by a Party (or its licensors) that exists prior to, or is developed independently of, the Contract.
PBG	Performance Bank Guarantee furnished under Clause 9.3.
DPDP Act	The Digital Personal Data Protection Act, 2023, and rules, regulations and notifications made thereunder, as amended from time to time.
Party / Parties	The University and the Successful Bidder individually or collectively, as the context requires.

9.1.2 Contract Documents

The Contract shall be constituted by, and shall be deemed to include, the following documents ("**Contract Documents**"), which shall be read and construed as one integrated instrument:

1. The **Agreement** executed between the Parties, together with its schedules and annexures;
2. The **Letter of Award (LoA)** and any corrigenda/amendments thereto;
3. All **corrigenda, addenda, clarifications and minutes** of the pre-bid meeting issued by the University in respect of this RFP;
4. This **RFP** (all Sections and Annexures), Tender Reference No. MBSPSU/PUR/ERP/2026/01;
5. The **Bidder's Proposal** (technical and financial), to the extent accepted by the University.

9.1.3 Order of Precedence

In the event of any ambiguity, conflict, inconsistency or repugnancy between or among the Contract Documents, the following order of precedence shall prevail (the earlier prevailing over the later):

> **Mandatory —** Order of precedence: (1) the **Agreement** → (2) the **Letter of Award (LoA)** → (3) **Corrigenda / Addenda / Clarifications** to the RFP (later-dated prevailing over earlier-dated) → (4) the **RFP** (this document and its Annexures) → (5) the **Bidder's accepted Proposal**.

Notwithstanding the above, where the Bidder's Proposal offers terms, warranties, service levels or specifications that are **more favourable to the University** than those in the RFP, such more-favourable terms

shall be binding on the Successful Bidder and shall prevail to that extent. Nothing in the Bidder's Proposal shall dilute, restrict or override any obligation of the SI under the RFP unless expressly accepted in writing by the University.

9.2 Award, Letter of Award and Execution of the Agreement

9.2.1 Notification of Award

9.2.1.1 The University shall notify the Successful Bidder of the award of the Contract by issue of a **Letter of Award (LoA)** within the bid-validity period of **180 days** from the last date of bid submission. The LoA shall constitute the formation of a binding contract between the Parties, pending execution of the formal Agreement.

9.2.1.2 The Successful Bidder shall convey **unconditional acceptance** of the LoA in writing within **seven (7) calendar days** of its issue, without any deviation, condition, reservation or qualification.

9.2.2 Performance Security and Execution of the Agreement

9.2.2.1 Within **fifteen (15) calendar days** of the date of the LoA (or such extended period as the University may permit in writing), the Successful Bidder shall furnish the **Performance Bank Guarantee (PBG)** in accordance with Clause 9.3.

9.2.2.2 Within **thirty (30) calendar days** of the date of the LoA, the Successful Bidder shall execute the formal **Agreement** with the University on a non-judicial stamp paper of appropriate value (stamp duty and incidental charges to be borne by the Successful Bidder), in the form and substance approved by the University and incorporating these Conditions.

> **Important —** Failure by the Successful Bidder to accept the LoA, furnish the PBG, or execute the Agreement within the stipulated periods shall constitute sufficient ground for **annulment of the award and forfeiture of the Earnest Money Deposit (EMD) of ₹96,000**, without prejudice to the University's other rights and remedies. In such an event, the University may, at its sole discretion, award the Contract to the next-ranked (H2) Bidder or re-invite bids.

9.2.3 Commencement of Work

The Successful Bidder shall commence work from the **Effective Date** or from the date specified in the LoA / Notice to Proceed, whichever is earlier, and shall adhere to the implementation timeline set out in Section 6 (*Project Management and Implementation*).

The sequence from award to commencement of work is summarised below.



9.3 Performance Bank Guarantee (PBG)

9.3.1 Amount and Form

9.3.1.1 The Successful Bidder shall furnish **performance security equal to five per cent (5%) of the total Contract Value** (as defined in Clause 7.4 of Section 7 — Sub-Total Part A + Sub-Total Part B), in either of the following forms, at the Bidder's option: (a) an unconditional, irrevocable and continuing **Performance Bank Guarantee** in the format prescribed in Section 10 (Annexure — PBG Format); or (b) an **account-payee**

Demand Draft drawn on a scheduled commercial bank in India in favour of **"The Registrar, The Maharaja Bhupinder Singh Punjab Sports University"**, payable at **Patiala**. References in this Contract to the "PBG" include performance security furnished by Demand Draft. Where furnished by Demand Draft, the amount shall be retained by the University as performance security, **without interest**, for the full Contract term plus the claim period, and shall be returned in accordance with Clause 9.16.4.

9.3.1.2 The PBG shall be issued by **any scheduled commercial bank** in India (or a nationalised bank), payable at Patiala, Punjab, and confirmed by a branch located in India. Guarantees issued by co-operative banks, non-scheduled banks or the Bidder's own related entities shall not be accepted.

9.3.1.3 After issue of the Final Acceptance (FAT) certificate, the University may, on the Successful Bidder's request and at the University's discretion, permit substitution of the PBG with a guarantee equal to **5% of the aggregate value of the remaining O&M/AMC term**, valid through the remaining term plus the claim period; performance security stands fixed at 5% — the lower end of the applicable band — as a deliberate facilitation measure consistent with the MSE-oriented posture of this procurement, as recorded in the procurement file.

9.3.2 Validity

9.3.2.1 Where furnished as a Bank Guarantee, the PBG shall remain valid for the **full Contract term plus a claim period of three (3) months** thereafter, i.e., covering the Implementation phase (T0 → Go-Live, up to 9 months) and the subsequent five (5) years of Operations, Maintenance, Support and AMC, plus three (3) months.

9.3.2.2 If the Contract term is extended, or if any obligation of the SI remains outstanding on expiry of the PBG, the SI shall procure a corresponding **extension of validity** of the PBG at least **thirty (30) days before its expiry**, failing which the University shall be entitled to invoke and encash the PBG.

9.3.3 Purpose, Forfeiture and Invocation

The PBG secures the due and faithful performance of all obligations of the SI under the Contract. The University shall be entitled to **invoke and appropriate**, in whole or in part, the PBG (in addition to and without prejudice to any other remedy), upon the occurrence of any of the following:

1. Failure of the SI to perform any obligation under the Contract within the stipulated time or standard;
2. Breach of any term or condition of the Contract not remedied within the applicable cure period;
3. Any loss or damage caused to the University due to the act, default, negligence or misconduct of the SI;
4. Recovery of **Liquidated Damages, penalties, SLA credits or any other sums** due from the SI and not otherwise paid or set off;
5. Termination of the Contract for default of the SI (Clause 9.15);
6. Any misrepresentation, fraud, or breach of the code of integrity by the SI.

9.3.4 Replenishment

Whenever the PBG is invoked/appropriated in part, the SI shall, within **fifteen (15) days** of a written demand, **replenish/restore** the PBG to the value applicable at that time — five per cent (5%) of the total Contract value under Clause 9.3.1.1 or, where substitution has been permitted under Clause 9.3.1.3, the substituted value. Failure to replenish shall itself constitute an event of default.

9.3.5 Release

The PBG shall be discharged and returned to the SI within **sixty (60) days** after the successful completion of the entire Contract term (including exit/transition obligations under Clause 9.16) and after the University is satisfied that all obligations of the SI have been fully and faithfully discharged and no claim or recovery is pending.

> **Reference —** The EMD/Bid Security (₹96,000) of the Successful Bidder may be adjusted towards, or released upon, submission of the PBG, at the University's discretion. EMD/PBG matters are further detailed in Section 2 (*Instructions to Bidders*) and the relevant Annexures in Section 10.

9.4 Contract Term, Commencement, Renewal and Extension

9.4.1 Term

The Contract shall be effective from the Effective Date and shall, unless earlier terminated in accordance with Clause 9.15, remain in force for the following term:

Phase	Duration
Implementation phase	T0 → Go-Live, up to **nine (9) months**
Operations, Maintenance, Support & AMC (post-Go-Live)	**Five (5) years** from Go-Live
Total Contract term	**Implementation (up to 9 months) + 5 years post-Go-Live O&M/AMC**

9.4.2 Commencement

The Implementation phase shall commence on T0 (the Effective Date / date of Notice to Proceed) and the O&M/AMC phase shall commence on the Go-Live date and continue for five (5) years thereafter.

9.4.3 Renewal / Extension

9.4.3.1 The University may, at its sole discretion and by **mutual written consent** of both Parties, **renew or extend** the O&M/AMC term beyond five (5) years, in one or more blocks, on the **same terms, conditions and rates** (or on such revised rates as may be mutually agreed within the ceiling of the accepted rate-card / TCO), for the purpose of continuity of service.

9.4.3.2 Any such extension shall be documented by a written amendment/supplementary agreement, and the SI shall correspondingly extend the validity of the PBG and insurance covers. No extension shall be construed as automatic; the University reserves the right not to extend without assigning any reason.

9.5 Intellectual Property, Source Code and Escrow

9.5.1 Ownership of University Data

9.5.1.1 The University shall be the **sole and exclusive owner of all University Data at all times**, irrespective of where or by whom such data is hosted, processed or stored. The SI acquires no right, title or interest in University Data and shall act solely as a data processor / service provider in respect thereof, strictly on the instructions of the University.

9.5.1.2 The SI shall not sell, licence, assign, mine, aggregate, anonymise for its own benefit, or otherwise exploit University Data, and shall not use it for any purpose other than performance of the Contract (see also Clause 9.7).

9.5.2 Custom Development — University Ownership of IP and Source Code

9.5.2.1 All **Custom Development** (bespoke software, modules, source code, object code, scripts, database schemas, configurations, interfaces, integrations, designs, documentation and other deliverables specifically created for the University under this Contract) shall, upon creation and payment, vest **absolutely, exclusively and perpetually in the University** as "work made for hire".

9.5.2.2 The SI hereby **irrevocably assigns** to the University all present and future intellectual property rights (including copyright and all economic rights) in such Custom Development, worldwide and in perpetuity, and waives all moral rights to the extent permissible in law. The SI shall execute all documents and do all acts necessary to perfect such assignment.

9.5.2.3 The SI shall deliver to the University the **complete, current, buildable and well-documented source code**, build scripts, configuration and technical documentation for all Custom Development, at Go-Live and thereafter upon each material update, and in any event as part of exit management under Clause 9.16.

9.5.3 COTS and SaaS Components — Licence, Source-Code Escrow and Continuity

9.5.3.1 Where the Solution incorporates **COTS** (pre-existing proprietary product) components **deployed on University or University-designated infrastructure**, the SI shall procure for the University a **perpetual, irrevocable, non-exclusive, enterprise-wide licence** to use such COTS software for the University's purposes, covering all its constituent units, affiliated colleges (to the extent applicable) and authorised users, without additional per-user or per-transaction fees beyond the accepted TCO.

9.5.3.2 The SI shall establish and maintain, at its cost, a **source-code Escrow arrangement** with a reputable third-party escrow agent, under a tripartite Escrow Agreement (SI/OEM — Escrow Agent — University), depositing the current source code, build instructions and documentation of the COTS product, and updating the deposit on each major release/version.

9.5.3.3 The Escrow shall be **released to the University** upon the occurrence of specified release events, including: (a) insolvency, liquidation, or cessation of business of the SI/OEM; (b) failure of the SI/OEM to provide contracted maintenance/support; (c) discontinuation/end-of-life of the product without an acceptable migration path; or (d) material uncured breach affecting the University's continued use of the Solution. **(e) expiry of the Contract by efflux of time, non-renewal, or termination for any reason.** On release, the University shall have a **perpetual, irrevocable, royalty-free licence to use, maintain, modify, enhance and support** the released source code for its own purposes, **and to permit any third-party contractor, successor agency or service provider engaged by the University to exercise those rights on its behalf**,

subject only to a written confidentiality undertaking from that third party. The University shall not use the released source code to offer the product commercially to third parties.

9.5.3.4 Where any component of the Solution is offered as a **SaaS / subscription service** (multi-tenant or hosted product), the obligations in Clauses 9.5.3.1 to 9.5.3.3 shall apply as modified below: (a) the SI shall procure for the University a **licence/subscription for the full Contract term at the accepted TCO**, without additional per-user or per-transaction fees beyond the accepted TCO; subscription / licence charges for the implementation phase (T0 to Go-Live) are deemed included in the one-time (Part A) prices, and the five recurring (B.1) years run from Go-Live; (b) the SI shall enable the **export of all University Data and configurations in open, documented formats**, at any time during the term and on exit; (c) the SI shall furnish a **business-continuity undertaking from the OEM** (as per the Manufacturer's Authorisation Form (MAF)); **and (d) the SI shall, at bid stage, elect and evidence,** in the format at Annexure Q (Delivery Approach and Continuity Route Declaration) of Section 10**, one of the two Continuity Routes below, so that the Solution delivers the same continuity end-state as every other delivery approach (Clause 9.5.6):**

Route 1 — Escrowed deployable build. The SI shall place in Escrow, under Clause 9.5.3.2, a **single-tenant deployable build** of the Solution (source code together with the build scripts, deployment artefacts, configuration and data-schema documentation required to build and run it independently), releasable on any event in Clause 9.5.3.3 **including expiry, non-renewal or termination**; or

Route 2 — Pre-committed perpetual fallback licence. The SI shall procure from the OEM, and furnish with the bid, a **binding pre-commitment to grant the University a perpetual, irrevocable, enterprise-wide licence to a functionally equivalent deployable edition** of the product, installable on University-designated infrastructure, exercisable at any time within **twelve (12) months** of expiry, non-renewal or termination, **at no charge beyond the accepted TCO**, that edition also being placed in Escrow under Clause 9.5.3.2.

A hosted / SaaS bid that elects and evidences either Route is **fully responsive** and may attain the maximum marks available under every criterion of Section 8. A hosted / SaaS bid that elects neither Route does not deliver the end-state at Clause 9.5.6 and shall be treated as **non-responsive**.

9.5.3.5 For **custom-developed components**, ownership of intellectual property and source code shall vest in the University as provided in Clause 9.5.2; nothing in this Clause 9.5.3 shall dilute that position.

9.5.6 Uniform Continuity End-State — applicable to every delivery approach

9.5.6.1 The University is **neutral as to technology, architecture, product and hosting**, and shall accept a Custom Development, COTS or hosted / SaaS approach. **The University is not neutral as to the licence, intellectual-property and continuity outcome.** Whichever approach is adopted, the Contract shall deliver the following end-state, which is **fixed, identical for all approaches, and not open to variation**:

(a) **Continued operation without further payment.** On and after expiry of the Contract by efflux of time, non-renewal, or termination for any reason, the University shall be entitled to **continue running the Solution at the then-current functional version, indefinitely and without any further payment** to the SI or the OEM.

(b) **Access to buildable code.** The University shall hold, or be entitled on demand to obtain, the **complete, current, buildable source code** (or, in the case of a pre-existing proprietary product, an equivalent

deployable build under Clause 9.5.3.4) together with the build scripts, deployment artefacts, configuration and data-schema documentation necessary to build, deploy and operate it independently of the SI.

(c) **Freedom to appoint a successor.** The University shall be entitled to have the Solution **maintained, modified, enhanced and supported by any vendor, contractor or agency of its choosing**, or by its own personnel, without the consent of the SI or the OEM and without further payment to either.

(d) **Data.** All University Data shall remain the absolute property of the University and shall be exportable in open, documented formats at any time and on exit.

9.5.6.2 **No bid shall be accepted which does not deliver this end-state in full.** A proposal that would leave the University unable to continue operating the Solution after the Contract term, or unable to have it maintained by a vendor of its choosing, **limits the University's rights within the meaning of the responsiveness provisions of Section 8 and shall be rejected as non-responsive**; the deficiency is not one that may be cured by the award of lower marks.

9.5.6.3 This Clause prevails over any inconsistent provision of these Conditions (including Clauses 9.5.1 to 9.5.5, 9.13, 9.15 and 9.16), Section 3, Section 7 or any Annexure.

9.5.4 IPR Ownership Matrix by Solution Type

The following matrix records the ownership/licence position by category. It is a summary and does not enlarge or restrict Clauses 9.5.1 to 9.5.3. In case of any conflict, **Clause 9.5.6 shall prevail**, and thereafter Clauses 9.5.1 to 9.5.3.

Category / Component	Ownership of IP	Source-code position	University's rights
Custom / bespoke development for the University	**University** (assigned, perpetual)	Full source code handed over to University	Use, modify, reproduce, sub-licence, transfer — unrestricted
COTS / proprietary product component	OEM / SI (retains IP)	Held in **third-party Escrow**; released on trigger events	Perpetual, irrevocable, enterprise-wide licence to use
Integrations, configurations, workflows built on COTS	**University**	Delivered to University	Use, modify, maintain
University Data (all data, at all times)	**University** (sole owner)	N/A	Absolute ownership; return + secure deletion on exit
SI/OEM Background IP & pre-existing IP	SI / OEM (retained)	Not handed over	Non-exclusive licence to the extent embedded in Deliverables, for University's use
Third-party / open-source components	Respective licensors	Per applicable licence	Licence sufficient for lawful University use; SI to disclose OSS and licences

9.5.5 Background IP and Carve-Outs

9.5.5.1 Each Party shall retain ownership of its **Background IP / Pre-existing IP**. To the extent any Background IP of the SI/OEM is embedded in, or necessary for the use of, the Deliverables, the SI grants (and

shall procure that the OEM grants) the University a **perpetual, irrevocable, royalty-free, non-exclusive licence** to **use, and to modify and enhance as part of the Solution,** such Background IP for the University's purposes, **exercisable by the University and by any third-party contractor, successor agency or service provider engaged by it**, subject only to a written confidentiality undertaking.

9.5.5.2 The SI shall clearly identify and disclose, prior to Go-Live, all Background IP, third-party components and open-source software (with their respective licences) incorporated in the Solution. The SI shall not incorporate any component whose licence terms would compromise the University's rights, data ownership, or ability to use/maintain the Solution.

9.5.5.3 The SI warrants that the Deliverables shall not infringe the intellectual property rights of any third party; indemnity for IP infringement is governed by Clause 9.9.

9.6 Confidentiality and Non-Disclosure

9.6.1 Confidential Information

"**Confidential Information**" means all information, in any form, disclosed by or on behalf of the University to the SI, or accessed/generated by the SI in the course of the Contract, including University Data, personal data, financial information, student/athlete records, examination data, security configurations, source code, designs, know-how, and any information marked or reasonably understood to be confidential.

9.6.2 Obligations

9.6.2.1 The SI shall, and shall procure that its personnel, agents and sub-contractors shall: (a) hold all Confidential Information in strict confidence; (b) use it solely for performance of the Contract; (c) not disclose it to any third party without the University's prior written consent; and (d) apply security measures no less rigorous than those required under Clause 9.7 and Section 5 (*Technical Requirements*).

9.6.2.2 The SI shall restrict access to Confidential Information to those of its personnel who have a strict need-to-know for the Contract and who are bound by written confidentiality obligations no less protective than these Conditions. The SI shall, on request, execute and procure individual Non-Disclosure Undertakings from its deployed personnel.

9.6.3 Exclusions

The obligations of confidentiality shall not apply to information that: (a) is or becomes public through no breach by the SI; (b) was lawfully in the SI's possession free of any confidentiality obligation before disclosure; or (c) is required to be disclosed by law, court, or competent authority, provided the SI gives the University prompt prior written notice (where legally permissible) to enable it to seek protective relief.

9.6.4 Survival

> **Note —** The confidentiality and non-disclosure obligations under this Clause 9.6 **shall survive the expiry or termination of the Contract** and shall continue indefinitely in respect of personal data and University Data, and for a minimum period of **five (5) years** in respect of other Confidential Information (or such longer period as any law requires).

9.7 Data Protection and Privacy

9.7.1 Compliance with the DPDP Act, 2023

9.7.1.1 The SI shall, in the processing of any personal data under the Contract, comply fully with the **Digital Personal Data Protection Act, 2023 (DPDP Act)**, the rules and regulations made thereunder, the Information Technology Act, 2000 (and rules), CERT-In directions, and all other applicable data-protection and privacy laws of India, as amended from time to time.

9.7.1.2 The **University is the Data Fiduciary and sole owner** of all University Data (including personal data of students, athletes, employees, and other data principals); the **SI acts solely as a Data Processor** on behalf of, and strictly on the documented instructions of, the University. The SI shall not determine the purposes or means of processing.

9.7.2 Data Residency

> **Mandatory —** All University Data (including personal data, backups, logs and replicas) shall be **stored, hosted and processed within the territory of India**, on infrastructure located in India (data centres empanelled/certified as required, e.g., MeitY-empanelled). No University Data shall be transferred, mirrored, replicated or accessed outside India without the **prior written approval** of the University and strict compliance with the DPDP Act and applicable transfer restrictions.

9.7.3 Purpose Limitation and No Secondary Use

The SI shall process University Data **solely** for the purpose of performing the Contract. The SI shall **not** use, disclose, sell, share, profile, monetise, aggregate, anonymise for its own benefit, or otherwise exploit University Data for any secondary or independent purpose, whether during or after the Contract term.

9.7.4 Security Safeguards

The SI shall implement and maintain appropriate technical and organisational security safeguards (including encryption in transit and at rest, access controls, logging, and the controls specified in Section 5), consistent with **ISO/IEC 27001:2022** and reasonable security practices under Indian law, to protect University Data against unauthorised access, loss, alteration, destruction or breach.

9.7.5 Personal Data Breach — Notification

9.7.5.1 The SI shall notify the University of any **actual or suspected personal data breach or security incident** affecting University Data **immediately and in any case within six (6) hours** of becoming aware of it, followed by a detailed written report within **twenty-four (24) hours**, and shall cooperate fully with the

University in investigation, mitigation, notification to the Data Protection Board of India / CERT-In and to affected data principals, and remediation.

9.7.5.2 The SI shall bear all costs and consequences arising from a data breach attributable to the act, omission, negligence or default of the SI, its personnel or sub-contractors, and shall indemnify the University in accordance with Clause 9.9.

9.7.6 Sub-processing and Assistance

The SI shall not engage any sub-processor for personal data without the University's prior written consent, and shall flow down equivalent data-protection obligations to any approved sub-processor. The SI shall assist the University in fulfilling its obligations as Data Fiduciary, including responding to data-principal requests, consent management, grievance redressal, and audits.

9.7.7 Secure Return and Deletion on Exit

Upon expiry or termination of the Contract, or upon the University's instruction, the SI shall **return all University Data** to the University in a usable, agreed, open format and, thereafter, **securely and irretrievably delete/destroy** all copies of University Data in its possession or control (including backups and those held by sub-processors), and furnish a **certificate of secure deletion** signed by an authorised officer, save where retention is mandated by law (in which case the data shall remain protected and used only for the mandated purpose). This obligation is read together with Clause 9.16 (Exit Management).

9.8 Warranty and Defect Liability

9.8.1 Warranty Period

The SI warrants the entire Solution (all custom-developed and configured COTS components, integrations and deliverables) for a **warranty and defect-liability period of twelve (12) months from the date of Go-Live** ("**Warranty Period**"). Where any component is replaced or materially reworked during the Warranty Period, the warranty for that component shall be extended correspondingly.

9.8.2 Scope of Warranty

9.8.2.1 During the Warranty Period, the SI shall, **at no additional cost** to the University: (a) rectify all defects, bugs, errors and non-conformities; (b) ensure the Solution performs in accordance with the RFP, the approved SRS/BBP, and the accepted Proposal; (c) provide patches, fixes and updates; and (d) meet the applicable SLAs, including the **uptime SLA of 99.5% monthly, measured at the application layer**.

9.8.2.2 The SI warrants that: the Solution is free from material defects and malicious code; it conforms to the agreed specifications and applicable standards; the media, documentation and licences are genuine and valid; and the Solution complies with applicable laws (including accessibility and data-protection requirements).

9.8.3 Defect Liability and Continuity with AMC

9.8.3.1 The Warranty Period shall run concurrently with the commencement of the O&M/AMC phase; warranty obligations shall not be construed to reduce or dilute the SI's AMC/O&M obligations under Section 6. Defects

notified during, but not remedied by the end of, the Warranty Period shall continue to be the SI's responsibility until fully rectified.

9.8.3.2 Rectification during the Warranty Period shall be completed within the timelines set out in the SLA table in Section 6. Persistent or unremedied defects shall entitle the University to invoke penalties (Clause 9.17) and/or the PBG (Clause 9.3).

9.8.3.3 Services owed to the University free of charge under the warranty in this Clause 9.8 shall not be separately charged or double-counted within the paid O&M/AMC scope during the Warranty Period; the quoted O&M/AMC price shall be deemed to account for this overlap.

9.9 Indemnification

9.9.1 SI's Indemnity

The SI shall, at its own cost, **indemnify, defend and hold harmless** the University, its officers, employees and authorised agents from and against any and all claims, actions, suits, proceedings, losses, damages, liabilities, penalties, fines, costs and expenses (including reasonable legal fees) arising out of or in connection with:

1. **Intellectual property infringement** — any claim that the Solution, Deliverables or any component thereof infringes or misappropriates the intellectual property rights of any third party;
2. **Third-party claims** — death, personal injury, or loss of/damage to property caused by the act, omission, negligence or default of the SI, its personnel or sub-contractors;
3. **Data breach / privacy violation** — any breach of Clause 9.6 or 9.7, loss or unauthorised disclosure of University Data or personal data, or violation of the DPDP Act attributable to the SI;
4. **Statutory non-compliance** — any breach by the SI of applicable laws, including labour laws, EPF/ESI, tax laws, and licensing/regulatory requirements (Clause 9.20);
5. **Breach of representations, warranties or obligations** under the Contract, and any fraud, wilful misconduct or gross negligence of the SI.

9.9.2 IP Infringement — Additional Remedies

In the event of an IP infringement claim, the SI shall, at its cost and option, either: (a) procure for the University the right to continue using the affected component; (b) modify or replace it with a non-infringing equivalent of at least equal functionality; or (c) if neither is feasible, refund the amounts paid for the affected component and reimburse the University for reasonable substitution costs — in each case without prejudice to the University's other remedies.

9.9.3 Procedure

The University shall notify the SI of any indemnifiable claim, provide reasonable cooperation (at the SI's expense), and permit the SI to conduct the defence/settlement, provided that no settlement adversely affecting the University shall be made without the University's prior written consent.

9.9.4 Survival

The indemnities under this Clause 9.9 shall survive the expiry or termination of the Contract.

9.10 Limitation of Liability

9.10.1 Aggregate Cap

Subject to Clause 9.10.2, the aggregate liability of either Party arising out of or in connection with the Contract, whether in contract, tort (including negligence) or otherwise, shall **not exceed the total Contract Value** (as defined in Clause 7.4 of Section 7) (i.e., the accepted 5-year TCO).

9.10.2 Carve-Outs

> **Important —** The limitation of liability in Clause 9.10.1 shall **NOT apply** to the liability of the SI in respect of: (a) **wilful misconduct, fraud or gross negligence**; (b) **infringement of intellectual property rights**; (c) **breach of confidentiality** (Clause 9.6); (d) **data breach / breach of data-protection obligations** (Clause 9.7); (e) amounts payable under the **indemnities** in Clause 9.9; and (f) Liquidated Damages, penalties and SLA credits **up to their respective contractually stipulated caps** (LD capped at 10% of the total contract value per Clause 9.17 and Section 7; aggregate SLA penalties capped at 10% of the relevant quarter's O&M/AMC invoice value per Section 6), which amounts shall not count towards, and shall be recoverable in addition to, the aggregate cap in Clause 9.10.1. Liabilities under carve-outs (a) to (e) shall be unlimited (or as otherwise fixed by law).

9.10.3 Exclusion of Indirect Damages

Neither Party shall be liable for indirect, incidental, special or consequential loss (including loss of profit not directly attributable to a breach), except to the extent arising under the carve-outs in Clause 9.10.2. Nothing in this Clause shall limit any liability that cannot be limited under applicable law.

9.11 Insurance

9.11.1 Required Covers

The SI shall, at its own cost, obtain and maintain in force throughout the Contract term (including the transition period) adequate insurance policies from insurers registered in India, including, at minimum:

Cover	Purpose
Professional Indemnity / Errors & Omissions	Covering deficiency in professional services / negligence
Cyber-liability / Data-breach cover	Covering data breach, loss and third-party claims
Public/Third-party liability	Covering injury to persons and damage to property
Workmen's Compensation / Employees' liability	Statutory cover for deployed personnel
Asset / equipment cover (as applicable)	For SI-owned assets used at University premises

9.11.2 Obligations

The SI shall furnish copies of the policies (and renewals) to the University on request, shall keep the covers valid and adequate, and shall not do anything that renders any policy void or voidable. Insurance shall not relieve the SI of any liability or obligation under the Contract, and any uninsured or under-insured loss attributable to the SI shall be borne by the SI.

9.12 Sub-Contracting and Assignment

9.12.1 Sub-Contracting

9.12.1.1 The SI shall **not sub-contract or sub-let** the whole or any part of the Contract without the **prior written consent** of the University. Any consent, if granted, shall not relieve the SI of any of its obligations or liabilities under the Contract.

9.12.1.2 The **SI shall remain solely and fully responsible and liable** to the University for the acts, omissions, defaults and performance of all its sub-contractors (including any OEM/partner under a back-to-back arrangement) as if they were the acts of the SI itself. The SI shall flow down all applicable obligations (including confidentiality, data protection, security and IPR) to its approved sub-contractors.

9.12.1.3 The OEM–SI back-to-back MoU disclosed at the bid stage (consortium being not permitted, as per Section 2) shall be honoured; any change in such arrangement requires the University's prior written approval.

9.12.2 Assignment

Neither Party shall assign, transfer, charge or otherwise deal with the Contract or any rights or obligations thereunder without the prior written consent of the other Party, **save that** the University may assign or novate the Contract, in whole or in part, to any successor entity, department, or Government body, upon written notice to the SI. Any purported assignment in breach of this Clause shall be void.

9.13 Change Control and Change-Request Procedure

9.13.1 Principle

Either Party may propose changes to the scope, deliverables, or specifications of the Contract. No change shall be implemented, and no additional payment shall accrue, except through the formal change-control procedure below, documented in a signed **Change Request (CR)**.

9.13.2 Procedure

1. **Initiation** — The requesting Party issues a written change request describing the proposed change.
2. **Impact assessment** — The SI shall, within a reasonable time (ordinarily **seven (7) working days**), submit an impact assessment covering scope, effort, timeline, deliverables, risks, and cost/credit implications.
3. **Pricing** — Any incremental effort shall be priced strictly in accordance with the **agreed rate-card / man-day rates** submitted with the financial bid (BOQ) in Section 7; no rates in excess of the accepted rate-card

shall apply. Rate-card pricing is subject to the benchmarking and annual aggregate cap stated in Section 7 (Part C note).

4. **Approval** — No change shall take effect until approved in writing by the University's competent authority. Minor changes / clarifications not affecting cost, scope or timeline shall be handled through the project-governance mechanism without a priced CR.
5. **Documentation** — Approved changes shall be recorded, version-controlled, and appended to the Contract.

> **Note —** Correction of defects, non-conformities, or omissions necessary to meet the RFP, approved SRS/BBP or accepted Proposal shall **not** qualify as a chargeable change and shall be carried out by the SI at no additional cost.

9.14 Force Majeure

9.14.1 Definition

"**Force Majeure**" means an event or circumstance beyond the reasonable control of the affected Party, which could not have been foreseen or prevented by the exercise of reasonable diligence, including acts of God, natural calamities (flood, earthquake, storm), fire, epidemic/pandemic, war, hostilities, terrorism, civil commotion, riots, and lawful acts of Government or restraint of the State (other than those arising from the affected Party's own default).

9.14.2 Effect and Procedure

9.14.2.1 Neither Party shall be liable for failure or delay in performing its obligations (other than payment obligations for services already rendered) to the extent such failure/delay is caused by a Force Majeure event. Force Majeure shall **not** excuse obligations relating to the security, confidentiality, protection, return or non-corruption of University Data.

9.14.2.2 The affected Party shall notify the other in writing within **seven (7) days** of the onset of the event, provide reasonable particulars, use all reasonable endeavours to mitigate and resume performance, and notify the cessation of the event.

9.14.3 Prolonged Force Majeure

If a Force Majeure event continues for a period exceeding **ninety (90) consecutive days**, either Party may terminate the Contract by written notice, in which case the Parties shall settle accounts for work duly performed up to the date of termination, without penalty, and the SI shall comply with exit-management obligations under Clause 9.16.

9.15 Termination

9.15.1 Termination for Default

9.15.1.1 The University may, without prejudice to any other remedy, terminate the Contract in whole or in part by written notice on the occurrence of a material default by the SI, including: (a) failure to perform any material obligation or achieve any milestone within the stipulated/cure period; (b) accrual of **Liquidated Damages to the ceiling of 10%** of Contract value; (c) persistent or repeated breach of the Service Level Agreements constituting material breach; without limitation, the aggregate quarterly SLA-penalty cap (Section 6) being reached in three (3) consecutive quarters shall be **deemed** material breach for this purpose; (d) breach of confidentiality, data protection, IPR or code-of-integrity obligations; (e) fraud, misrepresentation, or corrupt/fraudulent practice; or (f) abandonment of the Contract.

9.15.1.2 The University shall issue a written **cure notice** granting the SI a period of ordinarily **thirty (30) days** (or such shorter period for critical breaches, including data-protection breaches) to remedy the default; if the default is not cured to the University's satisfaction within such period, the University may terminate forthwith.

9.15.2 Termination for Convenience

The University may terminate the Contract, in whole or in part, **for convenience** at any time by giving the SI **not less than sixty (60) days'** prior written notice, without assigning any reason. In such event, the SI shall be paid for services duly rendered and deliverables duly accepted up to the effective date of termination; the University shall not be liable for loss of anticipated profit or consequential loss.

9.15.3 Termination for Insolvency

The University may terminate the Contract with immediate effect by written notice if the SI becomes bankrupt or insolvent, has a receiver/liquidator/administrator appointed, enters into insolvency proceedings under the Insolvency and Bankruptcy Code, 2016, makes an arrangement with creditors, or ceases (or threatens to cease) to carry on business.

9.15.4 Consequences of Termination and Recoveries

Upon termination (for any reason):

1. The SI shall promptly hand over all Deliverables, University Data, source code, configurations, documentation, licences and knowledge, and comply fully with the **Exit Management** obligations in Clause 9.16; for SaaS / subscription components this includes release of the Route 1 escrow deposit or grant of the Route 2 fallback licence elected under Clause 9.5.3.4, and handover is not complete until the University holds a running instance and the rights set out at Clause 9.5.6.1(a)-(c);
2. In the case of termination for **SI default or insolvency**, the University may **invoke the PBG**, recover Liquidated Damages, penalties, excess re-procurement costs, and any other losses, and may engage a third party to complete the work at the SI's risk and cost;
3. The University may **set off** any amounts due to the SI against amounts recoverable from the SI (Clause 9.17);
4. Accrued rights, obligations and remedies of the Parties, and provisions which by their nature survive (including Clauses 9.5, 9.6, 9.7, 9.9, 9.10, 9.16, 9.18), shall survive termination.

> **Important —** Termination shall not, under any circumstances, entitle the SI to withhold, disable, encrypt-lock, or degrade access to the Solution or University Data, or to invoke any lock-in. The SI shall ensure continuity of critical services during the notice and transition period.

9.16 Exit Management and Transition

9.16.1 Objective — No Lock-In

The Contract is structured to ensure **continuity of service and the absence of any vendor lock-in**. Upon expiry or termination of the Contract (for any reason), the SI shall provide full cooperation to enable a smooth, orderly transition of the Solution and services to the University or to a replacement service provider nominated by the University.

9.16.2 Exit Management Plan

The SI shall prepare and maintain, and update at least annually, an **Exit Management / Transition Plan** (first draft to be submitted within ninety (90) days of Go-Live and approved by the University), covering knowledge transfer, handover inventory, data and source-code handover, roles, timelines and acceptance criteria.

9.16.3 Scope of Exit / Transition Obligations

During the exit/transition period, the SI shall, at no additional cost beyond the accepted contract price (save where the transition is occasioned by the University's convenience termination, in which case reasonable, pre-agreed transition charges from the rate-card may apply):

1. Provide **structured knowledge transfer** and training to University staff and/or the incoming provider;
2. Hand over **complete University Data** in a usable, documented, open/interoperable format, together with data dictionaries and migration support;
3. Hand over the **complete source code, build scripts, configurations, environment details, credentials, licences and technical/operational documentation** (including release of Escrow where applicable under Clause 9.5.3); for SaaS / subscription components this includes release of the Route 1 escrow deposit or grant of the Route 2 fallback licence elected under Clause 9.5.3.4, and handover is not complete until the University holds a running instance and the rights set out at Clause 9.5.6.1(a)-(c);
4. Provide **reverse-transition / handholding assistance for a period of up to three (3) months** (extendable by mutual consent) to stabilise the environment under the new arrangement;
5. Continue to render contracted services during the transition period, maintaining agreed SLAs, until the University certifies completion of transition;
6. **Securely delete University Data** from its systems and furnish a certificate of secure deletion, in accordance with Clause 9.7.7.

The exit and transition workflow is summarised below.



9.16.4 Certification and Release

The PBG and any amounts withheld by way of set-off under Clause 9.17.2 shall be released only after the University certifies the **successful completion of exit and transition** and confirms full handover of data, source code and knowledge in accordance with this Clause; for SaaS / subscription components this includes release of the Route 1 escrow deposit or grant of the Route 2 fallback licence elected under Clause 9.5.3.4, and handover is not complete until the University holds a running instance and the rights set out at Clause 9.5.6.1(a)-(c).

9.17 Penalties, Recoveries and Set-Off

9.17.1 Liquidated Damages and SLA Credits

9.17.1.1 For delay in achievement of any milestone attributable to the SI, **Liquidated Damages (LD) of 0.5% of the delayed milestone value per week (or part thereof)** shall be levied, subject to an **overall ceiling of**

10% of the total Contract Value as defined in Clause 7.4 of Section 7, as detailed in Section 7 (*Pricing and Payment Terms*).

9.17.1.2 SLA breaches (including the **99.5% monthly uptime SLA**) shall attract service-level credits/penalties as specified in the SLA table in Section 6. LD and SLA credits are **genuine pre-estimates of loss** and not penalties in the punitive sense, and their levy shall not require proof of actual loss.

9.17.2 Recovery and Set-Off

9.17.2.1 The University shall be entitled to **recover and set off** any LD, SLA credits, penalties, over-payments, or other sums due from the SI against: (a) any amount payable to the SI under this or any other contract; (b) the PBG; and/or (c) any other security or amount available.

9.17.2.2 Recovery under this Clause shall be without prejudice to, and in addition to, the University's other rights and remedies, including termination and invocation of indemnities.

9.18 Dispute Resolution, Arbitration and Jurisdiction

9.18.1 Amicable Settlement

The Parties shall use their best efforts to settle amicably, through mutual consultation and negotiation, any dispute, controversy or claim arising out of or relating to the Contract. Either Party may, by written notice, refer a dispute for resolution first to the **Project Steering Committee** and, if unresolved within **thirty (30) days**, to escalation between the Registrar (or nominee) and a senior officer of the SI, who shall endeavour to settle it within a further **thirty (30) days**.

9.18.2 Arbitration

9.18.2.1 If the escalation under Clause 9.18.1 fails to resolve the dispute, the Parties shall first attempt to settle the dispute by **mediation under the Mediation Act, 2023**, for a period of up to **sixty (60) days** from the date such escalation fails. Any dispute not settled by such mediation, and whose **claimed value does not exceed ₹10 Crore**, shall be **referred to and finally resolved by arbitration** in accordance with the **Arbitration and Conciliation Act, 1996** (and any statutory modification or re-enactment thereof). Disputes whose claimed value exceeds ₹10 Crore shall not be referred to arbitration and shall lie exclusively with the competent courts at Patiala, Punjab, in accordance with Clause 9.18.3.

9.18.2.2 The arbitral tribunal shall consist of a **sole arbitrator** appointed by mutual consent of the Parties; failing consensus within thirty (30) days, the tribunal shall consist of **three (3) arbitrators**, one nominated by each Party and the third (presiding arbitrator) nominated by the two nominated arbitrators.

9.18.2.3 The **seat and venue of arbitration shall be Patiala, Punjab**; the **language** of arbitration shall be **English**; and the arbitral award shall be final and binding on the Parties. Each Party shall bear its own costs unless the tribunal directs otherwise.

9.18.2.4 The existence of a dispute or arbitration shall not relieve the SI of its obligation to continue performance of the Contract (save for any matter that is the subject of the dispute), and payments not in dispute shall continue.

9.18.2.5 This graduated dispute-resolution mechanism (escalation, followed by mediation, with arbitration confined to disputes whose claimed value does not exceed ₹10 Crore and higher-value disputes reserved to the competent courts) follows current Government guidance on arbitration in domestic public procurement, as recorded by the competent authority.

9.18.3 Governing Law and Jurisdiction

The Contract shall be governed by and construed in accordance with the **laws of India**. Subject to the arbitration clause above, the **courts at Patiala, Punjab, shall have exclusive jurisdiction** over all matters arising out of or relating to the Contract.

9.18.4 Rights of Micro and Small Enterprises

Nothing in this Clause 9.18 derogates from the rights of a supplier that is a registered micro or small enterprise under Chapter V of the MSMED Act, 2006, including reference of a payment dispute to the Micro and Small Enterprises Facilitation Council.

9.19 Conflict of Interest, Code of Integrity and Anti-Corruption

9.19.1 Conflict of Interest

The SI shall not have, and shall disclose forthwith, any actual or potential **conflict of interest** that may compromise its impartial performance of the Contract. The SI shall not, during the Contract term, engage in any activity that conflicts with the interests of the University.

9.19.2 Code of Integrity and Anti-Corruption

9.19.2.1 The SI shall comply with the **Code of Integrity** applicable under the Punjab public-procurement framework and shall not, directly or indirectly, engage in any **corrupt, fraudulent, collusive, coercive or obstructive practice**, or offer/give/agree to give any inducement, gratification, commission or bribe to any person in connection with the procurement or the Contract.

9.19.2.2 Breach of the Code of Integrity shall entitle the University to reject the bid, terminate the Contract, forfeit the EMD/PBG, recover damages, and **blacklist/debar** the SI, in accordance with applicable rules, without prejudice to any legal action.

9.19.3 Anti-Corruption Declaration

The SI shall execute and abide by the **Anti-Corruption, Anti-Collusion & Conflict-of-Interest Declaration** in the format prescribed in Section 10 (Annexures and Forms), which shall form part of the Contract and remain in force through the Contract term.

9.19.4 Fall Clause

> **Note — Fall Clause —** The SI warrants that the prices charged to the University under this Contract shall **not exceed** the lowest price at which the SI supplies goods/services of identical or substantially similar description and terms to any other customer during the Contract term. If, during the Contract term, the SI offers a lower price to any other buyer for comparable scope, the SI shall **forthwith notify the University and reduce its price** to the University to that lower level, with effect from the date of such lower quotation, and refund any excess already charged.

9.20 Statutory and Regulatory Compliance

9.20.1 General Compliance

The SI shall, at its own cost, comply with all applicable **Central, State and local laws, rules, regulations, notifications, licences and permits** relevant to the performance of the Contract, and shall keep all such registrations and licences valid throughout the Contract term.

9.20.2 Labour and Social-Security Laws

The SI shall comply with all applicable **labour laws**, including the Employees' Provident Funds and Miscellaneous Provisions Act (**EPF**), the Employees' State Insurance Act (**ESI**), the Minimum Wages Act, the Payment of Wages Act, the Contract Labour (Regulation and Abolition) Act, and the applicable Labour Codes, in respect of all personnel deployed for the Contract. The SI shall be the **sole employer** of its personnel; no employer–employee relationship shall arise between the University and the SI's personnel.

Deployed personnel — payroll and conduct. Without limiting the foregoing, in respect of every person deployed by the SI for this Contract, whether on-site at the University or off-site:

1. the **salaries, wages, allowances and all statutory dues** (EPF, ESI, gratuity, bonus, leave encashment, TDS) of such personnel shall be paid **solely by the SI**, in full and **on time, irrespective of the status of any payment due from the University to the SI**; the University shall bear no liability whatsoever for their remuneration or dues;
2. the SI shall, on demand, produce **payroll registers and EPF/ESI challans** for deployed personnel, and shall obtain and maintain any registration or licence required under the Contract Labour (Regulation and Abolition) Act, 1970 at its own cost;
3. on-site personnel shall carry **SI-issued photo identity cards**, shall have undergone the SI's **background verification**, and shall abide by the University's campus rules, security and safety instructions, and the University's **POSH** framework while on campus;
4. the University may, for reasons recorded, require the **replacement** of any deployed person, and the SI shall replace such person within fifteen (15) days with an equal-or-better substitute at no additional cost; and
5. any claim by or in respect of the SI's personnel (wages, statutory dues, compensation, or injury on campus) shall be the SI's sole responsibility, covered by the indemnity at Clause 9.9 and the insurance at Clause 9.11.

9.20.3 Taxes

The SI shall be responsible for payment of all **taxes, duties, cesses and levies** (including GST) applicable to it under law. The University shall deduct tax at source (TDS/TCS) as required by law. The accepted TCO/BOQ position and treatment of taxes shall be as set out in Section 7.

9.20.4 Records and Audit

The SI shall maintain proper statutory records and, on reasonable notice, permit the University (or its authorised auditors / Government audit authorities) to inspect and audit records relevant to the Contract, including compliance with labour, tax and data-protection obligations.

9.21 Notices, Amendment, Waiver, Severability and Entire Agreement

9.21.1 Notices

9.21.1.1 All notices under the Contract shall be in **writing, in English**, and delivered by hand, registered post/speed post, courier, or e-mail (with delivery/read confirmation) to the address of the receiving Party specified in the Agreement. Notices to the University shall be addressed to **The Registrar, MBSPSU, Patiala**.

9.21.1.2 A notice shall be deemed received: if by hand, on delivery; if by post/courier, on the **fifth (5th) working day** after dispatch; and if by e-mail, on the next working day after transmission (absent a delivery-failure notice), subject to a hard copy following where the Agreement so requires.

9.21.2 Amendment

No amendment, modification or variation of the Contract shall be valid or binding unless made in **writing** and **signed by the authorised representatives of both Parties** (through the change-control mechanism in Clause 9.13 where applicable).

9.21.3 Waiver

No failure or delay by either Party in exercising any right, power or remedy under the Contract shall operate as a **waiver** thereof, nor shall any single or partial exercise preclude any further exercise. Any waiver shall be effective only if in writing and signed by the waiving Party, and shall apply only to the specific instance for which it is given.

9.21.4 Severability

If any provision of the Contract is held to be invalid, illegal or unenforceable by a competent authority, such provision shall be **severed** to the minimum extent necessary, and the remaining provisions shall continue in full force and effect. The Parties shall negotiate in good faith to replace the severed provision with a valid one that achieves, as nearly as possible, the original intent.

9.21.5 Entire Agreement

The Contract Documents (as defined in Clause 9.1.2, read with the order of precedence in Clause 9.1.3) constitute the **entire agreement** between the Parties in respect of its subject matter and **supersede** all prior negotiations, representations, understandings and communications, whether oral or written. No representation or warranty not expressly set out in the Contract Documents shall be binding on either Party.

9.21.6 Relationship of the Parties

Nothing in the Contract shall be construed as creating a partnership, joint venture, agency or employment relationship between the Parties. The SI shall act as an **independent contractor**, and neither Party shall have authority to bind the other except as expressly provided.

> **Mandatory —** By submitting a bid in response to this RFP, the Bidder confirms that it has read, understood and **unconditionally accepts** all the General and Special Conditions of Contract set out in this Section 9, and agrees to be bound by them upon award. Any conditional acceptance, deviation or reservation to these Conditions may render the bid liable to rejection under Section 2 (*Instructions to Bidders*).

Section 10 — Annexures and Bid Forms

This Section provides the ready-to-use form templates that the Bidder shall complete, compile, sign and upload as part of its bid against Tender Reference No. **MBSPSU/PUR/ERP/2026/01**. The Annexures are the prescribed formats for the declarations, statements and pricing required elsewhere in this RFP; they must be read together with Section 2 (Instructions to Bidders), Section 7 (Pricing and Payment Terms) and Section 8 (Evaluation Criteria).

> **Mandatory —** Every form in this Section shall be reproduced on the **Bidder's official letterhead**, completed without alteration to its substance or sequence, and **signed and stamped on every page by the Bidder's authorised signatory**, then scanned clearly and legibly and uploaded as PDF on the **Punjab e-Procurement Portal (https://eproc.punjab.gov.in)**.

10.1 How to use these forms

- **Do not delete, renumber or reorder** any Annexure. If an item is not applicable, the Bidder shall write "**Not Applicable**" and state the reason; blank fields will be read against the Bidder.
- Where a form provides fill-in blanks shown as " _____ ", the Bidder shall enter the correct particulars legibly (typed) in place of the underscores.
- Where a form is a table, the Bidder shall complete every row and may add rows of the same format where the instruction permits (e.g., additional projects, additional line items).
- Every supporting document referred to in a form shall be **cross-indexed by page number** in the uploaded bid so that the Evaluation Committee can trace it.
- All monetary figures shall be in **Indian Rupees (₹)**. Where both figures and words are required, the two shall agree; in case of a discrepancy, **words shall prevail**.

10.1.1 Cover-wise placement of Annexures

The bid is submitted online in a **Two-Cover (Two-Bid)** structure. The Annexures shall be placed strictly in the cover indicated below.

Cover	Contents	Annexures to be enclosed
Cover-1 — Fee/EMD + Technical Bid	Tender fee proof, EMD/Bid-Security, all eligibility, technical and compliance documents	**A, B, C, D, E, F, G, H, J, L, M, N, O, Q**
Cover-2 — Financial Bid	Priced Bill of Quantities only	**I** (Financial Bid / BOQ) — **and nothing else**

> **Note —** Annexure **K (Performance Bank Guarantee Proforma)** is a post-award instrument. It is **not** enclosed with the bid in either cover; it is furnished by the successful Bidder after the Letter of Award, within the period stipulated in Section 9.

The two-cover placement is summarised below.



> **Important —** The Financial Bid (Annexure I) — or any figure, rate, discount or price disclosing the Bidder's commercials — shall **NOT** appear anywhere in Cover-1 or in any technical Annexure. Any disclosure of price in Cover-1 shall render the entire bid **liable to summary rejection** under Section 2 and Section 8.

10.1.2 Index of Annexures

Annexure	Title	Cover
A	Form of Bid Submission / Covering Letter (Technical)	Cover-1
B	Bidder's Profile / General Information	Cover-1
C	Pre-Qualification Compliance Sheet	Cover-1
D	Financial Capability Statement (CA-certified)	Cover-1
E	Project Experience / Citation Format	Cover-1
F	Functional Requirements Compliance Sheet	Cover-1
G	Technical Requirements Compliance Sheet	Cover-1
H	Proposed Team / Key Personnel + CV Format	Cover-1
I	**Financial Bid / Bill of Quantities (BOQ)**	**Cover-2**

Annexure	Title	Cover
J	EMD Details / Bid-Security Declaration	Cover-1
K	Performance Bank Guarantee (PBG) Proforma	Post-award (not enclosed with bid)
L	Self-Declaration of Non-Blacklisting / Non-Debarment	Cover-1
M	Anti-Corruption, Anti-Collusion & Conflict-of-Interest Declaration	Cover-1
N	Power of Attorney + Manufacturer's Authorisation Form (MAF)	Cover-1
O	Statement of Deviations	Cover-1
P	**Pre-Bid Query Format**	**Not enclosed with the bid — submitted by e-mail before the pre-bid query deadline (Clause 2.7.2)**
Q	**Delivery Approach and Continuity Route Declaration**	**Cover-1**

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

A

ANNEXURE A

Form of Bid Submission / Covering Letter (Technical)

Section 10 — Annexures and Bid Forms

Annexure A — Form of Bid Submission / Covering Letter (Technical)

Instruction: Reproduce on the Bidder's letterhead, complete the blanks, and have it signed and stamped by the authorised signatory. This letter constitutes the Bidder's formal offer and shall be the first document in Cover-1.

> **Note —** This covering letter accompanies the **Technical Bid only**. It must not state, imply or annex any price.

Date: _____ (DD/MM/YYYY)

To,
The Registrar (Tendering Authority),
The Maharaja Bhupinder Singh Punjab Sports University (MBSPSU),
Adjoining Rajiv Gandhi National Law University, Bhadson Road,
Patiala – 147006, Punjab.

Subject: Submission of Technical Bid against **Tender Reference No. MBSPSU/PUR/ERP/2026/01** — Selection of an Agency for the Design, Development and Implementation of an Enterprise Resource Planning (ERP) System at MBSPSU.

Sir/Madam,

1. Having examined the Request for Proposal (RFP) document, including all its Sections, Annexures, and Corrigenda/Addenda issued up to the last date of submission, the receipt of which is hereby acknowledged, we, _____ (legal name of the Bidder), having our registered office at _____, hereby offer to design, develop, implement, host, operate, maintain and support the ERP System for the University in full conformity with the said RFP.
2. We confirm that we have read and understood, and we **unconditionally accept**, all terms, conditions, specifications and requirements of the RFP, including the General and Special Conditions of Contract in Section 9, except only for those deviations (if any) expressly listed in **Annexure O (Statement of Deviations)**. We understand that deviations not so listed shall be treated as withdrawn.
3. We agree to abide by this bid, and it shall remain **binding upon us and open for acceptance for a period of 180 (one hundred and eighty) days** from the last date of bid submission, and it may be accepted by the University at any time before the expiry of that period.
4. We confirm that the prices quoted in our **Financial Bid (Annexure I)**, submitted separately in Cover-2, are firm and have **not been disclosed** in this Technical Bid or in any document placed in Cover-1.
5. We enclose the required **Tender Document Fee of ₹5,000** and **Earnest Money Deposit (Bid Security) of ₹96,000** — or, where we claim exemption as an MSE (valid Udyam) / DPIIT-recognised Startup under Clause 2.2A of Section 2, the relevant valid certificate together with the Bid-Security Declaration — as detailed in **Annexure J**.
6. We hereby declare that:

- all information and statements made in this bid and its Annexures are **true, correct and complete** to the best of our knowledge and belief, and we understand that any misrepresentation shall be a ground for rejection, forfeiture of EMD, and/or debarment;
- we are **not blacklisted, debarred or declared ineligible** by any Central/State Government, PSU, University or public agency as on the date of bid submission (per **Annexure L**);
- we possess the legal, technical, financial and managerial capacity to perform the Contract;
- we have not engaged in any corrupt, fraudulent, collusive or coercive practice in connection with this bid (per **Annexure M**);
- we **adopt the scanned signatures** on every document uploaded with this bid as our own, **ratify the submission** made through our registered account on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in), and shall not deny the execution, authenticity or integrity of any document whose hash matches the Portal's system-generated acknowledgement (Clause 2.6A of Section 2); and
- we agree that the University is not bound to accept the lowest or any bid, and may annul the bidding process, without incurring any liability or any obligation to state reasons.

7. We agree that, if selected, we shall furnish a **Performance Bank Guarantee equal to 5% of the total contract value**, valid for the full contract term plus a three-month claim period, in the form of **Annexure K** or as an account-payee Demand Draft per Clause 9.3 of Section 9, and shall execute the Contract within the period stipulated in Section 9.
8. The authorised signatory who signs this bid is duly empowered to make this offer and to bind us, as evidenced by the Power of Attorney at **Annexure N**.

Yours faithfully,

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
For and on behalf of (legal name of Bidder)	_____
Place	_____
Date	_____

Particulars	Details
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

B

ANNEXURE B

Bidder's Profile / General Information

Section 10 — Annexures and Bid Forms

Annexure B — Bidder's Profile / General Information

Instruction: Complete every field. Attach documentary proof (certificate of incorporation, PAN, GST) and cross-index the page numbers.

#	Particulars	Details
1	Legal name of the Bidder	_____
2	Constitution (Company / LLP / Partnership / Society / Other)	_____
3	Date of incorporation / registration	_____
4	Registration / CIN / LLPIN number	_____
5	Number of completed years in continuous operation (as on bid-submission date)	_____
6	Registered office address (with PIN)	_____
7	Punjab office / support office address, if any (Patiala preferred)	_____
8	Other existing office(s) in India (cities)	_____
9	Permanent Account Number (PAN)	_____
10	GST Identification Number (GSTIN)	_____
11	ISO 9001:2015 certificate no. & validity	_____
12	ISO/IEC 27001:2022 certificate no. & validity	_____
13	ISO/IEC 20000-1:2018 certificate no. & validity	_____
14	Udyam Registration No. & category (Micro / Small), if claiming MSE benefits under Clause 2.2A	_____
15	DPIIT Startup Recognition No. & validity, if claiming Startup benefits under Clause 2.2A	_____
16	Total technical professionals on rolls (as on bid date)	_____
17	Authorised contact person (name)	_____
18	Designation of contact person	_____

#	Particulars	Details
19	Email (official)	_____
20	Mobile / telephone	_____
21	Company website	_____
22	Authorised signatory — name	_____
23	Authorised signatory — designation	_____
24	Power of Attorney / Board Resolution — reference no. & date	_____
25	Bank account for refunds (bank, branch, A/c no., IFSC)	_____

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name (in block capitals)	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

> **Reference —** The eligibility of the above particulars is assessed against the thresholds in Section 2 and **Annexure C**.

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

C

ANNEXURE C

Pre-Qualification Compliance Sheet

Section 10 — Annexures and Bid Forms

Annexure C — Pre-Qualification Compliance Sheet

Instruction: For each canonical eligibility criterion, state "Yes" or "No" for compliance and give the exact supporting document and page reference in the uploaded bid. Non-compliance with any mandatory criterion shall render the bid liable to rejection.

#	Eligibility Criterion	Requirement	Complied (Yes/No)	Supporting Document & Page Ref
1	Legal entity & vintage	Incorporated/registered in India (Companies Act 2013 / LLP Act / Partnership) and in **continuous operation ≥ 3 years** as on bid-submission date — *waived for DPIIT-recognised Startups (Clause 2.2A)*	_____	_____
2	Financial turnover & net worth	**Average annual turnover ≥ ₹50 Lakh** (average of FY 2022-23, 2023-24, 2024-25) from IT / software / ERP services, and **positive net worth** in the latest FY (CA-certified) — *MSE (Udyam) / DPIIT Startup: ≥ ₹25 Lakh (Clause 2.2A)*	_____	_____
3	Project experience	ERP / campus / university / institution-management solutions successfully implemented in **≥ 2 institutions in the last 7 years**, of which **≥ 1 in a Government / Public University or HEI**, with **at least one order ≥ ₹20 Lakh** — *MSE (Udyam) / DPIIT Startup: ≥ 1 completed institutional software implementation, any value (Clause 2.2A)*	_____	_____
4	Certifications	Valid **ISO 9001:2015** and **ISO/IEC 27001:2022 (ISMS)** — no relaxation; plus valid **ISO/IEC 20000-1:2018 (ITSM)** or documented, auditable ITSM processes aligned to ISO/IEC 20000-1 with an undertaking to obtain certification within 12 months of award (per PQ-4) — equivalence-route Bidders shall enclose: mapped ITSM policy/SOPs, ≥6 months' operating evidence, and the 12-month certification undertaking	_____	_____
5	Non-blacklisting	**Not blacklisted / debarred** by any Central/State Govt, PSU or University/agency as on bid date (affidavit)	_____	_____
6	Statutory registration	Valid **GST registration** and **PAN**	_____	_____

#	Eligibility Criterion	Requirement	Complied (Yes/No)	Supporting Document & Page Ref
7	Manpower	Minimum **10 technical professionals** on rolls — *MSE (Udyam) / DPIIT Startup: minimum 5 (Clause 2.2A)* — plus key-personnel commitment per Annexure H (self-certified + PF/ESI proof)	_____	_____
8	Support presence	Existing office in India; commitment to a support/project office **within Punjab (Patiala preferred)** during the contract	_____	_____
9	Bid formalities	RFP purchased/downloaded; **tender fee & EMD** paid **or valid exemption claimed under Clause 2.2A**; single bid per bidder; consortium not permitted (OEM–SI back-to-back MoU allowed with primary bidder as SI)	_____	_____
10	MSE / Startup relaxation claim (if any)	Claiming relaxation as: **MSE (Udyam — Micro/Small)** / **DPIIT Startup** / **Not applicable**. If MSE: state the Udyam category as printed on the certificate (Micro / Small): _____ and the NIC code(s) on the certificate covering IT / software / computer-related services: _____. If Startup: DPIIT Recognition No. & validity: _____. Certificate must be in the name of the bidding entity and enclosed.	_____	_____

Declared true and correct.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____

Particulars	Details
Place	_____
Date	_____
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

D

ANNEXURE D

Financial Capability Statement (CA-certified)

Section 10 — Annexures and Bid Forms

Annexure D — Financial Capability Statement (CA-certified)

Instruction: Complete the figures from audited financial statements and have them certified by a practising Chartered Accountant. Attach the CA certificate, audited balance sheets and profit-and-loss accounts for all three years.

Bidder's legal name: _____ **PAN:** _____ **GSTIN:** _____

Financial Year	Turnover from IT / Software / ERP services (₹ in Lakh)	Total Turnover (₹ in Lakh)	Net Worth at year-end (₹ in Lakh)
FY 2022-23			
FY 2023-24			
FY 2024-25			
Average (3-year)			—
Net worth in latest FY (2024-25) — positive?			**Yes / No:**

> **Note —** A Bidder (including a DPIIT-recognised Startup availing the vintage waiver under Clause 2.2A) that has been in existence for fewer than three completed financial years shall complete only the rows for the financial years since its incorporation and compute the average over those years; CA-certified provisional figures are permitted for a year whose statutory audit is not yet due. Mark inapplicable rows 'N/A — incorporated on _____'.

Chartered Accountant's Certification

I/We certify that the above figures are true and correct as per the audited financial statements of the Bidder examined by me/us.

CA particular	Detail
Name of Chartered Accountant / Firm	
Membership No. / Firm Registration No.	
UDIN	

CA particular	Detail
Signature, seal & date	

> **Mandatory —** The three-year average annual turnover must satisfy the **≥ ₹50 Lakh** threshold (**≥ ₹25 Lakh** for MSEs (Udyam) / DPIIT-recognised Startups claiming relaxation under Clause 2.2A), and net worth must be **positive** in the latest FY, as required by Section 2 and **Annexure C**.

Bidder's confirmation:

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	
Name	
Designation	
Place	
Date	
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

ANNEXURE E

Project Experience / Citation Format

Section 10 — Annexures and Bid Forms

Annexure E — Project Experience / Citation Format

Instruction: Furnish one block per project — up to 6 (up to 4 ERP, ERP-module or campus-automation implementations and up to 2 other institutional software projects for a University, HEI, research or comparable institution, per Rubric T2 of Section 8). Evidence relied on for T2.3 (highest single order value) and T2.4 (sports-sector engagement) is additional to this cap; additional blocks in the same format are permitted. Each citation must be supported by a work order/purchase order AND a client completion/satisfaction certificate. For the standard criterion: at least one project must be in a Government/Public University or HEI, and at least one order value must be ≥ ₹20 Lakh. Bidders claiming the MSE / DPIIT-Startup relaxation (Clause 2.2A) shall cite at least one completed institutional software implementation of any value. Other completed software projects for Universities/HEIs (portals, websites, SIS, e-governance) may also be cited here — they are scored under criterion T2 of Section 8.

Repeat the following block for **each** cited project (Project 1 to Project 6).

Project _____ (1 / 2 / 3 / 4 / 5 / 6)

#	Particulars	Details
1	Name of client / institution	_____
2	Government / Public University / HEI? (Yes/No)	_____
3	Sector (University / Higher Education / Govt / Other)	_____
4	Project title	_____
5	Scope & modules implemented (brief)	_____
6	Solution approach (Custom / COTS / SaaS)	_____
7	Order / contract value (₹)	_____
8	Order value ≥ ₹20 Lakh? (Yes/No)	_____
9	Start date (MM/YYYY)	_____
10	Completion / Go-Live date (MM/YYYY)	_____
11	Current status (Completed / Ongoing / In O&M)	_____
12	Number of users / student records served	_____
13	Client contact — name & designation	_____

#	Particulars	Details
14	Client contact — email & phone	
15	Reference of work order & completion/satisfaction certificate (doc name & page ref)	

> **Reference —** This experience is scored under criterion **T2** of the Technical Evaluation Matrix in Section 8. Citations without both a work order and a client completion/satisfaction certificate may be disregarded.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	
Name	
Designation	
Place	
Date	
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

F

ANNEXURE F

Functional Requirements Compliance Sheet

Section 10 — Annexures and Bid Forms

Annexure F — Functional Requirements Compliance Sheet

Instruction: The Bidder shall respond to EVERY functional requirement listed in Section 4 (Functional Requirements), identified by its `FR-*` ID, without omission. Reproduce all `FR-*` IDs in the same order as Section 4 and complete the compliance code and remarks for each. Do not summarise or group requirements.

Compliance codes to be used in the "Compliance Code" column:

Code	Meaning
FC	Fully Compliant — available out-of-the-box in the proposed product/module as on bid date
CF	Compliant through Configuration — met by standard configuration, no source-code change
CD	Compliant through Customisation/Development — to be delivered by build within project scope
NC	Not Compliant — requirement not met

Format (one row per `FR-*` requirement; complete for all IDs in Section 4):

Req ID	Requirement (as stated in Section 4)	Priority	Compliance Code (FC/CF/CD/NC)	Remarks / Product-module offered
FR-ADM-01				
FR-ADM-02				
FR-…-…				
(continue for every FR- ID in Section 4)*				

> **Important —** Any `FR-*` ID left blank shall be read as "**NC (Not Compliant)**". A response of **CD** must identify the module/component that will deliver the requirement. Overstating compliance (e.g., marking **FC** for a capability shown to be absent during the product demonstration under Section 8) is a material misrepresentation and a ground for disqualification and EMD forfeiture.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	
Name	
Designation	
Place	
Date	
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

G

ANNEXURE G

Technical Requirements Compliance Sheet

Section 10 — Annexures and Bid Forms

Annexure G — Technical Requirements Compliance Sheet

Instruction: The Bidder shall respond to EVERY technical requirement listed in Section 5 (Technical Requirements), identified by its `TR-*` ID, without omission — including architecture, hosting/data-residency, security & compliance (CERT-In, DPDP Act 2023), the SBIePay payment-gateway integration, performance, accessibility and standards. Use the same compliance codes as Annexure F (FC/CF/CD/NC).

Req ID	Requirement (as stated in Section 5)	Compliance Code (FC/CF/CD/NC)	Remarks / How met (product, version, standard)
TR-ARC-01			
TR-SEC-01			
TR-INT-01			
TR-…-…			
(continue for every TR- ID in Section 5)*			

> **Note —** For the **SBIePay** integration requirements, the "Remarks" column shall confirm support for the Aggregator-Hosted model, Double-Verification / Status-Query API, Push-Response, DVP settlement, Refund/Cancellation API, asymmetric-key request-response encryption, TLS 1.2, SHA-256 checksum and no storage of card/SAD data, as specified in Section 5.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

ANNEXURE H

Proposed Team / Key Personnel

Section 10 — Annexures and Bid Forms

Annexure H — Proposed Team / Key Personnel

Instruction: Complete the summary table for all proposed key personnel, then attach a one-page CV for each in the format outlined below. CVs must be signed by the individual and countersigned by the authorised signatory. Role titles correspond to the key-personnel roster in Section 6 (Clause 6.4), which is authoritative. Roles may be combined in one individual where the competencies demonstrably overlap, except that the Project Manager and the QA / Test Lead shall be distinct individuals. MSEs and DPIIT-recognised Startups may propose consultant / contracted specialists for non-core roles, with express disclosure of the engagement basis in the table.

H.1 Key Personnel Summary

#	Role	Name	Highest Qualification	Total Exp (yrs)	Relevant Exp (yrs)	Key Certifications *(optional — not evaluated)*
1	Project Manager — core team, full-time (may also act as Functional Lead)	_____	_____	_____	_____	_____
2	Functional / Implementation Consultant 1 — core team, full-time	_____	_____	_____	_____	_____
3	Functional / Implementation Consultant 2 — core team, full-time	_____	_____	_____	_____	_____
4	Technical / Integration Engineer — core team, full-time (integrations incl. SBIePay; data migration)	_____	_____	_____	_____	_____
5	Solution Architect — named specialist, part-time (min 20%)	_____	_____	_____	_____	_____
6	Security Specialist (Information Security / Data Protection) — named specialist, part-time (min 20%)	_____	_____	_____	_____	_____

#	Role	Name	Highest Qualification	Total Exp (yrs)	Relevant Exp (yrs)	Key Certifications *(optional — not evaluated)*
7	QA / Test Lead — named specialist, part-time (min 20%)	_____	_____	_____	_____	_____
…	*(add rows for other proposed key personnel)*					

> **Note —** The **Training Lead** and **Support Lead** are nominated **after award** under Clause 6.4.3(c) of Section 6 and are **not** to be named in this Annexure at the bid stage.
>
> **Entries in the "Key Certifications" column are optional and are not evaluated.** No individual professional or vendor certification — including PMP, PRINCE2, CISA, CISSP, CEH, ISTQB, TOGAF, ITIL and any OEM or product certification — is required for any role, and the Tender Evaluation Committee shall disregard this column in awarding marks under Rubric T5 of Section 8. A Bidder shall be neither advantaged nor disadvantaged by completing or leaving this column blank.

H.2 One-page CV format (one per key resource)

CV field	Details
Name	_____
Proposed role on this project	_____
Date of birth / nationality	_____
Educational qualifications (degree, institution, year)	_____
Professional certifications (PMP, CISA, CISSP, TOGAF, OEM certs, etc.)	_____
Total years of professional experience	_____
Years of experience relevant to ERP / campus solutions	_____
Employment status with the Bidder (on-rolls since / employee ID)	_____
Key assignments (project, client, role, duration, contribution) — 3 to 5	_____
Languages known	_____

CV field	Details
Declaration of availability for this project (Yes/No; % allocation)	

Particulars	Individual (CV holder)	Authorised Signatory (countersignature)
Signature		
Name		
Date		

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	
Name (in block capitals)	
Designation	
Place	
Date	
Company Seal / Stamp	

> **Reference —** Key personnel are scored under criterion **T5** of the Technical Evaluation Matrix in Section 8. Substitution of key personnel after award shall be governed by Section 6 and Section 9.

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

ANNEXURE I

Financial Bid / Bill of Quantities (BOQ)

Section 10 — Annexures and Bid Forms

Annexure I — Financial Bid / Bill of Quantities (BOQ)

Important — THIS ANNEXURE (I) IS TO BE PLACED IN COVER-2 (FINANCIAL BID) ONLY. IT MUST NOT APPEAR, IN WHOLE OR IN PART, IN COVER-1 OR IN ANY TECHNICAL ANNEXURE. Any disclosure of price in Cover-1 shall render the entire bid liable to summary rejection.

*Instruction: Quote firm, all-inclusive prices in Indian Rupees, exclusive of GST; GST will be paid at actuals and is not counted for evaluation. This Annexure reproduces, and shall be read with, the BOQ format of Clause 7.3 of Section 7. The evaluated bid value for QCBS is the 5-Year Total Cost of Ownership (TCO) = Sub-total Part A (one-time costs) + Sub-total Part B (recurring costs over 5 years) + Evaluated Total Part C (rate card priced on the University's fixed notional quantities). The Bidder shall not add, delete, re-order, re-label or reformat any row or column of this Annexure. Every Part A and Part B cell must be entered; a blank Part A or Part B cell will be read as ₹0.00 and shall bind the Bidder. Every Part C rate must also be entered; a blank Part C rate will be read as ₹0.00 per man-day and shall bind the Bidder. A blank Part D cell means the item is not offered and shall not be read as ₹0.00. Part C is evaluated on the University's fixed notional quantities and IS counted in the evaluated TCO; Part D is quoted for price-discovery only and is NOT counted.***

Bidder's legal name: _____ **Tender Ref:** MBSPSU/PUR/ERP/2026/01

Legend for the "Nature" column: OT = One-time; R = Recurring. The "Years" column indicates the multiplier applied to a recurring unit price (1 for one-time items; 5 for the five-year recurring items).

I.1 Part A — One-Time Costs

Sl	Cost Component	Nature (One-time / Recurring)	Unit / Qty	Unit Price excl. GST (₹)	Years	Total Amount excl. GST (₹)
A.1	Software Licence — perpetual COTS licences, all modules, full user base	One-time (OT)	Lot / 1	_____	1	_____
A.2	Implementation & Customisation — study, SRS/BBP, build, configuration, testing, Go-Live, hypercare	One-time (OT)	Lot / 1	_____	1	_____
A.3	Data Migration — extraction, cleansing, transformation, load, reconciliation	One-time (OT)	Lot / 1	_____	1	_____
A.4	Third-Party Integrations incl. **SBIePay** payment gateway, SMS/e-mail, biometric, DigiLocker/UGC	One-time (OT)	Lot / 1	_____	1	_____

Sl	Cost Component	Nature (One-time / Recurring)	Unit / Qty	Unit Price excl. GST (₹)	Years	Total Amount excl. GST (₹)
A.5	Training — role-based end-user, administrator / train-the-trainer, manuals	One-time (OT)	Lot / 1	_____	1	_____
	Sub-Total Part A — One-Time Costs (OT)					_____

I.2 Part B — Recurring Costs (per year × 5 years, post-Go-Live)

Sl	Cost Component	Nature (One-time / Recurring)	Unit / Qty	Unit Price per year excl. GST (₹)	Years	Total Amount excl. GST (₹)
B.1	Software Subscription / SaaS charge — only if the offer is subscription-based; else ₹0.00	Recurring (R)	Per year	_____	5	_____
B.2	Hosting & Infrastructure — cloud/DC, compute, storage, bandwidth, backup, DR; vendor-managed, else ₹0.00	Recurring (R)	Per year	_____	5	_____
B.3	Operations, Maintenance, Support & AMC — O&M / AMC	Recurring (R)	Per year	_____	5	_____
	Sub-Total Part B — Recurring Costs over 5 years (R)					_____

> **Note —** For Part B, the Bidder shall quote a single firm and fixed **per-year Unit Price** for each recurring line; the same firm annual rate applies uniformly to each of the five (5) post-Go-Live years — no year-on-year escalation is permitted (Clause 7.7 of Section 7). The Total Amount for each recurring line is the Unit Price multiplied by five (5). A Bidder offering a pure SaaS model shall quote its subscription under B.1 and shall not double-count the same charge under B.2 or B.3.

I.3 Part C — Change-Request Rate Card (per man-day, by role — evaluated on notional quantities)

Sl	Role / Resource Category	Nature	Notional Qty (evaluation only)	Unit Price excl. GST (₹ per man-day)	Evaluated Total (₹)
C.1	Project Manager	Evaluated on notional qty	**10** man-days	_____	_____
C.2	Solution / Technical Architect	Evaluated on notional qty	**10** man-days	_____	_____
C.3	Business Analyst / Functional Consultant	Evaluated on notional qty	**25** man-days	_____	_____
C.4	Senior Software Engineer / Developer	Evaluated on notional qty	**30** man-days	_____	_____
C.5	Software Engineer / Developer	Evaluated on notional qty	**40** man-days	_____	_____
C.6	Database Administrator / DBA	Evaluated on notional qty	**10** man-days	_____	_____
C.7	Quality Assurance / Test Engineer	Evaluated on notional qty	**20** man-days	_____	_____
C.8	Trainer / Documentation Specialist	Evaluated on notional qty	**15** man-days	_____	_____
	EVALUATED TOTAL PART C — 160 notional man-days, excl. GST — carried to the Grand Total		**160**		_____

> **Important —** The Part C rate card is **evaluated**. The **notional quantities are fixed by the University solely for financial evaluation**, so that change-request rates are competed rather than quoted freely; they create **no commitment, minimum order or entitlement** whatsoever. Quoting against every role is **mandatory**; a blank rate shall be construed as ₹0.00 per man-day and shall bind the Bidder. Actual drawdown is only against Change Requests approved in writing under the change-control procedure of **Clause 9.13 of Section 9**, and is capped at **10% of the Part A (implementation-phase) contract value per contract year**. Rates are firm and fixed for the Contract term.

I.4 Part D — Phase-2 Optional Items (NOT counted in TCO)

Sl	Phase-2 Optional Item (cross-ref)	Nature	Firm Lump-Sum Price excl. GST (₹)
D.1	Athlete video-analysis — upload, tagging, annotation (**FR-ATH-04**)	Phase-2 Optional	_____
D.2	Tournament live scoring & real-time standings (**FR-TOUR-04**)	Phase-2 Optional	_____
D.3	E-commerce / merchandise storefront with fulfilment & returns (**FR-ECOM-01–03**)	Phase-2 Optional	_____
D.4	Personalised nutrition & meal tracking (**FR-NUT-03**)	Phase-2 Optional	_____
D.5	Full trilingual user interface — Punjabi & Hindi (**FR-GEN-11**)	Phase-2 Optional	_____

> **Note —** Part D prices are firm and fixed lump sums for the Contract term, are quoted in Cover-2 only, and are **NOT counted in the evaluated 5-Year TCO or the financial score**. The University may commission any Part D item within 24 months of Go-Live per §4.1.3 of Section 4, at the quoted price, under the change-control procedure. A blank Part D row means the item is not offered and shall not be read as ₹0.00.

I.5 Grand Total — 5-Year Total Cost of Ownership (TCO)

Ref	Description	Total Amount (₹) — in figures	In words
	Sub-Total Part A — One-Time Costs	_____	_____
	Sub-Total Part B — Recurring Costs (5 years)	_____	_____
	Evaluated Total Part C — Change-Request Rate Card (160 fixed notional man-days)	_____	_____
	GRAND TOTAL — Evaluated 5-Year TCO (Part A + Part B + Evaluated Part C), exclusive of GST	_____	_____

Grand Total (5-Year TCO) in words (Rupees): _____

> **Note —** The **GRAND TOTAL — 5-Year TCO (excl. GST)** — being **Sub-Total Part A + Sub-Total Part B + Evaluated Total Part C**, exclusive of GST and exclusive of Part D — is the single figure used for financial evaluation under Section 8, where the Financial Score `Sf = (Lowest evaluated quote ÷ Bidder's quote) × 100`. It shall be quoted in both **figures and words**. In case of any discrepancy between figures and words, **the amount in words shall prevail**; between a unit rate and a total, **the unit rate shall prevail**.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

J

ANNEXURE J

EMD Details / Bid-Security Declaration

Section 10 — Annexures and Bid Forms

Annexure J — EMD Details / Bid-Security Declaration

Instruction: Complete Part J.1 with the details of the EMD instrument. Bidders claiming exemption as an MSE (valid Udyam — Micro or Small) or DPIIT-recognised Startup under Clause 2.2A of Section 2 shall instead complete and submit the Bid-Security Declaration in Part J.2, together with their valid Udyam / DPIIT certificate.

J.1 EMD / Bid-Security Instrument Details

Earnest Money Deposit (Bid Security) required: **₹96,000 (Rupees Ninety-Six Thousand only)**.

#	Particulars	Details
1	Mode (online transfer / Bank Guarantee from scheduled bank)	_____
2	Amount (₹)	_____
3	Instrument / UTR / BG number	_____
4	Date of instrument	_____
5	Issuing bank & branch	_____
6	Valid up to (must cover bid validity + claim period)	_____
7	Favouring	The Registrar, MBSPSU, Patiala

J.2 Bid-Security Declaration (for MSE / DPIIT-Startup exempt Bidders)

(To be reproduced on the Bidder's letterhead by Bidders claiming exemption in lieu of EMD.)

We, _____ (legal name), holding **Udyam Registration No. (Micro/Small) / DPIIT Startup Recognition No.:** _____ *(strike out whichever is inapplicable)*, hereby submit this Bid-Security Declaration against Tender Reference No. **MBSPSU/PUR/ERP/2026/01**.

Exemption claimed as: **MSE / DPIIT-recognised Startup** (per Clause 2.2A of Section 2).

We understand and accept that, if we:

1. **withdraw, modify or impair** our bid during the period of bid validity (180 days) specified in the Form of Bid Submission, or any extension thereof; or
2. **fail to accept the correction of arithmetical errors** under Clause 8.7.2 of Section 8; or
3. **engage in any corrupt, fraudulent, collusive or coercive practice, or any misrepresentation**, as described in Clause 2.13; or
4. having been declared the successful Bidder, **fail within the stipulated time to accept the Letter of Award, execute the contract agreement, or furnish the Performance Bank Guarantee**;

then we shall be **suspended and declared ineligible** to participate in any tender/bid of MBSPSU for a period of **one (1) year** from the date of such default, and shall be liable to such other action as the University may take under the applicable procurement rules.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

K

ANNEXURE K

Performance Bank Guarantee (PBG) Proforma

Section 10 — Annexures and Bid Forms

Annexure K — Performance Bank Guarantee (PBG) Proforma

Instruction: To be furnished by the successful Bidder within the period stipulated in Section 9, on non-judicial stamp paper of appropriate value, issued by a scheduled commercial bank in India, for an amount equal to 5% of the total contract value, valid for the full contract term plus a three-month claim period. In lieu of a Bank Guarantee, the performance security may be furnished as an account-payee Demand Draft drawn on a scheduled commercial bank in favour of 'The Registrar, The Maharaja Bhupinder Singh Punjab Sports University', payable at Patiala — in which case this proforma is not applicable (refer Clause 9.3 of Section 9). Reproduce the text below on the issuing bank's format.

To,
The Registrar, Maharaja Bhupinder Singh Punjab Sports University (MBSPSU), Patiala.

Bank Guarantee No.: _____ **Date:** _____

WHEREAS _____ (name of the successful Bidder), having its registered office at _____ (hereinafter called "the Contractor"), has been awarded the Contract for the Design, Development and Implementation of an Enterprise Resource Planning (ERP) System vide Letter of Award No. _____ dated _____ against Tender Reference No. **MBSPSU/PUR/ERP/2026/01** (hereinafter called "the Contract");

AND WHEREAS the Contract requires the Contractor to furnish a Performance Bank Guarantee for a sum of ₹_____ (Rupees _____), being **5% (five per cent) of the total contract value**, for the due and faithful performance of the Contract;

NOW THEREFORE, we, _____ (name and address of the Bank), a scheduled commercial bank, do hereby unconditionally and irrevocably undertake to pay to the University, on first written demand and without demur, cavil or protest, and without reference to the Contractor, any sum or sums up to an aggregate of ₹_____, merely on a demand from the University stating that the Contractor has failed to perform any of its obligations under the Contract or has committed a breach thereof. Any such demand shall be conclusive and binding on the Bank as regards the amount due and payable, notwithstanding any dispute between the University and the Contractor.

We further agree that:

1. this Guarantee shall remain in full force and effect from _____ up to and including _____, being the full contract term plus a **three (3) month** claim period, and the University's rights hereunder shall not be affected by any extension of time or variation granted to the Contractor;
2. our liability under this Guarantee shall not exceed ₹_____;
3. this Guarantee shall not be discharged by any change in the constitution of the Bank or of the Contractor; and
4. the University shall be entitled to invoke this Guarantee, in part or in full, at any time before its expiry.

For and on behalf of the issuing Bank

Particulars	Details
Signature of Authorised Bank Official	
Name	
Designation & Employee Code	
Bank & Branch	
Place	
Date	
Bank Seal	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

L

ANNEXURE L

Self-Declaration of Non-Blacklisting / Non-Debarment

Section 10 — Annexures and Bid Forms

Annexure L — Self-Declaration of Non-Blacklisting / Non-Debarment

Instruction: Reproduce on the Bidder's letterhead and, where required by Section 2, on ₹100 non-judicial stamp paper / e-affidavit duly notarised. Sign and stamp by the authorised signatory.

I/We, _____ (legal name of the Bidder), having our registered office at _____, do hereby solemnly affirm and declare, in respect of Tender Reference No. **MBSPSU/PUR/ERP/2026/01**, that as on the date of submission of this bid:

1. we are **not blacklisted, debarred, suspended, or declared ineligible** by any Central Government, State Government, Public Sector Undertaking, University, statutory body, or any public agency in India, for any reason whatsoever;
2. **no proceedings** for blacklisting or debarment are pending against us before any such authority;
3. we have **not been convicted** of any offence involving moral turpitude or economic/financial fraud, nor is any such conviction subsisting against us or any of our directors/partners;
4. no contract awarded to us has been **terminated for default or breach** by any Government/public entity in the last three (3) years, save as expressly disclosed herein; and
5. there is **no vigilance, CBI or other investigation** pending against us that would materially affect our ability to perform the Contract.

We understand that if any of the above declarations is found to be false or misleading, at any stage, the University may reject our bid, forfeit our EMD/PBG, terminate the Contract, and debar us from future participation, without prejudice to any other legal remedy.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
For and on behalf of (legal name of Bidder)	_____
Place	_____
Date	_____

Particulars	Details
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

M

ANNEXURE M

Anti-Corruption, Anti-Collusion & Conflict-of-Interest Declaration

Section 10 — Annexures and Bid Forms

Annexure M — Anti-Corruption, Anti-Collusion & Conflict-of-Interest Declaration

Instruction: Reproduce on the Bidder's letterhead, sign and stamp. This declaration binds the Bidder to ethical conduct throughout the procurement and the contract period.

I/We, _____ (legal name of the Bidder), in respect of Tender Reference No. **MBSPSU/PUR/ERP/2026/01**, hereby declare, undertake and agree that:

1. **No corrupt practice:** we have not offered, given or agreed to give, and shall not offer, give or agree to give, to any official, employee or representative of the University or any other person, any inducement, gift, gratification, commission or bribe, directly or indirectly, in connection with this bid or the resulting Contract.
2. **No collusion / bid-rigging:** we have prepared and submitted this bid **independently**, without any consultation, communication, agreement or arrangement with any other bidder or competitor as to price, content or any restriction on competition; and we have not, directly or indirectly, engaged in bid-rigging, price-fixing or any collusive or anti-competitive practice.
3. **No fraudulent / coercive practice:** we have not misrepresented facts, nor engaged in any fraudulent, coercive, obstructive or undue-influence practice to secure any advantage in this procurement.
4. **Conflict of interest:** we declare that we do **not** have any conflict of interest — financial, personal or professional — with the University, its officers, or the members of the Evaluation Committee, that could improperly influence the evaluation or performance of the Contract; and we shall disclose forthwith any such conflict that may arise. *(If any relationship exists, disclose here: _____.)*
5. **Single bid:** we have submitted **only one** bid against this tender, whether directly or through any associate/affiliate, and we are not participating in any other bid for the same tender.
6. **Consequences:** we accept that any breach of this Declaration shall entitle the University to reject our bid, forfeit our EMD/PBG, terminate the Contract, recover damages, and debar us from future tenders, in addition to any action under applicable law.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name	_____
Designation	_____
For and on behalf of (legal name of Bidder)	_____
Place	_____
Date	_____

Particulars	Details
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

N

ANNEXURE N

Power of Attorney + Manufacturer's Authorisation Form (MAF)

Section 10 — Annexures and Bid Forms

Annexure N — Power of Attorney + Manufacturer's Authorisation Form (MAF)

Instruction: Part N.1 (Power of Attorney) is mandatory for all Bidders and shall be executed on non-judicial stamp paper of appropriate value and duly notarised. Part N.2 (MAF) is to be furnished only where the Bidder proposes an OEM/third-party product under an OEM–SI back-to-back arrangement, on the OEM's letterhead.

N.1 Power of Attorney for Authorised Signatory

Know all persons by these presents that we, _____ (legal name of the Bidder), having our registered office at _____, do hereby constitute, appoint and authorise **Mr./Ms.** _____, son/daughter of _____, presently holding the position of _____ in our organisation, whose specimen signature is attested below, as our true and lawful attorney (the "Authorised Signatory"), to do, in our name and on our behalf, all such acts, deeds and things as are necessary or required in connection with or incidental to the submission of our bid against Tender Reference No. **MBSPSU/PUR/ERP/2026/01**, including but not limited to signing and submitting the bid and all Annexures, operating our registered account on the Punjab e-Procurement Portal (https://eproc.punjab.gov.in) and completing the OTP-authenticated final submission (Clause 2.6A of Section 2), participating in pre-bid meetings, clarifications, negotiations and presentations, and signing and executing the resulting Contract and all documents connected therewith.

We hereby agree to ratify and confirm all acts, deeds and things lawfully done by our said Authorised Signatory pursuant to this Power of Attorney, and the same shall bind us as if done by us.

For _____ (Bidder)

For and on behalf of the Bidder (Executant)

Particulars	Details
Signature of Executant (Board-authorised signatory)	_____
Name	_____
Designation	_____
Board Resolution No. & date	_____
Place	_____
Date	_____

Particulars	Details
Company Seal / Stamp	
Name of the Authorised Signatory (attorney)	
Designation of the Authorised Signatory	
Specimen signature of the Authorised Signatory (attested)	

Attestation	Details
Attested by (Notary — name, registration no., seal & date)	

Particulars	Witness 1	Witness 2
Signature		
Name		
Address		

N.2 Manufacturer's Authorisation Form (MAF) — for OEM-backed bids

(To be reproduced on the OEM's letterhead where a third-party/OEM product is offered.)

To,
The Registrar, MBSPSU, Patiala.

We, _____ (name of the OEM / manufacturer), having our registered office at _____, being the original manufacturer/owner of the product(s) _____ (product name & version), do hereby:

1. **authorise** _____ (name of the Bidder/System Integrator) to offer, quote, supply, implement and support our said product(s) for MBSPSU against Tender Reference No. **MBSPSU/PUR/ERP/2026/01**, under a back-to-back arrangement dated _____;
2. confirm that the said product(s) are **genuine and currently supported (not end-of-life / end-of-support)** during the contract term, and that we shall make available updates, patches and technical support as required;
3. undertake to provide **product support / escalation and, in the event of the Bidder's default, continuity of support** (including, where applicable, source-code escrow per Section 9) so that the University's operations are not disrupted; and
4. confirm that we have authorised **only this Bidder** for this tender for the said product(s).

For and on behalf of _____ (OEM)

Particulars	Details
Signature of Authorised Signatory (OEM)	_____
Name	_____
Designation	_____
Place	_____
Date	_____
OEM Seal / Stamp	

> **Note —** Consortium bidding is **not permitted**. An OEM–SI back-to-back MoU is permitted only where the **primary Bidder is the System Integrator (SI)**, as provided in Section 2.

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

O

ANNEXURE O

Statement of Deviations

Section 10 — Annexures and Bid Forms

Annexure O — Statement of Deviations

Instruction: List every deviation the Bidder takes from the RFP terms, specifications or conditions, with the exact clause reference, the deviation, and its justification. Deviations not listed here shall be deemed withdrawn and the corresponding RFP provision accepted in full. Material deviations may render the bid non-responsive.

#	RFP Section / Clause reference	Page	Deviation taken (as against the RFP requirement)	Justification
1				
2				
3				
…				

Mandatory — Where the Bidder takes **no** deviation, it shall retain this Annexure and enter the single word "**NIL**" across the table, and sign the following declaration: *"We confirm that we accept all terms, conditions and specifications of the RFP in full and take NIL deviations."*

NIL deviations declaration (tick if applicable): ☐ We take **NIL** deviations and accept the RFP in full.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	

Particulars	Details
Name	_____
Designation	_____
For and on behalf of (legal name of Bidder)	_____
Place	_____
Date	_____
Company Seal / Stamp	

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

P

ANNEXURE P

Pre-Bid Query Format

Section 10 — Annexures and Bid Forms

Annexure P — Pre-Bid Query Format

Mandatory — This is the **sole valid format** for pre-bid queries. Queries in any other format may not be entertained (Clause 2.7.2 of Section 2). Submit **one consolidated file** per Bidder in **editable** `.docx` or `.xlsx` to **registrar@mbspsu.ac.in** by **T + 9, 05:00 PM IST**, with the subject line **"Pre-Bid Queries — RFP No. MBSPSU/PUR/ERP/2026/01 — [Name of Bidder]"**. This Annexure is **NOT** to be enclosed in Cover-1 or Cover-2.

To: The Registrar, Maharaja Bhupinder Singh Punjab Sports University, Adjoining Rajiv Gandhi National Law University, Bhadson Road, Patiala – 147006, Punjab

Bidder identification

Particular	To be completed by the Bidder
Name of the Bidder (legal entity)	_____
Registered address	_____
Contact person and designation	_____
E-mail	_____
Mobile	_____
Date of submission	_____

Does the Bidder intend to attend the Pre-Bid Meeting? ☐ Yes ☐ No

If Yes, pre-register by e-mail under Clause 2.7.1 by T + 12, 01:00 PM IST, stating the names, designations and mode of attendance of not more than two representatives. If No, the responses, minutes and any Corrigendum remain binding on the Bidder under Clause 2.7.4.

Is the Bidder claiming MSE (valid Udyam) or DPIIT-recognised Startup status for the relaxations at Clause 2.2A? ☐ Yes ☐ No

If Yes, the relevant certificate is to be enclosed with the bid; no enclosure is required with this Annexure. If No, the standard thresholds apply.

Specimen — how to complete this form

Note — SPECIMEN ONLY. Do not complete these rows. They are printed for guidance and form no part of the Bidder's submission.

#	RFP Section / Clause No.	Page No.	RFP Text as Stated	Query / Clarification Sought / Suggestion
S1	*Clause 2.2 — Pre-Qualification Criteria, read with Annexure C*	*—*	*"Average annual turnover of at least ₹50 Lakh (₹25 Lakh for MSE / DPIIT-recognised Startups) …"*	*Kindly confirm whether the standalone turnover of the bidding entity alone shall be considered, and whether a CA-certified provisional statement is acceptable for FY 2024-25.*
S2	*Section 5 — Hosting, Data Residency & Infrastructure*	*—*	*"Disaster Recovery shall be provisioned in a second cloud region within India; RTO ≤ 24 hours, RPO ≤ 4 hours."*	*Please clarify whether DR in a second Availability Zone of the same Indian region of a MeitY-empanelled CSP is acceptable in lieu of a second region.*

Pre-bid queries — to be completed by the Bidder

One query per row. Quote the RFP text exactly and briefly. Do not include any price, rate or commercial information. Continue on a Continuation Sheet if more than twelve queries are raised.

#	RFP Section / Clause No.	Page No.	RFP Text as Stated	Query / Clarification Sought / Suggestion
1				
2				
3				
4				
5				

#	RFP Section / Clause No.	Page No.	RFP Text as Stated	Query / Clarification Sought / Suggestion
6				
7				
8				
9				
10				
11				
12				

Declaration

Particular	Detail
Signature of Authorised Signatory	_____

Particular	Detail
Name (in block capitals)	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

Annexure P — Continuation Sheet _____ of _____

Name of the Bidder: _____

#	RFP Section / Clause No.	Page No.	RFP Text as Stated	Query / Clarification Sought / Suggestion
13				
14				
15				
16				

#	RFP Section / Clause No.	Page No.	RFP Text as Stated	Query / Clarification Sought / Suggestion
17				
18				
19				
20				
21				
22				
23				
24				

Particular	Detail	Particular	Detail
Initials of Authorised Signatory	_____	Date	_____

TENDER REFERENCE NO. MBSPSU/PUR/ERP/2026/01

Q

ANNEXURE Q

Delivery Approach and Continuity Route Declaration

Section 10 — Annexures and Bid Forms

Annexure Q — Delivery Approach and Continuity Route Declaration

Mandatory — Cover-1. Every Bidder shall complete and enclose this Annexure. A bid that does not declare a delivery approach, or that proposes a hosted / SaaS component without electing a Continuity Route under Clause 9.5.3.4, **does not deliver the uniform continuity end-state at Clause 9.5.6 and shall be rejected as non-responsive** (Clause 9.5.6.2).

Q.1 — Delivery approach proposed *(tick one)*

Approach	Tick
(a) Custom Development — bespoke solution, IP and source code assigned to the University (Clause 9.5.2)	☐
(b) COTS Product Implementation — perpetual enterprise-wide licence plus source-code escrow (Clause 9.5.3.1–9.5.3.3)	☐
(c) Hosted Solution (SaaS / subscription) — **a Continuity Route at Q.2 must also be elected** (Clause 9.5.3.4)	☐
(d) Hybrid — state which components fall under which approach in Q.3	☐

Q.2 — Continuity Route *(complete if the bid includes ANY hosted / SaaS component, whether under (c) or as part of a Hybrid under (d) — tick one)*

Route	Election	What the Bidder undertakes
Route 1 — Escrowed single-tenant deployable build	☐	To place in escrow a single-tenant deployable build (source code with build scripts, deployment artefacts, configuration and data-schema documentation sufficient to build and run the Solution independently), releasable on any event in Clause 9.5.3.3 **including expiry, non-renewal or termination**
Route 2 — Pre-committed perpetual fallback licence	☐	To furnish with this bid a **binding OEM pre-commitment** to grant the University a perpetual, irrevocable, enterprise-wide licence to a functionally equivalent **deployable edition**, installable on University-designated infrastructure, exercisable within **12 months** of expiry, non-renewal or termination, **at no charge beyond the accepted TCO**, that edition also being escrowed

Where Route 2 is elected, the OEM pre-commitment is to be enclosed with this Annexure. Where the bid includes any hosted / SaaS component and neither box is ticked, the bid is non-responsive (Clause 9.5.6.2).

Q.3 — Component-wise statement *(mandatory for a Hybrid bid; otherwise write "Not applicable")*

#	Component / Suite	Approach (Custom / COTS / Hosted)	Continuity Route (Route 1 or Route 2 — required for every Hosted component)	Remarks
1				
2				
3				
4				
5				
6				
7				
8				

Q.4 — Declaration

We confirm that, whichever approach is proposed above, our offer delivers **in full** the uniform licence, intellectual-property and continuity end-state at **Clause 9.5.6** — namely that on and after expiry or termination of the Contract for any reason the University may continue running the Solution indefinitely without further payment, holds or may obtain buildable code, may have the Solution maintained, modified and enhanced by **any vendor of its choosing**, and retains absolute ownership of and export rights over all its data. We acknowledge that any qualification of this position renders our bid non-responsive.

For and on behalf of the Bidder

Particulars	Details
Signature of Authorised Signatory	_____
Name (in block capitals)	_____
Designation	_____
Place	_____
Date	_____
Company Seal / Stamp	

> **Reference —** These Annexures are to be read with Section 2 (Instructions to Bidders), Section 7 (Pricing and Payment Terms), Section 8 (Evaluation Criteria) and Section 9 (Terms and Conditions). In the event of any inconsistency between an Annexure format and the body of the RFP, the **body of the RFP and any issued Corrigendum shall prevail**.

End of Section 10 — Annexures and Bid Forms.